



Submission on Agriculture to the Guyana Sugar Corporation Commission of Inquiry.

OCTOBER 2015

Harold B Davis
COMMISSIONERS |

John A Piggott

Guyana Sugar Industry Commission of Inquiry- Agriculture Report

Table of Contents

Sections

Executive Summary	Page 2
1-Introduction	Page 5
2-Overview and Current Situation	Page 6
3-Recommended Actions and Medium Term Prospects	Page 22
4-Cane Farming Issues	Page 31
5-Progress and Prospects for Mechanisation	Page 39
6-Agriculture Procurement	Page 47
7-Research and Development	Page 50
8-Weather and Climate Change	Page 55
9- Environmental Matters	Page 61
10-Opportunities for Diversification	Page 63
11-Observations and Recommendations	Page 68
Bibliography	
Appendix 1 – Industry Production Trends	
Appendix 2 – Agriculture Operating Costs and Capital	
Appendix 3 Cane Farming Records	
Appendix 4 – Agriculture Policy Matters	
Appendix 5 - Historical Rainfall and Climate	
Appendix 6 – Tillage, Planting and Machine Utilization	

Guyana Sugar Industry Commission of Inquiry – Report Agriculture

The Guyana Sugar Industry is in a significant decision making phase, following successive years of financial loss, that have required subventions from the Central Government in 2013, 2014 and 2015. These subventions have been used mainly to service debt and do not reflect any long term investment in the Business. The Agriculture Report is a component of a wide-ranging Commission of Inquiry appointed by the Central Government and tasked with identifying the root causes underlying the Industry's poor performance, and to chart a way forward towards a more financially viable and sustainable future. The Agriculture sub-Committee comprises Dr. Harold Davis and Mr. John Piggott, both of whom have had extensive experience within the sugar industry of Guyana and several other countries.

Executive Summary

Agriculture is the basis of production for the sugar industry and the single largest contributor to operating cost. The Industry has faltered financially over the past 7 years and this can be attributed largely to poor yields. The members of the Agriculture sub-Committee of the Commission visited and held in-depth discussions with each operating estate and Service Department during the initial 8 weeks of the Study. This reports reflects views from the estates' technical and managerial staff as much as the views and experience of the writers.

Average cane yields have plummeted since 2009 on most estates. Blairmont and Albion estates have maintained some respectability in production, but even on these estates, the performance has been well below their potential. Poor production has been highlighted by unacceptable plant cane yields on each estate. Ratoon maintenance and productivity has also been poor. Several contributing factors were identified for these yields, **most of which could be linked to estates and support staff falling short of fundamental agronomic and agriculture management standards**, including quality of tillage, timing of planting, shortages of inputs, chronic weed competition and in too many cases, harvesting canes out of season. In 2015, over 5000 hectares of First Crop canes had yet to receive fertiliser in August. While the fertilizer has since been delivered, there will be an undetermined impact on the 2016 production.

Skeldon Estate has been a special consideration throughout the exercise. This estate received considerably more inputs in agriculture and factory than other estates but has not produced at the projected efficiencies since the commissioning of the new mill. From the Agriculture perspective, cane quality has continued to be compromised by a high percentage of over age cane in each crop compounded by delays in crop start leading to machine harvesting in wet and consequent high percentages of extraneous matter and muds delivered to the factory. These conditions combined with delays in delivery to the mill have resulted in consistently very poor sugar recoveries since the new mill was commissioned in 2009. Skeldon has experienced relatively low average rainfall since 2008, but the external drainage for the expanded cultivation is inadequate. A new 340 TPM drainage pump has been sited on the banks of the Canje that will substantively address this issue. The NDIA is expected to complete the required

6Km canal to link the pump to the estate's drainage system at Sookram's Cross. This project is sufficiently important for Guysuco to consider undertaking the drain on its own, should financial approval from the NDIA be subject to delays.



The report offers guidance on the management and technical interventions that will promote better yields that if achieved would result in improvements in sustainable productivity by 2020.

Unfortunately, projected costs of production for agriculture will probably not be low enough for the industry to be profitable at prices projected for the European Market where the bulk of Guyana's sugar is sold after 2017. The recommendation from this report is that the Industry needs to add other revenue streams in addition to raw sugar. Since all factories will have to cope with increasing volumes of machine loaded or harvested canes, it is inevitable that changes in Boiler plant will be required. It is proposed that the opportunity be taken to design the operations for export of seasonal power. A suggestion is also made to consider the manufacture of food grade plantation white sugars by a new technology involving ultrafiltration.

Mechanization is increasingly important to sugarcane production in Guyana. Although progress has been made with the development and operation of equipment and results indicate the potential for significant cost efficiencies not only in harvesting but for crop agronomy and maintenance. It has been a disappointment that although the Bell Loader has been accepted as the preferred mode of operation by cane harvesters, who are more productive with less physical effort, the operation has not resulted a cost incentive to the Industry. It is proposed here that the Union work with Guysuco to eliminate additional payment for "obstacles and other extras" from the cut and stack operation that already includes a built in compensation of 15% for these factors.

Mechanization of sugarcane harvesting has been accompanied by several challenges to agriculture management and operations in the factories that receive significant volumes of these canes. The importance of achieving Kill to Mill intervals of under 24 hrs is imperative for billeted canes if unacceptable cane quality is to be avoided. Agriculture Managers have not recognised the opportunity mechanized harvesting offers for early release of punts from harvesting fronts and recycling from mill reception that can contribute to efficient utilization of punts and also significantly reduce Kill to Mill intervals.

The importance of Cane Farming to the future production for the sugar industry is considered. It is however noted that apart from the new farmers at Skeldon, the Berbice region has seen an overall decline in cane farming. The prospects for developing these as independent operators will have to be encouraged. It is also proposed that the concept of a “farmer owned” cane supply for Wales Estate should be studied as a production model for that estate.

The importance of system development and continued innovation is recognized for mechanization and in research and development. The appointment of a mechanization Coordinator is proposed. This individual would be provided with the resources to focus on addressing critical issues such as land levelling, haul-out improvements, irrigation and cane delivery management for a mechanized industry. It is also recognised that Research and Development has a vital role to play in maintaining agronomic standards, resolving problems as they arise, and finding technical solutions to potential areas of concern. The support of senior management will be vital if the effectiveness of this unit is to be preserved.

This report is presented in 11 sections. The first 4 relate to the current production issues on Estates and Farmers cultivations, including cost and medium term productivity Improvements. Sections 5 to 7 address the development issues mechanization, research and also avenues for improving procurement. Strategies for managing current and predicted climatic events and the environment are discussed in sections 8 and 9. Opportunities for Diversification are addressed in Section 10. Section 11 summarizes significant findings and recommendations.

1-Introduction

1.1 This assignment is being undertaken at a time when the state owned Guyana Sugar Corporation appears to be at a significant crossroads, having for the past 3 years been forced to seek subventions rising from G\$5B in 2013 to G\$12B in 2015, from the Government to cover an increasing debt that has accumulated to G\$82B, a figure that is anticipated to increase, particularly when the sugar supply contracts between the ACP countries and the EU refineries are re –negotiated after 2017.

1.2 -Agriculture is the largest component of operating expenditure in the sugarcane industry and also provides the largest opportunity for cost efficiencies and improved productivity. The Agriculture team members have visited each estate and have paid attention to critical areas of the Guysuco and Cane Farmers cultivations in order to assess growing conditions, infrastructure and the effectiveness of operations, including the coordination with the Factories. In depth discussions were held with Estates management and with and with the Central Technical staff of the Agriculture Services, Research, Factory Operations and Materials Control Depts. A special session was also held with the Engineering and Operational staff who have been active in mechanization development. Guysuco has also provided detailed records of historical and current production, environment and cost data which were reviewed to show the way forward.

1.3 -The majority of these visits were made together with the Factory team members and both teams were thus enabled to develop a common perspective of the critical issues as they relate to cane supply, quality and operational issues in both field and factory.

2 –Overview and Current Situation

2.1 Sugarcane and sugar production from the Guyana Industry have experienced significant changes over the 16 years from 2000 to 2015. Production from the first seven years of the period reflected the efforts made across the Industry to operate within the set guidelines of an Agriculture Improvement Programme that was formally launched in 2000 to improve relatively stagnated productivity of the 1990s. This programme was developed by and coordinated by the Central Agriculture Depts and entailed investments in prime movers and implements and emphasized strict adherence to guidelines for tillage and to established agronomic standards that were common during the 1970's.

2.2 These efforts produced consistent satisfactory cane of the order of 3.4 million tonnes annually. It appeared perfectly reasonable to anticipate in excess of 4 million tonnes of cane after the expanded cultivation from Skeldon contributed to production. In 2005, intense prolonged rainfall and severe floods, particularly in Demerara disrupted agriculture operations for 2005 and 2006. An apparent recovery in agriculture performance in 2007 proved to be short lived as heavy rainfall in 2008 again disrupted operations and resulted in depressed yields. Consistently poor productivity since 2010 cannot be simply attributed solely to adverse weather, as average growing conditions have prevailed since 2009. It is apparent that the operating principles established for the preceding years may have been quickly forgotten.

2.3 The Board and Management of Guysuco had recognised the continuing problems and have published reviews of the Industry Strategic Plan in 2009, 2013 and 2014. These reviews have recognized the deficiencies in the Industry performance and its technical and operating shortcomings, all of which are evident today. Unfortunately none of these plans have resulted in tangible measures to retrieve the production decline.

2.4 Records and accounts suggest that planting outside of the recommended windows, non-adherence to tillage standards and poor timing of inputs have been frequent. **The imposition of ill-advised and technically unsound directives on agriculture practices were also a disturbing and unfortunate feature particularly over the past three years.**

2.5 Difficulties with cash availability and credit have been experienced since the delay in commissioning the new Skeldon Factory and the continuing high expenditure on the project. Agriculture was significantly affected. In 2012, with the objective of reducing costs, the rates of fertiliser N was reduced by 25% and the percentage of the cheaper source urea was also increased. The ratio of ammonium sulphate to urea in the recommended fertiliser mix is effective in minimising volatilisation of N from urea. At the same time potash fertiliser was curtailed. **The subsequent year 2013, cane and sugar yields were the lowest since 1992.**

2.6 The reductions in fertiliser were not justified by the available technical information nor the Research Dept. The fertiliser regime was eventually restored after June of 2013. Although the reduction in production should not be attributed to this sole cause, the measure is symptomatic

of a willingness to compromise agriculture standards. Previous history in the Guyana Industry (1970s) has demonstrated the need for caution before making adjustments to fertiliser policy.

2.7 The very poor production year in 2013 was followed by panic bringing forward of canes in 2014 to produce more acceptable gross results. This was short term thinking at best that did not address the fundamental causes of the poor yield that have since continued. The practice of Bringing Forward immature canes to the preceding crop, not only sacrifices the potential production that may have resulted from harvesting those canes at maturity, it also risks compromising the subsequent development from those areas by exposure of the young developing stools to end of season rainfall and in some cases having adverse physiological impacts for subsequent crops. This practice appears to have become institutionalised as a standard practice over the past 5 years.

Year	First Crop- Ha	Second Crop- Ha	Total - Ha
2011	43	2678	2721
2012	741	1913	2654
2013	948	1718	2663
2014	2032	3237	5269
2015	1813	0 budgeted	1813 to date

Table 2.1 – Progressive Brought Forward Areas 2011 -2015

2.8 Successive seasons of poor performance have forced the Industry to seek subventions from the Central Government, that have been made at increasing levels in 2013, 2014 and 2015 when \$12B were approved. Despite this, unavailability of cash during the production periods has led to shortages of fertilizers and agrichemicals at critical crop development stages.

Year	2002	2004	2005	2007	2008	2012	2013	2014
Ha Estates.	41295	45213	41907	39758	44262	43616	40676	45302
Ha Farms	4852	5081	4871	4317	4035	5387	5287	5667
T cane Estates	3322456	3394983	2738299	2861253	2554288	2405853	2163889	2513741
T cane Farms	348806	325303	264723	237927	212281	303517	294836	307074
TC/Ha Estates	80.5	75.1	65.3	72.0	57.7	55.2	53.2	55.5
TC/TS Estates	11.2	11.37	12.11	11.55	12.16	12.23	12.98	12.95
TC/Ha Farms	71.9	67.7	54.4	55.1	52.6	56.3	55.8	54.2
T Sugar	331052	325303	246047	266481	226270	218007	186755	216361
TC/TS Farms	12.6	12.85	13.24	12.6	13.1	14.22	14.89	14.53
Rainfall (mm)	1773	1990	2484	2554	3002	1827	1807	1802

Table 2.2 Cane and Sugar production Trends 2002 to 2014

2.9 These disturbing trends have suggested that without planned subsidies from the Government, this industry would be unable to sustain itself. This is clearly unacceptable for an Industry that has been developed as a business required to produce profitable returns for its shareholders.

2.10 All estates have recorded lower efficiencies and poor output during the past 5 years. It is apparent that these impacts have been generally more severe on the Demerara Estates than in

Berbice. However any conclusion on the inherent weakness in Demerara relative to Berbice, should be viewed with caution, as preference is commonly given to the Berbice region when there is competition for resources.

2.11 –The actual causative factors to the present poor agriculture productivity are several and complex, but the observations and data outlined are symptomatic of poor or weak management. Senior agriculture personnel and managers have admitted being aware of the pitfalls of some of the measures that were implemented but themselves felt helpless to voice their concerns in the environment in which they were operating. The team has observed and taken note of the following:

- High turnover of managerial and supervisory staff for various reasons including migration
- Managers in many instances are transferred between estates before coming to grips with issues on their present estate
- High and increasing frequency of Bringing Forward canes (including the 2015 First Crop) rising to over 5000ha in 2014
- Low yield of plant cycle cane, inclusive of flood fallowed fields (Appendix 6) attributed to poor land preparation and late season planting
- Plant fields established from older (3R) cycles seed cane is increasing
- Increasing occurrence of renewed planting older, less productive varieties e.g. DB 66113 and D7761
- Short, weakly developed stalks in several areas including early cycles. This can be to some extent attributed to soil compaction resulting from traffic of cane loaders and trailer over fields in damp conditions.
- Steep decline of cane yield between cycles
- Approximately 30% -35% improvements in tillage and planting achievement from 2009 to 2011 produced disappointing results in subsequent seasons' productivity, calling into question the quality of output attained. The GuySuCo tillage fleet is insufficient in numbers and serviceable condition to achieve a 20% replant programme in an typical Crop period. The important criteria should therefore be on the quality of tillage rather than the quantity of land disturbed and planted. Evidence of poor crop husbandry and maintenance as indicated by large gaps in field and prolific weed growth.
- Labour shortages in crop maintenance e.g. weeding, chemical weed control
- Poor condition of estate infrastructure including access roads, bridges, canals and revetment. This has to a large extent impacted adversely on the condition of the punt fleet, that although presently adequate for all estates does incur high expenditure for repairs and re-bottoming.
- Lack of discipline in field labour, evidenced by prolonged disputes and excessive demands for “ extras” payment

- Unwillingness of some agricultural management to display initiative in principled settling of disputes
- Staff not forthcoming with responses to queries raised on issues

2.12 All of these direct and indirect factors will probably pose a challenge in the present environment to precisely replicate the efforts of the 2000 to 2005 period that had placed emphasis on intensive field assessment and timely interventions. The increasing absence of institutional memory through migration of experienced Field practitioners will be a significant factor, which will have to be addressed by a robust training and mentoring programme.

2.13 Estates would also have to work towards increasing the extent of mechanisation for as many crop maintenance operations as possible. In this regard, the awareness of the capacity and limitations of field machinery is very limited among many agriculture senior and supervisory staff. This deficiency in non-specialist staff can be addressed by formal and informal training by the Agriculture Engineers and other staff members who have been exposed to machine operation and management. There has been a noticeable improvement in urgency and commitment displayed in the Industry since the commencement of the team’s visits and interactions with Estates’ and Head Office Staff. We would like to hope that our advice and encouragement may have contributed to the current improvements in performance now being observed in the Industry.

2.14.-The changes in relative productivity in cane for individual estates are summarised in the discussion following




Fig 2.1 Cycle Productivity Trends Skeldon - 2000 to 2015

2.14.-1 Initial impressions of the Skeldon cultivation were that the most of the current crop appeared to be in an active growth phase, although stalks are relatively short in relation to the stated physiological ages of the areas inspected. A high proportion of the Skeldon crop (inclusive of the farmers' canes) will be harvested as carry over acreage. The estate's plan is to harvest all the available canes for delivery to the mill that is reportedly in a sounder condition for continuous operation. The Estate proposes to commence rehabilitation of the cultivation with attention on establishing field gradients and in field drainage with the land levelling equipment. It is also expected the external drain linking the estate from Sookram's Cross to the new Manarabisi/ No.66 Creek drainage pump at the Canje River would be completed before the end of 2015. It is anticipated that this measure should impact on the responsiveness of the Skeldon cultivation to drier conditions. The No.66 drain is included among proposals for funding and execution by the National Drainage and Irrigation Authority (NDIA). However it will be critical to the Skeldon Agriculture Operations and as such Guysuco should be prepared to finance its construction should the project evaluation process experience delays.

2.14.2 Concern must be expressed over the significant decline in plant and ratoon cycle yields since 2008. Average Plant cycle yield for the years 2006 to 2008 was 91 tons cane per ha that declined to under 70 tons cane per ha after 2009. Relative ratoon productivities were similarly affected.

2.14.3 For successive seasons, Skeldon has experienced difficulty in harvesting its standing crop because of restricted access to fields and forced harvesting in wet soil conditions. The principal cause was the unreliability of the Factory that influenced late starts. The result has been increasing areas of over-age canes in both the estate' and farmers' cultivations.

2.14.4 200 hectares of Plant canes in the Estate Expansion Blocks 10 and 13 were ploughed in during 2011 and 2012, after being judged as un-harvestable. During the same period a further 50 ha of first ratoon canes were also abandoned from Manarabisi Block 2. Previously In 2009, a flash flood in the Manarabisi section forced the loss of 209 ha. This incident was a consequence of the drainage canal to the No 19 pump not being completed.

2.14.5 Traffic of heavy machines over wet soils has contributed to soil compaction and stool losses that are reflected in the pronounced yield decline and depressed yields

2.14.6 These problems have as much to do with the inadequate drainage capacity and the fundamental error made at the onset of the expansion programme in which only cursory attention was paid to land levelling for establishing the required field gradients. This was further compounded in the succeeding tillage and replant cycles in which tillage could only be conducted well past the recommended cut-off periods with the risks of early exposure to heavy rainfall.

2.14.7 Discussions with estate personnel did not provide reassurance that they have fully appreciated the consequences of the late season planting, these may be symptoms of a combination of inexperience and unclear decision making over the recent years. The present plan to utilise the precision levelling equipment is a welcome change, but these good intentions will not produce the desired results unless the operators and supervisory personnel are adequately trained in the pre levelling surveys and operating plans for each field.




Fig 2.2 Cycle Productivity Trends Albion 2000 to 2015

2. 14.8 Cane yield decline since 2008 has also been recorded at Albion Estate. Average cane yield has also not been stable over the same period. This estate has recorded a very high occurrence of repeated “bringing forward” of canes since 2009. The impact on productivity is reflected in a 15% decline in yield from the 1st to the 2nd ratoon cycle. The colour of several areas of the latter harvested sections of the 2015 first crop, appear pale. These areas much of which were brought forward had not received fertilizers.

2.14.9 Albion has been a relatively stable Estate but still suffered tremendously in the First Crop 2013 with a production of 10,127 tonnes sugar primarily from a combination of Bringing Forward Canes and a fertiliser adjustment programme in 2012.

Table 2.3 ALBION First Crop 2002 to 2015

Year	ha	sugar	cane	tc/ha	ts/h	tc/ts
2002	3,240.0	25,314	255,634	78.90	7.81	10.10
2003	3,327.9	24,789	227,267	68.29	7.45	9.17
2004	3,256.5	23,077	241,092	74.03	7.09	10.45
2005	3,476.7	16,206	191,730	55.15	4.66	11.83
2006	3,485.1	21,849	231,005	66.28	6.27	10.57
2007	3,427.0	24,370	244,738	71.41	7.11	10.04
2008	4,297.6	26,299	297,319	69.18	6.12	11.31
2009	3,413.4	17,140	182,577	53.49	5.02	10.65
2010	3,285.6	17,785	183,868	55.96	5.41	10.34
2011	4,315.8	27,738	324,112	75.10	6.43	11.68
2012	3,420.4	16,140	172,598	50.46	4.72	10.69
2013	2,513.4	10,127	118,501	47.15	4.03	11.70
2014	3,040.8	16,918	184,343	60.62	5.56	10.90
2015	3,376.8	21,386	225,823	66.87	6.33	10.56

2.14.10 Starting with Carry Over canes from 1039 Ha in Second Crop 2010 to the First Crop of 2011 followed by Bringing Forward 747 Ha in the Second Crop of 2011 triggered a serious juggling of the crop ratios. An attempt to balance the First Crop 2012 had 208 Ha Brought forward from the Second Crop 2012 but that was further aggravated by another 794 Ha being brought forward from the First Crop 2013.

2.14.11 The 2013 First Crop only harvested 2,513 Ha producing an all-time low of only 10,127 tonnes sugar even though 174 Ha was Brought Forward from the Second Crop of 2013.

2.14.12 The 2014 First Crop had another 547 Ha brought forward from the Second Crop 2014 which was intended to re-balance the two crops in any one year.

2.14.13. The “policy” of Bringing Forward cane into the First Crop 2015 from the Second Crop in 2015 was restricted to only 118 Ha and there is no budgeted Brought Forward cane to be made in the Second Crop 2015.

2.14.14. Notwithstanding these deficiencies, the cultivation at Albion appears closer to what might be expected in a managed situation than most of the other estates. This has been reflected in the early results of the 2015 Second Crop in cane production and factory recoveries. Albion has managed to maintain its access roads in a reasonable state of repair, permitting staff to access the cultivation and make time crop maintenance decisions. It is our view that this estate should be in a position to return to a productive and relatively cost

effective operation with modest capital intervention and provision of timely agronomic inputs and equipment spares.

2.14.15. The Agriculture Department of Albion is at present, capable of satisfying the factory demand but only with the use of Bell Loaders. The Estate is not confident that the status quo will remain, as labour availability is a critical issue each year. A programme of continuing field conversion to prepare for mechanised crop maintenance and eventually harvesting is a sensible measure.




Fig 2.3 Cycle Productivity Trends Rose Hall 2000 to 2015

2.14.16 Rose Hall Estate like Albion has maintained its cultivation access roads in fair condition. However the cane yields in all cycles have declined significantly particularly after 2011, when Plant Cycle average yield fell from 81 tons cane per Ha to just 65 tons cane per Ha. The prime ratoon cycle yields were also averaged only 60 tonnes of cane per ha falling to 50 tons cane per ha at the third ratoon cycle. The estate has acknowledged that these conditions reflect poor supervision of tillage and crop establishment. Large sections of the developing 2015 First Crop appeared weak. It was claimed that this may have been due to non-application of fertilizers.

2.14.17 There are signs of modest improvements in crop development for the Second Crop of 2015. Rose Hall has reported an increased labour turnout and recruitment for the early part of the crop. It remains to be seen whether this would be sustained.

Table 2.4 Rose Hall First Crop 2002 to 2015

Year	ha	sugar	cane	tc/ha	ts/h	tc/ts
2002	2121.0	14,782	150,077	70.76	6.97	10.15
2003	2440.8	16,637	161,387	66.12	6.82	9.70
2004	2402.6	14,693	181,202	75.42	6.12	12.33
2005	2541.8	14,231	181,859	71.55	5.60	12.78
2006	2554.2	13,509	159,932	62.62	5.29	11.84
2007	2329.4	13,800	160,494	68.90	5.92	11.63
2008	2690.3	14,047	167,086	62.11	5.22	11.89
2009	2230.7	10,347	123,984	55.58	4.64	11.98
2010	1846.0	7,201	88,425	47.90	3.90	12.28
2011	2466.6	13,702	182,621	74.04	5.56	13.33
2012	2177.7	9,896	122,888	56.43	4.54	12.42
2013	1812.4	5,082	72,791	40.16	2.80	14.32
2014	2090.0	8,599	111,575	53.39	4.11	12.98
2015	2018.5	8,290	113,171	56.07	4.11	13.65

2.14.18 Rose Hall Estate suffered similar First Crop imbalances from Brought Forward cane between 2011 and 2015 with the largest manipulation in First Crop 2014 having 446 Ha. This was followed by 459 Ha in the Second Crop 2014 totalling 905 Ha for the year 2014.

2.14-19 Rose Hall has produced for several seasons poorer cane quality than the neighbouring estates Albion and Blairmont. The reasons for this are not obvious. The maturity sample data do appear consistent with mature canes of the varieties under test. However the factory has continued to experience steam generation problems that have at various times been attributed to muds in Bell Loaded cane. The team's visit to the Roy Hanoman cultivation where the Bell Loader fleet was at work, did indeed see evidence that the cutting was not done to the required standard, with poor stacking and significant quantities of extraneous matter being picked up with bundles. This could only be attributed to poor supervision that is disappointing given that Rose Hall has had the longest Industry experience with the Bell Loaders.




Fig 2.4 Cycle Productivity Trends Blairmont 2000 to 2015

2.14.20 Blairmont Estate has for several years recorded the highest cane yields in Guysuco. Average cane yields of early cycle cane have declined significantly since 2011. The estate has however maintained its older cycle yields at around 60 tons cane per ha. This would indicate that while work standards in ratoon maintenance on the estate have been maintained, the underlying causes for reduced Plant cane productivity will have to be further investigated. One possible cause that cannot be ignored is the impact of forced tillage, particularly during years of 2010 to 2011, when the emphasis appears to have been on attaining the new acreage at all cost. To verify this would require on site investigations that would not be possible during the time permitted by this Inquiry.

2.14.21 Access to the cultivation was good permitting staff the opportunity to effectively undertake crop maintenance tasks. Some sections of the 2015 First Crop were beginning to display obvious symptoms of lack of fertiliser. This was more apparent in the blocks that had been Brought Forward during the preceding crop's campaign.

Table 2.5 Blairmont First Crop 2002 to 2015

Year	ha	sugar	cane	tc/ha	ts/h	tc/ts
2002	2,112.0	17,629	181,451	85.91	8.35	10.29
2003	2,296.6	19,024	186,220	81.09	8.28	9.79
2004	2,316.2	19,511	204,039	88.09	8.42	10.46
2005	2,191.5	15,280	180,513	82.37	6.97	11.81
2006	2,313.1	13,361	157,559	68.12	5.78	11.79
2007	2,038.9	14,474	153,689	75.38	7.10	10.62
2008	2,527.2	15,040	193,678	76.64	5.95	12.88
2009	2,102.6	12,882	135,111	64.26	6.13	10.49
2010	2,058.1	12,111	122,425	59.48	5.88	10.11
2011	2,396.7	17,611	205,787	85.86	7.35	11.69
2012	2,216.2	12,801	149,134	67.29	5.78	11.65
2013	1,802.9	6,286	82,726	45.88	3.49	13.16
2014	1,887.2	10,776	121,048	64.14	5.71	11.23
2015	2,164.3	13,681	160,249	74.04	6.32	11.71

2.14.22 Blairmont did not escape the consequences of Bringing Forward of cane and the fertiliser adjustment programme of 2012 as can be seen in the 6,286 tonnes production in the First Crop 2013. The reduced harvested area of 1,803 Ha and the extremely low 46 tonnes cane per hectare contributed to that record low production.

2.14.23 Blairmont has sufficient cane harvesters for a cut and stack operation. A visit to the operations in field to observe the operation, highlighted that the cane was properly stacked and that the operators were achieving good results despite the damp soil conditions. The tyres on the Bell Loaders were not the recommended Trelborg that Guysuco now considers very expensive. The fitted tyres though of low ground pressure specification will not match the Trelborgs that can be deflated to 6psi in wet conditions. Under the conditions of the operation the repeated passes of the Bells were leaving depression on the soil surface. These, it is anticipated will self-repair once the soil dries but there is a measurable risk for soil compaction that will contribute to reduced ratoon vigour.



Bell Loader on damp soil

2.14.24 Like Albion, it would be prudent to prepare for the eventual necessity for more dependence on machines in other areas of operation.




Fig 2.5 Cycle Productivity Enmore 2000 to 2015




Fig 2.6 Cycle Productivity La Bonne Intention 2000 to 2015

2.14.25 -The East Demerara cultivation comprising the Enmore and LBI Estates is still in transition towards being integrated into a single operating unit, following the closure of the LBI factory. This has been an area of the coast where labour availability has been problematic for several years. Yield decline across cycles has been chronic, more so in LBI. Both sections are dependent on machine loading and the management has reported that the acquisition of two Case 8800 Combine Harvesters in 2014 enabled East Demerara to take off its entire crop for the first time since 2010. East Demerara has some of the better contoured “broad bed” converted fields in the Industry, having commenced their conversion programmes around 2000



Harvested Broad Bed



Weedy canal and field

2.14.26. Unfortunately, it is difficult to enter any section of the cultivation without gaining the impression of neglect and that staff are either not visiting or are not making the effort to maintain sanitation. The cultivation is threatened by the spread of the *Antidesma ghesaembilla* shrub and guinea grass, both of which will have to be subjected to an aggressive campaign with an eradication objective. It is fortunate that Enmore has recently been able to recruit persons to weed control and spray gangs, both of which were under strength for several seasons.

Table 2.6 ENMORE & LBI Cultivations First Crop 2002 to 2015

EHP	ha	sugar	cane	tc/ha	ts/h	tc/ts	LBI	ha	sugar	cane	tc/ha	ts/h	tc/ts
2002	1,519.0	10,683	126,284	83.14	7.03	11.82	2002	1,933.1	12,615	149,368	77.27	6.53	11.84
2003	1,711.2	10,809	109,189	63.81	6.32	10.10	2003	1,980.8	11,480	122,996	62.09	5.80	10.71
2004	1,745.3	12,619	123,708	70.88	7.23	9.80	2004	2,142.3	12,546	145,943	68.12	5.86	11.63
2005	1,092.7	5,344	63,679	58.28	4.89	11.92	2005	1,538.0	5,346	66,541	43.26	3.48	12.45
2006	1,250.7	7,666	78,935	63.11	6.13	10.30	2006	1,301.0	6,307	70,494	54.18	4.85	11.18
2007	1,630.4	12,078	121,539	74.55	7.41	10.06	2007	1,309.0	7,647	82,735	63.20	5.84	10.82
2008	1,645.0	9,377	95,545	58.08	5.70	10.19	2008	1,566.3	7,596	83,310	53.19	4.85	10.97
2009	1,569.2	9,731	101,163	64.47	6.20	10.40	2009	1,544.0	5,903	70,178	45.45	3.82	11.89
2010	1,560.3	7,810	79,781	51.13	5.01	10.21	2010	1,573.6	7,858	84,361	53.61	4.99	10.74
2011	2,011.4	9,435	137,515	68.37	4.69	14.57	2011	1,043.4	3,673	58,923	56.47	3.52	16.04
2012	1,297.8	6,116	72,760	56.06	4.71	11.90	2012	761.6	2,262	30,097	39.52	2.97	13.30
2013	1,348.8	3,565	60,013	44.49	2.64	16.83	2013	1,035.9	2,607	44,566	43.02	2.52	17.09
2014	2,306.5	8,734	113,552	49.23	3.79	13.00	2014	1,622.4	5,278	71,159	43.86	3.25	13.48
2015	1,598.8	7,164	88,169	55.15	4.48	12.31	2015	970.3	3,148	38,450	39.63	3.24	12.21

2.14.27 East Demerara like the Berbice Estates followed a similar decline in production in the First Crop of 2013. The two estates then brought forward 1824 Ha in the Second Crop 2014 which produced 5880 tonnes sugar. Adding the relatively small 107 tonnes from the 2014 First Crop, that Brought Forward total of 5987 tonnes sugar out of the East Demerara production of

30,933 tonnes sugar is a significant 19%. This high percentage of brought forward sugar production must have contributed to the lower First Crop 2015 Estates' production of 10,312 tonnes which included 909 tonnes of sugar from 252 Ha of cane Brought Forward from Second Crop 2015. Since 2011 both Enmore and LBI had been unable to harvest the crop area and had consistently carried over approximately 1500 ha annually. This would also have contributed to the estates' low productivity and also poor recoveries each year until 2013. No Estate has a budget for any Brought Forward cane in the Second Crop 2015 and barring any unforeseen adverse conditions ought to be achieved.

2.14.28 The East Demerara senior staff have morale issues, having in the past year dismissed a group of workers who were found guilty of dumping fertilizers instead of performing their task. These persons were reinstated on the instruction of Senior Management. This is a dangerous precedent as it undermines the management on the ground and has led to feelings of insecurity over their authority. There is also the possibility that similar incidents and other poor work practices will continue on this estate, unless management is given the firm support required.

2.14.29 Accessibility within the cultivation is restricted and this has probably contributed to the proliferation of aquatic vegetation within the canals. A mechanical weed cleaner has been constructed and introduced and is reported to be coping with this problem.




Fig 2.7 Cycle Productivity Wales 2000 to 2015

2.14.30 Wales Estate has also reported very steep productivity drop between successive cycles, particularly since 2008. These effects are compounded by an intractable infestation by

Tanner grass. Apart from the weed infestation, there is also growing evidence of rodent incursions that is linked to prolific weed growth and poor sanitation in the fields.

2.14.31 The weed problems at this estate did not develop overnight and is evident from the successive years of poor productivity over which alarms appear not to have been raised. The Wales Management Accounts reveal very high expenditure on repeated applications of herbicide that seemingly are not effective. Large sections of the estate appear to have been abandoned. These include the Eccles and Powell’s Polder sections that are known to comprise some of the most productive soils on the estate. The Wales area accountability record does not list any area as either Temporary (TAB) or permanently abandoned. However 421 ha or 12.5% of the estate cultivation was identified as Untilled Out of Cane, this was an increase of 122 ha since December 2014 (Appendix 6)



Rodent Damage



Tanner Grass Infestation

2.14.3 The Weeds Agronomist is supporting the Estate with its efforts and the Management has also initiated an investigation into whether the large quantities of herbicide issued from the Chemical Weed Control Bond are actually being used in the Estate Cultivation. Farmers’ plots within the cultivation do not appear to be as seriously affected.




Fig 2.8 Cycle Productivity Uitvlugt 2000 to 2015

2. 14.33 Uitvlugt Estate has also reported very poor average yields across all cycles since 2011. This estate has also recorded a sharp exodus of field labour and has been making serious efforts

to prepare for mechanization for which a project document from the Caribbean Development Bank is in circulation. The risk to this project is the high rainfall in Uitvlugt.

2.14.34 Analysis of the distribution of rainfall on the estate (Section 8) suggests that a significant input from mechanised harvesting would have to be planned around a crop duration not exceeding 24 weeks.

2.14.35 Cane yield in sections of the cultivation are compromised by significant infestation with the noxious weed Tanner grass and also *Antidesma ghesaembrilla*. The Weeds Agronomist is working with the estate on an eradication strategy for these weeds. Uitvlugt has embarked on a field conversion programme to a machine adaptable layout from their English cambered bed fields. The cane growth in these blocks has been very satisfactory in comparison with the other sections of the estate that are characterised by large gaps and dense weed growth.

2.14.36 Notwithstanding, Uitvlugt has persisted with the practice of Bringing Forward sections of its cultivation every production season. This practice is not consistent with any attempt at improving the cultivation.

2.14.37 In 2104 the estate leased 1496 ha of its cultivation to Farmers, 284 ha have been developed It is intended that this “new” farmers’ cultivation will be machine adaptable. After the release of this land, the estate still has 676 ha or 14.6 of the reduced cultivation out of cane.

3. Recommended Actions and Medium Term Prospects

3.1 Sugar estates are currently on a very restricted expenditure regime. Productivity will however only improve by judicious expenditure on areas that can reduce constraints. The availability of fertilizers at the appropriate times is an essential and first measure that should be guaranteed. The same consideration applies to agrichemicals, specifically herbicides. It is advisable to have the requisite supply of these materials, available for the commencement of each forthcoming crop.

3.2 This planning measure would ensure that the first steps in agronomic management are not compromised. Estates' fertiliser bonds were designed with the capacity to store and supply stock for each crop. The Industry's traditional suppliers have been more than willing to hold consignment stock of agrichemicals once tenders have been approved.

3.3 Having ensured the availability to the fundamental inputs, estates would be well advised to adhere as closely as is practical to the established operational guidelines for sugarcane. The following measures should be addressed as priority areas:

1. Field Workshops to work towards 100% availability in optimal working condition of all prime movers, tillage implements, ditchers, excavators, cane loaders, harvesters and associated equipment, and crop maintenance equipment.
2. Conduct regular equipment assessment to effectively plan maintenance and spares requirements and where necessary determine obsolescence and programme replacement.
3. Negotiate for consignment stores of essential equipment spares with agricultural machinery suppliers.
4. Plan and adhere to determined maintenance schedules for estate roads and civil infrastructure, including sluices, drainage pumps and water management structures
5. Update and re-issue the Guysuco Agriculture Operations Manual as a technical reference and for training.
6. Continuous training in all agriculture practices for staff and workers, including mentoring by more experienced persons.
7. Tillage to be conducted only at soil moisture and friability range established as suitable for specific soils and individual operations.
8. Planting to cease by established "cut off" dates March 31st for the First Crop and November 15th for the Second Crop, unless determined by environmental conditions in which case appropriate advice would be provided from the Centre.
9. Re-establish effective primary, secondary and commercial seed cane nursery programmes on all estates.
10. Seed cane to be drawn only from certified commercial seed fields in accordance with individual estate variety development programme agreed with the Breeding and Selection Unit of the Agriculture Research Centre (ARC).

11. Cultivation status reports projected daily work programme to be discussed by Field supervisory and senior staff each afternoon.
12. Crop surveillance including surveys and nutrition monitoring (foliar and soil sampling) to guide agriculture planning and actions, that would include as appropriate members of the Central Technical Staff.
13. Development and Implementation of CANEPRO Cultivation Management support System with the Information Systems Department (ISD).

3.4 In addition to the above listed general measures, the follows interventions will be immediately critical to specific estates. These include:

- (a) The completion of the 6.4 km main drain linking Sookram's Cross to the Manarabisi/No66 Pump station at the Canje River.
- (b) Laser levelling of graded Ridge and Furrow and Broad bed fields at Skeldon and East Demerara that are scheduled for rehabilitation.
- (c) Eradication programme for Guinea grass and *Antidesma ghesaembilla* at East Demerara.
- (d) Eradication programme for Tanner Grass at Wales.
- (e) Rodent control at Wales.
- (f) Eradication Programme for Tanner Grass and *Antidesma ghesaembilla* at Uitvlugt.
- (g) Conversion programme to machine adaptable layouts for Albion, Rose Hall, Blaimont and Uitvlugt estate.

3.5 The practice of flood fallow would be utilised to the greatest extent that is practical on fields with responsive soils. The benefits of the practice on eliminating seed banks of noxious weeds and for control of pests and pathogens are well established. Flood fallow also promotes structure development and relieves subsoil compaction in some clay soils. Unfortunately increasing labour shortages for the more manual operations, point to the increasing role of semi-mechanized and mechanized planting. Flood fallow is not a practical option for either operation as the soil is required to be dry.

3.6 On fields that have been converted to machine adaptable layouts, alternative fallow methods such as legume fallow would be practised when required i.e. land settlement after conversion, to manage, pests, weeds and soil pathogens or for topsoil improvement.

3.7 The Guysuco Estates and Agriculture Dept have identified Capital requirements for 2016 to 2020 of G\$21B or US\$102M. Of this sum G\$ 13.9B or US\$ 68.1M (Appendix 2) should be spent between 2016 to 2018, to restore and secure estates at a satisfactory operating condition. The expenditure is distributed among Civil Works - \$15.5; Accessibilty and Cane Transport \$15.5M, Mechanisation \$21.8M, Tillage Equipment\$4.7M and Drainage and Irrigation requirements \$4.4M. Based on the information that only critical requirements can be funded, we have identified projects valued at G\$5.5B or US\$ 26.1M highlighted in table 3.1 as critical. It is recognised that the reduced investment will impact on the attainment of performance and

production targets, and unless the full investment is made, estates will remain vulnerable to increased operational costs.

CRITICAL AGRICULTURE CAPITAL ITEMS						
ESTATE	Description	AGRIC CAPITAL G\$M				TOTAL US \$
		2016	2017	2018	TOTAL	
Skeldon	ACCESSIBILITY & CANE TRANSPORT	54.0	150.0	150.0	354.0	1,678,050
	CIVIL STRUCTURES	75.6	118.0	118.0	311.6	1,519,800
	DRAINAGE & IRRIGATION	0	20.0	20.0	40.0	195,120
	MECHANIZATION	35	153.8	153.8	342.6	1,671,300
	TILLAGE & PLANTING	0	17.9	17.9	35.8	174,498
TOTAL	SKELDON	164.6	459.7	459.7	1,084.0	5,238,768
ALBION	ACCESSIBILITY & CANE TRANSPORT	34.8	100.0	100.0	234.8	1,072,220
	CIVIL STRUCTURES	78.0	150.0	150.0	378.0	1,843,854
	MECHANIZATION	20.3	70.0	70.0	160.3	781,553
	TILLAGE & PLANTING	0	15.5	15.5	31.0	151,002
TOTAL	ALBION	133.1	335.5	335.5	804.1	3,848,704
ROSE HALL	ACCESSIBILITY & CANE TRANSPORT	48.8	50.0	50.0	138.8	677,160
	CIVIL STRUCTURES	48.7	120.0	120.0	288.7	1,408,300
	DRAINAGE & IRRIGATION	19.9	0	0	19.9	97,100
	MECHANIZATION	25.7	65.0	65.0	155.7	759,710
	TILLAGE & PLANTING	0	18.9	18.9	37.8	184,470
TOTAL	ROSE HALL	143.1	253.9	253.9	650.9	3,126,790
Blairmont	ACCESSIBILITY & CANE TRANSPORT	35.8	60.0	60.0	145.8	711,160
Blairmont	CIVIL STRUCTURES	36.3	85.0	85.0	206.3	1,006,280
Blairmont	MECHANIZATION	58.3	100.0	100.0	258.3	1,260,000
Blairmont	TILLAGE & PLANTING	0	16.5	26.5	33.0	161,000
TOTAL	Blairmont	130.4	261.5	261.5	653.4	3,138,490
East Demerara	ACCESSIBILITY & CANE TRANSPORT	49.5	60.0	60.0	159.5	778,140
	CIVIL STRUCTURES	28.2	50.0	50.0	128.2	625,440

	DRAINAGE & IRRIGATION	0	0	0	0	0
	MECHANIZATION	24.0	153.7	80	257.7	1,257,300
	TILLAGE & PLANTING	0	19.0	19.0	38.0	185,280
TOTAL	East Demerara	101.7	282.7	209.0	593.4	2,846,210
Wales	ACCESSIBILITY & CANE TRANSPORT	10.0	26.5	26.5	53.0	258,500
Wales	CIVIL STRUCTURES	17.2	20.0	20.0	57.2	279,100
Wales	DRAINAGE & IRRIGATION	0	0	0	0	0
Wales	MECHANIZATION	0	0	0	0	0
WALES	TILLAGE & PLANTING	11.7	25.0	25.0	61.7	300,800
TOTAL	WALES	38.7	71.5	71.5	181.7	838,450
Uitvlugt	ACCESSIBILITY & CANE TRANSPORT	28.8	35.0	35.0	88.8	433,260
	CIVIL STRUCTURES	24.1	30.0	30.0	84.1	410,000
	DRAINAGE & IRRIGATION	0	0	0	0	0
	MECHANIZATION	0	1.8	14.0	15.8	77,000
	TILLAGE & PLANTING	0	14.7	14.0	28.7	140,000
TOTAL	Uitvlugt	52.9	81.5	93.0	227.4	1,060,310
CDB Equipment	Uitvlugt, Albion, Rose Hall					6,900,000
INDUSTRY TOTAL					5,609.5	26,097,722

Table 3.1 Recommended Essential Agriculture Capital

3.8 The areas of critical investment are directed primarily to Infrastructure, cane transport, improving staff access to the cultivation, securing the progress of Mechanised Operations at Skeldon, East Demerara and layout conversion at Albion, Rose Hall and Blairmont. We have also recognised that the CDB has approved a soft loan of \$12.0M for the mechanisation support to Albion, Rose Hall and Uitvlugt, \$6.9M of this loan is directed to harvesting and levelling equipment. We recommended that this offer should be taken advantage of.

3.9 On the assumption that these Capital inputs are made and that there are no restrictions to timely supply of fertilizers and herbicides, production projections were developed for the period 2015 to 2020. These are summarised in Tables 3.2 to 3.4

Estate	Estate Ha	Estate Cane	Estate sugar	Estate TC/Ha	Farm Ha	Farm cane (T)	Farm sugar	Farm TC/Ha	Sugar (T)
Skeldon	8040	459365	30361	57.1	2408	127444	8455	52.8	38816
Albion	8965	589026	53692	65.7	119	6480	518	51.4	54352
R. Hall	6305	363793	27149	57.7	647	39513	3041	61.1	30189
Blairmont	5732	402878	35872	70.3	-	-	-	-	35872
Enmore	4356	230388	17999	52.9	119	4773	367	40	18366
LBI	2699	127785	9906	47.4	82	3640	270	44.3	10175
Wales	2717	131222	10498	48.3	2126	117987	9290	55.5	19788
Uitvlugt	3933	174702	13659	44.4	285	24208	1847	85	15506
Industry	42745	2479158	199136	58.0	5786	325538	23929	56.3	223064

Table 3.2 Estimated Cane and Sugar Production 2015

Estate	Estate Ha	Estate Cane (T)	Estate sugar	Estate TC/Ha	Farm Ha	Farm Cane (T)	Farm sugar	Farm TC/Ha	Sugar (T)
Skeldon	8582	526135	40472	61.3	2408	130032	9632	54	50104
Albion	9002	622672	59302	69.2	150	8550	684	57	59986
R. Hall	6314	383699	29976	60.8	680	43160	3243	62	33220
Blairmont	5493	397688	38237	72.4	-	-	-	-	38237
Enmore	4472	252956	20076	56.6	119	6562	513	55	20588
LBI	2699	141720	11248	52.5	81	3240	249	40	14433
Wales	2833	166957	13464	57.9	2220	136400	10740	62	24204
Uitvlugt	3933	199815	15858	50.8	800	57600	4751	72	20430
Industry	43378	2691622	228624	62.1	6438	384544	29633	62.1	258266

Table 3.3 Estimated Cane and Sugar Production 2017

Estate	Estate Ha	Estate Cane	Estate Sugar	Estate TC/Ha	Farm Ha	Farm Cane	Farm Sugar	Farm TC/ha	Sugar (T)
Skeldon	8532	626008	49683	73.4	2800	156800	12062	56	61745
Albion	9002	679488	65970	75.5	200	11600	928	58	66898
R. Hall	6314	437245	34702	69.3	680	40120	3134	59	37836
Blairmont	5493	419895	40375	76.4	-	-	-	-	40375
Enmore	4472	307102	24766	68.7	95	5320	409	56	25182
LBI	2699	178720	14184	66.2	81	3240	249	40	14433
Wales	2915	201050	16214	69.0	2470	165470	13029	67	29243
Uitvlugt	3984	233953	18867	58.7	1000	72000	5806	72	24874
Industry	43411	3083461	264631	71.0	7326	454550	35755	62.1	300386

Table 3.4 Estimated Cane and Sugar Production 2020

3.10. It is forecast that the Industry cane production by incremental steps would attain to the level of 3.5M tonnes by 2020. Sugar output is projected at around 300,000 tonnes. On the assumption that these production indicators are met by 2020, it is expected that investments in critical areas would be increased with emphasis on cost saving and efficiency measures.


3.11 At the projected production levels in 2020 it is to be noted that the cane supply to Uitvlugt will only last 21 operating weeks while Wales would have 26 weeks of cane, as

opposed to typical crop budgets of 32 weeks. This observation supports the opportunity for expanding the contributions of private cane farmers to the Uitvlugt factory. The Enmore factory on the other hand, would have canes available for 33 weeks at present milling rates. Since it is anticipated that approximately 40% of the Enmore factory canes would be derived from combine harvesting, the Enmore milling rate could be increased to 120 tonnes cane per hour to complete the crop in an efficient 27 week period.

3.12 The attainment of these production objectives should be closely monitored on individual estates that would be considered as separate cost centres. Estates Managers and their teams would be held accountable for attainment of the progressive productivity goals. **It is recognised that there are limitations of experience within Estates that will require support and operational guidance from a strong Central Technical Team. In this regard, it is recommended that a Head of Agriculture be appointed at the top Executive level i.e. Director. This individual would hold ultimate accountability for the Agriculture programme objectives and with his team of senior technical personnel provide the necessary leadership in adaption to change that the envisaged programmes will require.**

3.13 Most of the operating units on the estates would function effectively with the current management structure. Since the 1990's there have been several attempts to change the Field senior staff structure and functions only to return to roles that have been consistent since the 1980's. In effect there have been changes in names but not substantive function.

3.14 With the increasing importance of mechanization in agricultural operations, the opportunity should be taken to recruit Mechanical Engineering graduates into the technical operating streams of the Estates. On estates with a high level of Mechanization, the following modified structure is proposed.



3.15 This structure would simplify the current Field structure to two senior managers reporting to the Agriculture Manager. The Engineering Manager would be an experienced Agriculture Engineer and would through his reports hold responsibility for both combine harvesting and machined loading and cane transport, as well as for tillage and maintenance of the estates' infrastructure. The Crop Manager's responsibilities would be similar those of the current Crop

Production Managers. They would also be required to be conversant with the application of machines to crop management such as plantings, application of fertilizers and agrichemicals and cultivation. Most modern agriculture and agronomy training programmes are structured around machine use and operation.

3.16 Maintaining the same guidelines for inputs and investment, production is projected to attain 3.8M tonnes of cane and 326,000 tonnes of sugar by 2025. This should be regarded as indicative of “steady state” production, with similar output levels forecast to 2030. These production estimates are consistent with those independently developed by Guysuco for the same period. The additional investments of US\$1.1M (each year) in 2016 and 2017 for tillage machines and implements would enable the annual achievement of at least 20% quality land preparation and planting from 2017. These measures would accelerate the attainment of a 3.5M tonnes of cane to 2019 and a steady state production of 3.8M tonnes of cane by 2022. It is our recommendation that the tenders for these additional equipment be prepared as a priority before the end of 2015. The projected agriculture cost summary data for Production year 2020 are highlighted in Table 3.5. Details together with those of Production Years 2014, 2017, 2025 are included in Appendix 2

Table 3.5 Summary of Industry Agriculture Costs 2020

Agric Units	Skeldon	Albion	Rose Hall	Blairmont	Enmore	LBI	Wales	Uitvlugt	Industry
Harvest Hectares	8,582	9,002	6,314	5,493	4,472	2,699	2,915	3,894	43,461
ESTATE HECTARES	8,903	9,616	6,689	5,808	4,693	2,988	3,356	4,500	46,553

Tonnes Cane Estate	626,008	679,488	427,245	419,895	307,102	178,720	201,050	233,953	3,073,481
--------------------	---------	---------	---------	---------	---------	---------	---------	---------	------------------

Tonnes Cane per Ha	73	75	68	76	69	66	69	59	71
--------------------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------

Tonnes Estate Sugar	49,683	65,970	37,055	40,375	24,766	14,184	16,214	18,867	267,114
Tonnes farmers Sugar	12,063	926	3,134	-	416	249	13,020	5,806	35,613
TOTAL TONNES SUGAR	61,745	66,896	40,189	40,375	25,182	14,433	29,234	24,673	302,727

Ha Tilled	1,780	1,925	1,355	1,162	940	600	672	900	9,334
Ha Planted	1,780	1,925	1,355	1,162	940	600	672	900	9,334

G\$ per Tonne cane	\$8,193	\$7,104	\$8,253	\$6,793	\$7,966	\$8,426	\$14,017	\$11,111	\$8,388
--------------------	---------	---------	---------	---------	---------	---------	----------	----------	----------------

G\$ per Tonne Sugar	\$83,067	\$72,157	\$87,738	\$72,518	\$97,145	\$104,336	\$96,397	\$105,356	\$85,158
---------------------	----------	----------	----------	----------	----------	-----------	----------	-----------	-----------------

G\$ per Ha	\$576,127	\$501,959	\$527,191	\$504,112	\$521,258	\$503,978	\$839,683	\$577,654	\$553,776
------------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	------------------

US¢ / lb sugar	20¢	17¢	21¢	18¢	23¢	25¢	23¢	25¢	21¢

3.17 The unit cost data highlight that Field production costs across the Guyana Sugar Industry though significantly improved from 27 US¢ per pound, reported in the 2014 accounts, will remain high. The major cost components are harvesting, crop maintenance, and overheads. In developing these estimates, it was recognised that integration of the agriculture units of LBI and Enmore into a single unit is still incomplete. It is anticipated in the projections that this process would be completed before 2017. This immediate impact on field operations will be the elimination of duplication of the Workshop, and stores as well as rationalisation of the tillage, harvesting and crop husbandry sub departments into single units. This measure would result in a 33% reduction of Field Management cost.

3.18 The data also indicate that this business would not be viable if the income is based solely on raw sugar and molasses exports even for the lower priced producers, Albion and Blairmont, particularly if sales are dominated by prices pegged to the World Market. Once Factory and Administrative costs are added to the field costs, only those two estates would appear to be close to a breakeven position.

3.19 For the Guyana sugar Industry to prosper even under efficient management in the future, it is readily apparent that other income earning streams will have to be added. The most stable prospect with constant demand will be power. While it is unfortunate that the experience with Cogeneration at the Skeldon factory has not been encouraging, there are possibilities for power export from the smaller mills during the production seasons. The investment would require at the onset changes to existing obsolete boiler plant and other equipment to enhance the efficiency of dealing with mechanically loaded canes. This was the approach initially followed by Mauritius (Lau, Kong Win Chang and Guinness, 2003) before power evolved as the principal income stream for that Industry. In Guyana's case the introduction of hydropower as the country base load would be compatible with power generation from bagasse during the dry season when output from the dams is reduced. The availability of second hand 45 and 68 bar boiler plant from closed mills in Brazil and Hawaii would seem to be "low hanging fruit" if this approach is pursued.

3.20 Another interesting possibility is the production of refined sugar quality plantation white sugar in a raw factory, using ultrafiltration technology (Chou et al, 2003). This process should at least be investigated as it seems to offer opportunities for access to the food grade white sugar market within the region at a lower investment and energy consumption cost than a conventional refinery.

3.21 These potential projects will require significant investment. These sums cannot be generated within the Industry at this time, nor is the possibility of these coming from the

State's reserves likely. This implies that the rational way forward would be to seek private investment into this industry.

3.22 There are two other areas of interest that have emerged from the cost data examination, the first is the lower harvesting cost on the estates that have significant combine harvesting. This offers a significant incentive to pursue and refine mechanization to impact on a wider range of agriculture operations. The introduction of machines to load hand cut canes has gained wide acceptance by cane harvesters as it is less onerous and can offer greater rewards than the traditional "cut and load". The practice unfortunately, has not had a significant impact on reducing cost. **It is recommended that Guysuco's management engage the support of the Union and work towards an agreement in which the added costs for "obstacles and extras" could be removed from consideration in Machine (Bell) loaded canes.**

3.23 The cost for Field Management at Skeldon and Wales includes cane purchases that are incurred while maintaining a complete Agriculture establishment. Wales high cost for production of cane is not reflected in the estate's "cost per pound of sugar" that has a favourable benefit from low priced farmers' sugar.

3.24 A detailed study in the first instance should be conducted to examine the impact on cost by supplying all of Wales cane requirements from farmers. At present, approximately 50% of the cane is from this source. This of course suggests the possibility of operating by the Belize Industry Model. The study will have to determine the true costs of "farmers" production at Wales. This study should also explore the option of a single production entity in West Demerara., supplied mainly by independent cane farmers. A number of cane farmers and other persons in West Demerara have already expressed interest in expanding involvement with cane farming to approximately 5,000 hectares. These applications should be carefully vetted in order to ascertain the support these individuals would require to successfully manage larger areas. (Appendix 3)

4 Cane Farming Issues

4.1 The National Cane Farming Committee Act Chapter 69:04 of the Laws of Guyana prepared a formal contract between the Cane Farmer and the Sugar Factories referred to as the “manufacturer”.

4.2 The Guyana Sugar Corporation Inc. now has the responsibility and functions of the “manufacturer” as detailed in the NCFC Act and has maintained that relationship with the Cane Farmers in accordance with the Act.

4.3 Traditionally Cane Farmers have produced 10% of Annual Sugar Production from the early 1970s with gradual increases up to 13% and a peak of 15% when the Estate Production was affected in 1977 as a result of Industrial unrest.

Table 4.1 Industry Sugar Production

Year	Estate	Farmers	Total	%
1974	298,140	39,464	337,604	12%
1975	261,943	36,818	298,761	12%
1976	294,596	35,479	330,075	11%
1977	205,582	35,726	241,307	15%
1978	285,179	35,258	323,437	12%

4.4 Cane Farmers’ annual production of over 30,000 tonnes of sugar was consistent during the years 1971 to 1983 and then declined rapidly to under 20,000 tonnes for nine years followed by a resurgence which has settled to just over 20,000 tonnes representing 10% of the current Industry production.

Table 4.2 Industry Sugar Production

Year	Estate	Farmers	Total	%
2010	196,158	24,660	220,818	11%
2011	212,244	24,261	236,505	10%
2012	196,665	21,343	218,007	10%
2013	166,723	19,797	186,520	11%
2014	195,225	21,133	216,358	10%

4.5 Wales Estate, as an example, depends heavily on Cane Farmers to meet its production targets when 10,000 tonnes Farmers’ Sugar represented 30% of the production in the early 1970s while today that same 10,000 tonnes is 50% of Wales’ total.

Table 4.3 Wales Sugar Production

Year	Estate	Farmers	Total	%
2010	11,538	10,149	21,687	47%
2011	11,079	10,880	21,959	50%
2012	9,967	9,286	19,254	48%
2013	12,742	10,004	22,746	44%
2014	9,457	9,441	18,898	50%
2015	10,214	11,009	21,223	52% Act 1st Crop + 2nd Crop Budget

4.6 This historical and current 10,000 tonnes sugar production from the Wales Cane Farmers is unlikely to go much higher although some Cane Farmers have already been offered and have started to grow their own cane on Wales Estate Temporary Abandoned Lands.

4.7 There is an assumption that a Cane Farmer will produce higher tonnages of Cane per hectare and of a better quality than the Estate, an assumption which is not unreasonable at this time since the 2014 Wales Estate productivity is at an all-time low of 44 TC/Ha while the Farmers have maintained a cane yield of 55 TC/Ha over several years.

4.8 Wales Cane Farmers should be able to increase their Tonnes Cane per Hectare from its present 55 TC/Ha to 65 TC/Ha which will in the long term provide the Factory with 146,000 tonnes cane capable of producing 11,230 tonnes sugar at 13 TC/TS.

4.9 This matches a similar initiative at Uitvlugt Estate where Cane Farmers have been allocated Temporary Abandoned Blocks in the Cultivation for the purpose of growing their own cane. Uitvlugt Estate Factory services its own cultivation as well as that of Leonora after the Leonora Factory was closed in 1982. Both Uitvlugt and Leonora Factories were supplied by Cane Farmers between 1964 to 1988, with a peak production of 15,053 tonnes in 1979.

4.10 Since the commissioning of the new Skeldon Factory in 2009, there has been renewed emphasis on Skeldon Cane Farmers to supply cane to produce 36,000 tonnes sugar annually, representing 33% of the rated capacity of the new 110,000 tonne Factory.

4.11 This Skeldon Cane Farming initiative was significantly different from previous efforts in that it required a completely different approach geared towards mechanized field operations from planting to harvesting.

4.12 The challenges for mechanized field operations were no different from those evolving on the Estate cultivations starting with specific field layouts and precise land preparation of new lands with its appropriate levelling and gradients for drainage.

4.13 Unfortunately many “shortcuts” were adopted and there was no real attempt to establish levels and gradients compatible with mechanized operations.

4.14 The traditional Cane Farmers at Skeldon in the 1970s consisted of relatively small units in the form of 2 Cooperatives and 2 Individuals totally about 300 Hectares. They were consistently more efficient than the Estate producing 2,500 tonnes sugar which was a respectable 9% of the Estate production.

4.15 The last time traditional Skeldon Farmers produced over 2000 tonnes sugar was 1985 and then it vacillated between 1,300 to 1,800 tonnes until 2004.

Table 4.4 Skeldon Sugar Production

Year	Estate	Farmers	Total	%
2000	33,656	1,444	35,100	4%
2001	34,719	1,575	36,924	4%
2002	37,162	1,435	38,957	3.6% [Record Production]
2003	31,917	1,353	33,280	4%
2004	35,119	1,397	36,516	3.80%

4.16 In 2005 original Skeldon Cane Farmers only produced 962 tonnes sugar further declining to 599, 497 and 778 tonnes in 2006, 2007 and 2008 respectively.

4.17 Since the New Skeldon Cane Farming expansion started in 2008/2009 there has been a rapid production increase of Cane Farmers’ Production. The Cane Farming Cultivation expansion was accompanied by the Estate also expanding in lands adjoining the original 4955 hectare cultivation.

Table 4.5 Expansion of Skeldon Estate & Farmers Hectares

		ESTATE Ha	FARMERS Ha
	Prior to SSMP	4955	306.6
EXPANSION	2009	2838.7	1336.2
	2010	766.2	831.1
	2011	289.3	285.1
	2012	0	180.3
	2013	53.4	163.4
	2014	0	0
	2015	0	0
TOTAL Expansion		3947.6	2796.1
Total Cultivation: Old + Exp		8902.6	3102.7
To Be Brought in Cane		737.4	1883.9

4.18 This expansion of cultivated land resulted in adjustments in the Sugar Production ratios between the Estate and Cane Farmer from 4% to 24% without increasing total production which is yet to reach the 38,000 tonnes produced in 2002.

Table 4.6 Skeldon Sugar Production

Year	Estate	Farmers	Total	%
2009	22,718	3,009	25,727	12%
2010	25,127	8,123	33,250	24%
2011	21,417	7,993	29,410	27%
2012	25,134	8,130	33,264	24%
2013	19,223	6,321	25,544	24%
2014	28,897	6,993	35,890	19%
2015	30,360	8,454	38,814	22% [Actual First Crop & Budgeted Second Crop]
2002	37,162	1,435	38,957	3.6% [Record Production]

4.19 This significant reduction in Estate sugar production from the record 38,957 tonnes in 2002 to under 30,000 tonnes in spite of the additional 3,900 hectares put under cane is a result of a combination of lower Cane Yields from 88 Tonnes Cane per Hectare to 55 TC/Ha and lower quality Canes from 11 Tonnes Cane per Tonne Sugar to 16 TC/TS.

Table 4.7 Skeldon Cane Farmers Production Summary 1999 to 2014

Year	Hectares	Sugar	Cane	TC/Ha	TS/Ha	TC/TS
1,999	302.0	1,678	22,530	74.60	5.56	13.43
2,000	310.0	1,444	20,086	64.79	4.66	13.91
2,001	304.0	1,575	22,871	75.23	5.18	14.52
2,002	298.0	1,435	21,752	72.99	4.82	15.16
2,003	305.2	1,363	20,763	68.03	4.47	15.23
2,004	304.8	1,397	23,073	75.70	4.58	16.52
2,005	290.2	962	17,683	60.93	3.31	18.38
2,006	215.6	599	10,004	46.40	2.78	16.70
2,007	115.2	497	8,479	73.60	4.31	17.06
2,008	176.5	777	11,930	67.59	4.40	15.35
2,009	690.2	3,009	56,556	81.94	4.36	18.80
2,010	1,438.2	8,123	136,669	95.03	5.65	16.82
2,011	2,119.6	7,993	150,732	71.11	3.77	18.86
2,012	2,416.7	8,132	140,781	58.25	3.36	17.31
2,013	2,119.4	6,312	118,613	55.97	2.98	18.79
2,014	2,376.7	6,993	117,511	49.44	2.94	16.80

4.20 These fundamental issues affected the Skeldon Cane Farmers in no small way as the figures in Table 4.7 above show.

4.21 The lower quality Canes was a direct of:-

- Cane being harvested well beyond their Peak Maturity
- Excessive Burning to Grinding Intervals
- Questionable Factory Performance

4.22 The less than satisfactory performance of the Cane Farmers' Cultivation led to several letters referring to the manner in which the Cane Quality parameters were administered in the Factory. Without going into the tedious exercise of a Financial Analysis of each Cane Farmer it was shown that the Skeldon Cane Farmers were paid substantial sums at the end of each year's transactions.

Table 4.8 Total Amount Paid to Skeldon Farmers for the Last Five Years

	2009	2010	2011 G\$	2012	2013	2014
Total Gross Owed to the Farmers for the Year for Canes Supplied	248,698,334	545,540,863	736,696,381	824,232,859	716,752,094	535,045,551
Less Expenses deducted	113,172,523	164,765,919	253,798,952	222,443,339	152,348,102	162,317,667
Net Paid to the Farmers for the Year for Canes Supplied	135,525,811	380,774,944	482,897,429	601,789,520	564,403,992	372,727,884
% of income deducted for expenses	46%	30%	34%	27%	21%	30%

4.23 There is no doubt that there may be some cash flow problems arising from the payment schedule and corresponding deductions as Cane is delivered. The traditional method of payment is by advances for canes delivered especially during the First Crop. The Final Payment is not due until the 31st March the following year.

4.24 All payment for the Skeldon Cane Farmers is made through their respective Bank Accounts. The Estate retains 30% of each payment made and sends the balance to the respective Banks.

4.25 Those Cane Farmers who had Bank Loans were responsible for whatever deductions were made by their respective Banks.

4.26 The Loans that were negotiated with the Bank were paid direct to the Farmers based on Certificates of the %age of work that was completed jointly by the Skeldon Estate Equipment & Personnel and the Farmer

4.27 All the development work done by the Skeldon Estate on behalf of the Cane Farmers was held in the respective Farmers' debtors account and amortised over four -five years period after harvesting of the plant canes. There is no interest charged on these sums and the Estate

started the recovery of those development sums after the Cane was Harvested and Sugar made.

4.28 None of the sums drawn down from the Bank Loans by the respective Cane Farmers was paid to Skeldon Estate or GuySuCo during the developmental land preparation phases and subsequent husbandry and Harvesting operations.

4.29 The Skeldon Cane Farmers currently owe the Corporation over G\$1.4B for routine operational work to date since the sums incurred for developmental works were subsequently recovered.

4.30 The total value of Sugar produced by Skeldon Cane Farmers from 2009 to 2014 is G\$3.607B. The total expenses deducted by Skeldon Estate was G\$1.069B, which is 30% of gross earnings, leaving a net paid into the Cane Farmers' respective Bank Accounts of G\$2.538B.

4.31 While this special interest in Cane Farmers exists at Skeldon, there has been a loss of Cane Farmers from the Industry over the years representing about 1400 hectares especially at Albion & Rose Hall Estates.

4.32 The converse is the newer developments at Wales and Uitvlugt Estates where temporarily abandoned blocks [TAB] of land in the respective cane cultivations have been offered to Cane Farmers to produce cane. Both Wales and Uitvlugt Factories suffer from very low cane deliveries as a result of relatively poor cane cultivations.

4.33 Between Wales and Uitvlugt Factories, it has been noted that one Factory with some investment should be able to process all the cane now done by the two. Wales Factory has 50% of its cane supply delivered by private Cane Farmers and their production has been at a stable 10,000 tonnes sugar with indications that some cane farmers have already started to put other crops on their cane lands. This assessment is in progress and the actual acreage involved is being compiled.

4.34 The Wales Cane Farmers supply of cane for 2015 has been given as 139,000 tonnes which at 12.70 TC/TS can produce 10,600 tonnes sugar. The projected supply of cane for 2016 is 135,000 tonnes.

4.35 Uitvlugt Estate was able to attract some of Wales' Cane Farmers to plant sections of the estate cultivation which were temporarily abandoned [TAB] for a number of years. The Uitvlugt cultivation was not under full production because of the inability to harvest its cane.

4.36 In 2013 the Cane Farmers started their investment in the Uitvlugt [TAB] cultivation and delivered 3,130 tonnes cane in the First Crop of 2014 that produced 243 tonnes sugar, In the second Crop 2014 some 4,182 tonnes cane produced 301 tonnes sugar making the total of 544 tonnes sugar for 2014 at an overall quality of 13.44 tonnes cane per tonne sugar (TC/TS). As plant cane crop, that 71.3 hectares had very good productivity of 102.55 tonnes cane per hectare (TC/Ha) which was budgeted at 80 TC/Ha.

4.37 Those Uitvlugt Cane Farmers delivered 17,562 tonnes cane in the first Crop of 2015 that produced 1,317 tonnes sugar at 13.33 tonnes cane per tonne sugar (TC/TS). The budget for the Second Crop 2015 is 12,900 tonnes cane to be delivered, which at 13.20 tonnes cane per tonne sugar (TC/TS) can produce 982 tonnes sugar. The Uitvlugt Cane Farmers have increased their production from 544 tonnes sugar in 2014 to 2,299 tonnes in from 30,525 tonnes cane 2015. The 2015 field productivity at 86.52 tonnes cane per acre reflects satisfactory husbandry practices.

4.38 The Cane Projections for 2016 from those Cane Farmers is 19,500 tonnes in the First Crop and 23,700 tonnes in the Second Crop totalling 43,200 tonnes cane producing 3,186 tonnes sugar for the year.

These results are summarised in the tables below

2014	Ha	sugar	cane	tc/ts	tc/ha	ts/ha
First Crop	30.7	243	3,130	12.88	101.95	7.92
Second Crop	40.6	301	4,182	13.89	103.01	7.41
YEAR	71.3	544	7,312	13.44	102.55	7.63

2015	Ha	sugar	cane	tc/ts	tc/ha	ts/ha
First Crop	200.3	1,317	17,562	13.33	87.68	6.58
Second Crop	152.5	982	12,963	13.20	85.00	6.44
YEAR	352.8	2,299	30,525	13.27	86.52	6.52

2016	Ha	sugar	cane	tc/ts	tc/ha	ts/ha
First Crop	250.0	1,477	19,500	13.2	78.00	5.91
Second Crop	289.6	1,708	23,700	13.9	81.83	5.90
YEAR	539.6	3,186	43,200	13.58	80.06	5.90

Unless new replanting takes place after 2017 these field productivity results will be compromised.

4.40 The reality facing these Cane Farmers is their cost of production, and the price being paid for their sugar produced will determine how much further expansion can take place. There is much doubt that at this point in time there is any incentive for rehabilitation of the current 540 Ha cultivation to maintain the 80 TC/Ha or improve it.

- 4.41** The Basic Average Price for Sugar in 2013 was G\$136,472 per tonne to which molasses is added and a transport differential is deducted leaving a gross of 70% for the farmer of about G\$103,000 per tonne sugar.
- 4.42** In 2014 that Basic Average Price dropped to G\$91,297 per tonne which gave the cane farmers an average of G\$72,000 per tonne sugar
- 4.43** It has been projected that for 2015 the Cane Farmer should not expect more than G\$62,000 per tonne sugar.
- 4.44** The Uitvlugt Cane Farmer initiative will be under the microscope in 2016 as the Estate Factory continues to struggle for a reliable supply of cane. The Cane Farmer is a business enterprise no different from any other and if the revenue stream is lower than the projected cost of production there will be no incentive to invest in either rehabilitation or expansion.
- 4.45** While every effort can be made to keep the present Cane Farmers' part of the Uitvlugt cultivation producing cane, it cannot be done if the Farmers are incurring losses. An important part of the "contract" with those Uitvlugt Cane Farmers is that they were required to convert the land for mechanised operations which can eventually lead to billet harvesting. One Cane Farmer has invested in a billet harvester which is being modified to a whole stalk harvester with the expert assistance of the John Deere Agents.
- 4.46** The higher rainfall experienced at Uitvlugt has traditionally excluded the development of mechanised operations. As this mechanised option is being developed, there has to be a conscious effort to start those mechanical operations, especially harvesting, at the beginning of the dry season and accelerating it to finish before the onset of the rains.
- 4.47** The result of the same initiative at Wales Estate cultivation with Farmers cultivating Estate land has not been as dramatic and while some more sugar can be produced, the net result of other farmers going out of cane production is showing nothing positive. Production from the Estate land leased to the Co-ops is being shown in the respective Co-operative gross returns and will be separated for future analysis.
- 4.48** Further the Lands leased from Wales were not converted for any mechanical operations and the formal lease document has not been completed as some members of the Co-op have refused to put their respective signatures. The Estate is prepared to assist those Cane Farmers who may request Bell Loader support.
- 4.49** The proposal for handing over the Wales Estate cultivation to Cane Farmers, lock stock and barrel, needs to be studied very carefully since the primary objective is to have a sustained increase in the supply of cane to the Factory.

5 Progress and Prospects for Mechanisation

5.1 Development Stages and Background

5.1.1 Sugar cane cultivation in Guyana has over 300 years developed as a bedded culture that effectively removes water from around cane roots during periods of intense rainfall and once well maintained has been demonstrated to support high yields. These beds either extend along the length (380m) – English cambered beds or width (115m) – Dutch cambered beds of each field. This system is adapted to only manual agricultural practices. Increasing labour costs have placed considerable pressure on the Industry to remain competitive despite general improvements in productivity.

5.1.2 The first serious attempt at commercial scale mechanisation in Guyana was in 1976 when 128 ha of former cambered bed fields were levelled and converted to Louisiana type ridge and furrow at Diamond estate. In this project, canal areas were filled in to facilitate traffic from within the fields to a trans-loading site. The harvest system comprised a tracked whole stalk harvester, a R6 Continuous Loader, tracked infield tipper transporters and an elevator for trans-loading the R6 billets into punts. Subsidence in former canal sites was a major restriction. Traffic was severely limited by soft soil conditions. The tracked equipment experienced excessive undercarriage wear, probably because of the difficult soil conditions. This programme was discontinued in 1985. An important and lasting development from the period has been the dumper, by which a punt could be lifted out of the water and the contents tipped onto the mill feed table

5.1.3 The deficiencies in the Diamond Project, were linked to the attempt to superimpose a layout on land without sufficient recognition of the existing topography and drain sites). From 1986 to 1990, a programme of phased conversion to Louisiana banks on wide (22m to 33m) beds, on which harvesting equipment comprising soldier (S30 and S32) Harvesters and slewed SP1800 Loaders operated in-field. The whole-stalk cane was transferred into punts with a grab trans-loader. This equipment worked satisfactorily at close to their rated potential of 24 to 30 tonnes per hour, when conditions were favourable. East Demerara, Blairmont and Skeldon were the main operating sites for this programme. The return of Field workers to estates in the early 1990's after removal of pay restrictions, resulted in a management decision to cease commercial mechanized harvesting.

5.1.4 During the 1990s, emphasis was placed on adapting machinery to the impacts of traffic on soft soils. One study indicated very clearly that improved flotation combined with weight transfer between prime mover and loaded trailer could reduce wheel slip and soil deformation. Given the limited opportunity time available for land development and the extensive work that would be entailed in changing field layouts to land forms more amenable to mechanised harvesting, it was desirable to consider any system that increase the productivity of labour (average 2.5 tonnes per man day). The Bell tricycle loader was introduced in 1992 and was demonstrated to significantly improve the productivity of labour working on standard "Dutch"

cambered beds. The ability to operate at low ground pressures (< 80 kPa), when equipped with the appropriate (750mm) Trellborg tires, and manoeuvrability of these machines can extend their function on damp soils. The advantage of these machines in the “Dutch” camber system is that because of the short distances to loading sites, the machines are able to traverse from cane windrow or bundle to load directly into cane punts without any intermediate stage. Cutting and Stacking of cane for loading by the Bell Loader has become the preferred and predominant mode of harvest in the Industry. In 2014, **1,356,799 tonnes of a total 2,536,206 tonnes of cane harvested across the Industry were loaded by the Bells. This accounts for 53% of cane loaded. Reports from the management of each estate, indicate that the proportions of machine loaded canes continue to increase.**

5.1.5 Notwithstanding the usefulness of the Bell Loaders as an intermediate stage for mechanized loading, the capacity to benefit fully from technology developments in land management and agriculture engineering requires flexibility of agriculture systems to accommodate field machinery. This requires modifying field layouts to forms less restrictive to traffic. Guysuco and expatriate technical personnel have expended considerable effort from the mid-1990s to the early 2000s in conceptualizing and evaluating layouts that would facilitate mechanization for sugar estate lands, Two approaches were adopted, . The first applied to “English cambered bed” fields that have been converted to wider cambered beds of widths varying from 30 m to 45 m. The selection of the design bed width is influenced by the topography and land elevation. Cane is planted in flat culture along the length of these beds. Surface runoff is shed across the camber into lateral drains that discharge directly into the main drainage canal via discharge tubes.




Fig 5.1 Wide camber bed layout

5.1.6 The second approach was encouraged for new land development for sugar cane, primarily on the Skeldon Expansion areas. These fields are in ridge and furrow with the design grade to a slope of 1:500. The design distance for drain flow through the furrows is 170m to shallow machine crossable trace drains that discharge through a small culvert into a parallel collector leading to the main drainage canal over a flow distance of 500m at a 1:1000 slope. Attainment of the stipulated gradients is critical to effective runoff of these fields. This layout offers few restrictions to the movement of field machinery, provided the design specifications are achieved.




Fig 5.2 Graded Ridge and Furrow Layout

5.1.7. During construction much of these new lands did not receive the benefit of laser land levelling because of operational difficulties with the equipment and when these issues were finally resolved, the equipment was not effectively utilized. This added to the anticipated problems of soil settlement that exacerbated the occurrences of low spots and localized water logging within sections of the fields. These issues would have to be addressed in the present cycle of land rehabilitation, when full use must be made of this Technology. The broad bed fields will also require laser levelling in the direction of the discharge to the side line drains.

5.1.8 A potential risk is that Guysuco currently has only two persons who possess more than basic training for pre-construction surveys and cut-fill design for precision levelling. One of them on leave pursuing an engineering degree, the other is in a Senior Management position. It would be advisable to conduct further intensive on-site training by the laser equipment suppliers when tillage has actually commenced. Guysuco should also identify with some urgency suitable persons who can be trained to conduct and interpret the pre levelling surveys.

5.1.9.1 The decision to proceed with a fully mechanised option for the expanded Skeldon cultivation only arose because the evidence as early as 2002 was that labour was increasingly difficult to attract. For mechanised harvesting in the Guyana environment, it was recognised that several potential challenges have to be faced:

- a) Foreign exchange for machines, spares and fuel;
- b) Training of mechanics and re-equipping agriculture workshops;
- c) Purchase of spare parts;
- d) High mud in cane when harvesting in wet conditions;
- e) High extraneous matter levels;
- f) Reduced harvesting season length to reduce risk of wet weather harvesting;
- g) Reduced ratoon yields;
- h) Infield cane losses;
- i) Increased deterioration of chopped cane as opposed to whole stalk cane;
- j) Social and political difficulties if willing labour was displaced.

5.1.10 System development work spearheaded by the Research Dept with support from the Booker Tate Agriculture Engineers and Project Team, addressed most of the technical issues that has culminated with the specifications of the current harvesting fleet. Each harvesting unit comprises a billet or combine harvester, three haul-out trailers with prime movers and a billet cane elevator. In the first instance the ground contact pressure under the harvester could be significantly reduced to less than 10psi by fitting wide 600 mm track plates of and extending the track frames to the rear. These features were installed on the first fleet of John Deere 3510 machines. Neither John Deere nor Case have been willing to apply this modification to the more recently supplied machines, indicating that the small size of the orders could not justify this deviation from their production lines. Both the John Deere 3520 and Case 8880 machines are however lighter than the original John Deere 3510 harvesters and were supplied with 550 mm wide track plates. They have performed satisfactorily in damp conditions.



Night Loading with Elevator

5.1.11 The Billet cane Elevators and haul out wagons are fabricated in Guyana from a collaborative Agric Research/Australian design. The haul outs also feature a weight transfer hitch developed in the ARC to more evenly distribute load between the haul out and the haulage tractor rear wheels. Trellborg low ground-pressure tyres are a standard feature on these haul outs. The rear axles on the haul out have been further modified to a more flexible design that permits greater manoeuvrability at the canal edge loading areas. The Research

Centre also developed a cultivation implement that is very effective in alleviating soil damage caused by the traffic of loaded trailers.

5.1.12 While these efforts can be considered successful, there continues to be the need for system development with the mechanized harvesting fleet, in the light of the problems that have manifested with the operation, most of which were predicted. **Under these circumstances, the decision in 2010 to effectively disband the collaborating group of Engineers and Technical staff of the Research and Agriculture Services Depts. and assign them to principal roles unrelated to mechanization was very premature.**

5.1.13 The new cane cultivation culture that has been developed for mechanized agriculture also provides an opportunity for reviewing alternative and more water conserving irrigation practices than the traditional flood irrigation methods. Winch operated travelling "rain gun" equipment were evaluated very extensively in the Skeldon project. The issue with this approach was non uniform distribution of water that affected the relative rates of emergence and early development in different sections of the fields. A variant of the winch operated system with the rain gun nozzles replaced by a linear move sprinkler has been proposed. A flexible hose furrow irrigation system has also demonstrated good potential in the ridge and furrow fields. Flood irrigation has continued to be the dominant practise because of cost and ready availability of water.

5.2. Current Operating Issues

5.2.1 The early campaigns with the Skeldon Harvesting fleet was associated with several machinery failures many of which were attributed to neglect of maintenance guidelines and poor decision making by supervisory staff who did not fully appreciate and still struggle with the complexities of handling a fleet of machinery. In efforts to satisfy cane supply to the factory after late crop starts, arising from factory unreliability, from 2010 to 2012, the machines worked in very wet infield conditions. This resulted in major damage to the fleet and the fields. Large sums were expended to rehabilitate the machines. A major effort has commenced to correct the situation in the fields. The interventions from the Dealer supported by personal interest from Guysuco's Field Engineers enabled several training sessions at the John Deere facilities and on site. These have effectively developed a core team of competent operators and mechanics who seem alert to the capabilities of their equipment and appear to be largely self-monitoring. The operators and mechanics of the new machines at Enmore were given hands on exposure to the Skeldon operation before the delivery of these new machines.

5.2.2 The Harvesting fleet as seems to be common in many areas of the Industry is at risk because of availability of spares. One of the machines is temporarily out of service. Fortunately the John Deere dealer on his own initiative and on the word of Guysuco's Agriculture Services Manager, has acquired the spares and is holding them in consignment stock. Guysuco is required to pay to uplift them. The present fleet 8 billet harvesters is capable of satisfying the

supply of cane from both farmers and estate cultivations at the present factory processing rate of 250 tonnes cane per hour. On attainment of the factory design capacity of 350 tonnes cane per hour another two harvesting units will be required.

5.2.3 The conditions under which the Skeldon Harvesting fleet have operated since have been very poor. Ground conditions have been wet for most of each year despite the lower rainfall regime relative to the other estates. The Installed drainage capability on the expanded estate is insufficient to effectively maintain a cultivation of this size that is further exacerbated by long conveyance path from the Manarabisi sections to the Block 19 Pump station. The importance of activation of the pump station at the Manarabisi/ No 66 cannot be overemphasized.

5.2.4 The harvesting environment for the Skeldon operation was also influenced by factory unreliability that has caused the late start and shorter crop duration in successive seasons. This has led to the accumulation of over age canes in both the Estate and Cane Farmers' cultivations

5.2.5 Harvesting operations in wet conditions starts the cycle of pronounced ratoon decline that can be attributed to soil compaction especially in the Billet harvested and Bell Loaded areas. Additional efforts at correcting this soil deterioration are done but these are never 100% effective, particularly in severe cases of soil deformation.

5.2.6 Invariably where ever Mechanical or Semi Mechanical harvesting is being done in adverse conditions, excessive soil will be delivered to the Factories with the cane. This will affect Factory Performance as the existing equipment is not designed for high percentages of extraneous matter.

5.2.7 Damp conditions and relatively short operating seasons arising from a combination of weather impacts and factory unreliability have contributed to a high percentage of overage canes that in many cases have lodged and exacerbated the problems with mud and high extraneous matter contents delivered to the factory. Reactions to the new operation at Enmore have also been very focused on extraneous matter and mud. The generally negative conversation has unfortunately not been helpful for the overall impressions of mechanization in the industry that has positive features and cost implications that have tended to be overlooked

Operation	Unit Cost G\$
Manual Harvesting	\$2155 per tonne cane
Cut & Stack – Machine Loaded	\$ 2139 per tonne cane
Combine Harvesting	\$ 1371 per tonne cane
Manual Planting	\$66000 per Ha
Semi – Mechanical Planting	\$ 55000 per Ha
Manual Fertilizing	\$ 5290 per Ha
Mechanical Fertilizing	\$ 3450 per ha
Chemical Weed control (Knapsack)	\$ 3810 per Ha
Chemical Weed Control (Boom spray)	\$ 2700 per Ha

Table 5.1 Indicative Costs of Main Agriculture Operations- Guyana

5.2.8 Mechanized harvesting has become the principal strategy for Skeldon and is anticipated to expand in East Demerara over the next 4 years. It is therefore necessary that the Agriculture and Factory Operations Depts. collaborate on strategies that would maintain cane deliveries, reduce the extent of extraneous matter and to manage the inevitable increased soil load of canes delivered to the factories.

5.3 Harvest Management and Cane Deliveries

5.3.1 Mechanized harvesting and loading are not subject to the same restrictions of waiting for individual punts to be loaded for payment assignments as is manual cane cutting. These operations permit punts to be hauled to the mill as soon as the requisite numbers for a haulage train have been loaded. This facilitates the recycling and reuse of punts and would allow for significant impacts on reducing Kill to Mill intervals. This opportunity has not been fully appreciated by harvesting managers who continue to plan their operations for traditional manual operations. Mechanised harvesting is also continuous over 24 hours, and once efficiently managed and coordinated will reduce the requirement for accumulating a large dock of punts before early cane deliveries, prior to grinding.

Estate	Cut & Load	Cut & Stack	Combine Harvested
Skeldon	85,483 tonnes	209,405 tonnes	177,424 tonnes
Enmore	152, 065 tonnes	62,795 tonnes,	56,096 tonnes

Table 5.2 Cane distribution to factories with combine harvesting -2014

5.3.2 Mechanized farming will increase in importance in the Guyana Sugarcane Industry. The positive impacts on costs of operation have already been demonstrated. There are however constraints and areas for improvements that cannot be underestimated. Many of these issues will have technical and managerial solutions that need to be addressed with appropriate urgency and technical support. **The programme should be coordinated by a very senior and experienced Engineer or Manager**, with the necessary support who would have authority to co-opt as required individuals with the required expertise to address system and technical development issues that will arise as this programme develops. Areas that require priority attention at this time include:

1. Development of expertise in survey techniques, cut fill design and planning for precision levelling.
2. Precision land levelling for ridge and furrow and Broad bed fields.
3. Planning and monitoring of Field rehabilitation of fields involved in mechanized harvesting, particularly at Skeldon.
4. Identify and introduce a fertilizer blend suitable for effective dispensing by mechanical band and placement applicators.
5. Develop and evaluate alternatives to flood irrigation.
6. Coordinate and guide Field Conversion programme.
7. Develop a conversion sequence for Dutch layout fields.

8. Coordinate regular discussion and training sessions on cane loading and delivery for estates' management.
9. Development and testing (with ISD) of a cane delivery and optimised harvesting scheduling schedules.
10. Revisit and test alternate modes of cane transport including road and also a hydraulically driven propeller tug prime mover.
11. Address extraneous matter cane quality issues in collaboration with Factory Operations Technical staff.
12. Further evaluation and testing of low ground pressure haul out equipment including tracked options for effective operation in damp conditions.
13. Development of punt restraint and punt movement system to improve efficiency at field loading sites.
14. Introduction and evaluation of precision farming including agronomic inputs, weed control and controlled tillage.

6 AGRICULTURE PROCUREMENT

6.1 The Guyana Sugar Corporation Inc. established a Procurement Policy which is second to none.

6.1.1 It requires a system of three quotations from which to choose a qualified supplier in accordance with the specifications provided in the bid documents.

6.1.2 Over the years, with increasing operational deficits, the Corporation has developed a special relationship with some suppliers who would provide goods and services in spite of delayed payments.

6.2 Fertiliser

6.2.1 The process of bidding for fertilisers has morphed into those who would bid to supply the major supplies such as Fertiliser requiring about US\$4M per year.

6.2.2 The inability to negotiate adequate supplies particularly of Fertiliser has developed a chronic field problem of relatively poor cane nutrition with the resultant lower cane yields and corresponding higher levels of weed infestation.

6.2.3 The lower cane yields has had a deleterious effect on controlling harvesting costs with escalating demands for “extras” usually paid for conditions which reduce the rate at which the Cane Harvester is expected to perform.

6.2.4 Demands for “extras” are accompanied by unfavourable industrial relations which invariably escalate into prolonged strike action in all areas of harvesting including those not requiring “extras”.

6.2.5 This unstable state of industrial affairs is often accelerated by the prolonging of the crop into the unfavourable wet season as the time lost earlier in the crop forces continued operations in order to achieve the production targets.

6.3 AGRO CHEMICALS

6.3.1 The aftermath of the financial crisis has reduced the number of credible suppliers to three which in its own right is a blessing in disguise.

6.3.2 The quality of the Agrochemicals with respect to unacceptable levels of contaminants has been maintained because the regular suppliers have avoided manufacturing sources that do not comply with the standard specifications in the order.

6.4 STEEL PLATES

6.4.1 There has been much concern expressed by all the Estates on the timely acquisition of the quantity of Steel Plates ordered for punt fabrication, repairs and re-bottoming. The standard quarter inch steel plate which in metric terms is six delta two millimeters and this specification is clearly stated on the orders. The suppliers have been delivering the metric equivalents of quarter inch plate that are approximately 6 mm thick. steel plates.

6.4.2 The re-bottoming programmes have not been in keeping with the respective planned schedules and therefore repairs have escalated. This has had some negative effects on the Estates' harvesting programmes because of the numbers of unserviceable punts in the fleets.

6.4.3 While the physical measurements of the steel plates supplied can confirm the thickness deficiencies the question of the quality of the steel is still being questioned. In re-bottoming a punt, one of the observations is the ease with which the band of steel can be bent to fit the round areas at the front and back of the punt without using clamps. **The need to re-bottom "new" punts because of unusual wear cannot be the result only of steel quality as there is evidence of poor maintenance of navigation canals and associated structures. This is further accompanied by undesirable operational issues such as the number of punts being pulled in a single train.**

6.4.4 There is no doubt that additional wear and deformation of the punt fleet is being experienced on all locations and there is a reluctance to admit that in the wetter conditions, the larger horsepower tractors are used to deliver the cane from the fields to the factories and far longer punt trains than the standard 35 punts are being used without regard for the eventual problems being faced today.

6.4.5 The visibly poor state of more than half the punt fleet which forms a key part of the assets of the Corporation displayed significant elongation and other forms of structural deformities.



Elongated Punts



Ripped Punt Head

6.4.6 The Corporation, to its credit, recognised the dire state of its punt fleets and established a Punt Management Review. The May 2015 report identified a Punt Age durability Analysis which will put into place an improvement in punt record keeping and its corresponding asset register of over 4,300 punts. All these initiatives are being supported by the Information Systems Department which is constantly visiting the Estates refining the forms and supporting documents.

6.4.7 The expenditure for punt repairs for the last 10 years, (2005 to 2014), was G\$1,378.96M, ranging from as low as G\$108.38M in 2009 to G\$202.20M in 2014.

6.4.8 Over the same 10 year period punt re-bottoming expenditure was G\$1,185.56M for 1,643 punts. The rate and consistency of re-bottoming over the years varied considerably and was dependent on the availability of steel plates.

6.4.9 A hydraulic press has been fabricated at Skeldon which can press out the punt sides in just 10 minutes.

6.4.10 The Budgeted 2014 fabrication of 400 new punts were completed in August 2015 as only 290 were completed at the end of 2014. Steel Plate for the Budgeted 2015 fabrication of 350 new punts has not been approved to date.

6.5 MACHINERY SPARES

6.5.1 The Field machinery fleet continues to expand as more specialised equipment especially for Mechanised Harvesting develops. The range of equipment is often influenced by the agencies providing the funding which adds to the maintenance spares woes.

6.5.2 The ability to pay for spares with the orders cannot be maintained in the present production and financial crisis, resulting in maintenance and repairs delays and increased fleet unavailability. None of the Estates can complete its tillage programme with the availability and efficiency state of the current fleet of tillage equipment.

6.5.3 The local agents for some of the specialised equipment, for example the John Deere Harvesters, recognised the critical state of some of their equipment and have been providing training modules for both the operators and maintenance personnel resulting in higher availability and better reliability of those machines.

7 Research and Development

7.1 In a technology dependent Industry, an effective research and development function is an asset to its sustainability. The Guyana Sugar Corporation's Research Development Departments have contributed to technological change and adaptation to environmental conditions in several areas:

- A robust variety development programme that has an independent capability for breeding as well as very strong linkage to the West Indies Central Sugarcane Breeding Station
- A well-established Integrated Management Programme for insect pests and weeds, which includes effective biological control for the ubiquitous moth borer *Diatraea* Sp. Most other insect pests are controlled by cultural methods with minimal chemical intervention.
- A mammalian pest management strategy, the principles of which have been successfully adapted by other Industries
- Soil Management and Cane Nutrition policy that has been responsive to changes in the environment since its formal institution in the 1960's.
- Established a robust Industrial Environmental Monitoring Capability
- Climate change assessment and adaptation strategies
- A lead role in mechanization system development within the Caribbean region
- Sugar cane and sugar chemistry analytical capability for supporting cane quality and process studies
- Lead role in Sugarcane for Energy Studies for Caribbean Industries.
- Regionally recognised Analytical Laboratory.

7.2 Most of the Department's established programmes including the Laboratory analyses continue to be executed. However there has been little interest or major actions emanating from the Dept.'s initiatives on the estates over the past 6 years. This a distinct variation from the previously established role of the Dept. when it was clear that the Industry Agriculture Policy emanated from the Department and the Scientists and Technical Officers were representatives of the Director and were acting on his authority when visiting estates. The subtle change in the recent past implies that estates could look elsewhere for the authority on guidance given by the Dept. and are in fact free to ignore it should they not agree with or understand the information.

7.3 Morale in the Dept. is low and more than one member of the group has expressed uncertainty over the Dept.'s future.

7.4 Subscriptions to Technical Journals and for Professional Memberships have been curtailed.

7.5 Likewise there are no budget allocations for research and development projects initiated by the Department.

7.6 The tractors that were used to service the Breeding and Selection Cultivation and trials were removed after the Field Engineering section of the Department was closed. The ARC is dependent on LBI estate for support for cultivation and trials. Requests have not always been given priority by the estate.

7.7 The current Head of Research also admits to being insecure. He has not been confirmed in his position despite having acted in the role for 6 years. Apart from having an uncomfortable relationship with the executive management, he also seems to be conscious of having to justify his status to the group he leads as he has not been a practising researcher.

7.8 It has also been claimed that the executive management and Board of the day have also foisted projects onto the Dept. over the objections of the scientists. Recent examples of this have been an attempt to adjust the crop fertilizer regime without previous investigation and an ill-advised large scale research programme to introduce a "Biofertilizer" of uncertain origin into the crop nutrition programme. The Company has risked US\$145,260 in purchase of this material. The researcher assigned to the project has expressed unease over the inadequate information on technical specifications for the material. The depressed production from the 2013 crop has indicated the pitfalls of arbitrary changes in agronomic practices. The latter trials are currently being harvested but the observations in field have not been favourable to the material.

7.9 There seems to have been no consistent appraisal of the nutritional status of the growing crop in order to adequately correct any deficiencies to optimise yield potential. The frequent episodes of inadequate fertilizer applications at the standard recommended times have further aggravated the downward trend in cane productivity. The Central Laboratory has however maintained as far as possible the programs set up to monitor Crop Nutrition trends. The data though limited, are beginning to highlight the occurrence of minor nutrient deficiencies and also that the average foliar N values have declined in recent years. These are important indicators and should warrant further investigations

7.10 These and other examples highlight the pitfalls of the temptation to disregard the evidence of accumulated knowledge in the interest of desirable financial objectives.

7.11. The Dept. has had a vacancy for an experienced Soil Scientist/Crop Nutrition Scientist for several years. This deficiency may contributed to the confusion that have influenced the attempted adjustments to fertiliser regimes. Efforts must continue to fill this vacancy or train an individual who has the aptitude and interest in the discipline.

7.12 Most of the issues raised in relation to plant nutrition have been addressed. There is documentation in the Research Dept. that can offer guidance at this time. In the absence of an incumbent scientist, recourse to these reports and recommendations should be sought.

Table 7.1 COMMERCIAL VARIETIES

Variety	ARC % as revised July 2009	2007	2008	2009	2010	2011	Mean TS/H per variety since 2008	Mean TC/H (PI – 5R+) per variety from 2008 to 2011
D 15841	5 - 10	6.9	6.1	5.0	4.2	3.2	4.55	56.7
D 7661	1 - 5	10.8	9.9	9.1	7.0	6.0	4.95	57.5
D 89138	5 - 10	15.7	12.3	9.8	7.4	4.6	4.525	55.3
D 9017	15 - 20	9.1	9.5	12.1	12.7	13.8	5.187	64.5
D 93222	1 - 5	1.1	2.4	3.2	3.7	3.5	5.212	71.5
D 93409	5 - 10	5.2	6.2	6.3	7.3	7.5	5.375	66.9
DB66113	1 – 2*	3.6	2.8	2.1	1.7	1.1	4.3	58.9
DB75159	15 - 20	6.3	6.4	7.6	7.9	7.6	4.518	59.2
<i>DB7869</i>	25 - 30	35.7	34.6	32.6	27.7	29.9	4.84	58.4
DB9314	5 - 10	0.1	0.5	0.7	1.3	2.4	5.8	72.7
DB9633	15 - 20	1.5	5.8	9.0	16.6	18.4	5.98	72.1
R 570	1 – 2**	1.7	1.4	1.5	1.1	0.8	4.6	55.1

7.13. The relationship with the West Indies Central Sugarcane Breeding Station has been maintained. The Dept has also continued the Demerara Breeding Programme that is based at LBI. The recent acquisition of Belize Sugar Industries by the American Sugar Refiners has enabled an expanded relationship of the WICSCBS with the USDA station at Canal Point. This, it is anticipated will strengthen the regional sugarcane breeding effort.

7.14 No variety has attained commercial status since 2008 when DB 9314 and DB9633 were released as commercial. These two and D93409 appear to be the most productive varieties in general cultivation. However the Department has recommended the withdrawal of D93409 because of smut and as a temporary measure two older varieties D7661 and DB66113 have been recommended for limited extension. This is unfortunate because neither variety is as productive as D 93409.

7.15 Since 2007, 27 varieties have been released to estates have had released for Stage 5 and Stage 6 evaluation. The Industry should be in a good position to find new commercials in a short time, if both parties exert the effort to pursue these evaluations purposefully. **The varieties D 9584 and D98633 have had sufficient evaluation to justify extension for Industry wide pre- Commercial trials and factory testing. These should proceed without further delay.**

The releases DB 98209, DB 9854 and D 98281 should also be given priority for accelerated trials as the data from Stage 4 and 5 trials indicate their superior pol %cane. .

Table 7. 2 Varieties Recommended for Stage VI

VARIETY	Year released	Status	PARENTAGE	ISSCT RATING	INDEXED VALUES		
					TC/H	Pol % Cane	TS/H
D9584	Dec 2007	In Trials	D9018 x Poly C	MR	118	94	111
D9824			D93287 x D93274	HR	101	102	104
D98490			D89190 x Poly C	R	99.5	100	99
D98633			D91101 x Poly C	R	100	102	102
D98122		Was withdrawn	D9181 x Poly C	HR	97	105	102
DB9925	March/April 2009	In Trials	DB75159 x Poly C	R	102	98	100
DB99126			DB75159 x Poly C	R	112	92	102
DB99590			DB75159 x D8415	R	108	103	110
D99460			DB9420 x Poly C	R	102	99	100
DB9984			B85342 x Poly C	S	97	104	100
DB9969			B90505 x Poly C	R	109	99	110
D96308			D9119 x Poly C	R	111	101	113
D96261			DB79327 x Poly C	HR	117	96	112
DB9855			BT65282 x C8751	MR	106	109	116
DB99269			B85342 x Poly C	R	113	101	114
DB98209	Aug 2009	Being bulked up at estate nurseries with the	B85342 x Poly C	R	101	110	110
DB9854			BR7514 x C8751	HR	98	110	109
D98225			D89158 x Poly C	VHR	107	99	105
D98281			DB92210 x Poly C	VHR	113	104	117

D98239	Mar/	excepti on of RH and LBI	D89192 x Poly C	R	95	109	104
DB99176	April 2011		B89666 x Poly C	R	102	105	106
D99192*			DB94109 x Poly C	R	101	103	104
D99187*			DB9486 x Poly C	R	110	101	111
D98602			D8601 x Poly C	MR	107	95	102
D98623*			DB93117 x Poly C	VHR	117	100.2	119
D99325			D8921 x Poly C	HR	121	99	118
DB99367			D8494 x Poly C	MR	109	104	112

7.16 Productivity data are now being obtained from Co 8602 that had been introduced as tissue culture plantlets from India. The objective reports on this variety indicate that it is comparable to the standard DB7869 in quality and gross yield, but that it may have a semi-recumbent habit that is an undesirable agronomic trait. The variety has been recommended for inclusion at the Stage VI trials for evaluation against the other varieties listed as promising.

7.17 The Research Department does indeed continue to generate helpful information that the industry is well advised to take advantage of. The Department must build on its strengths to enhance its image and relevance to the estates. In present circumstances support from the Executive Management will be necessary to emphasise the Dept.'s continuing value to the Industry.

8 Weather and Climate Change

8.1 Agriculture on coastal Guyana is very influenced by climatic variations. The country's sugarcane crop is grown under predominantly rain-fed conditions and the quantity, intensity and distribution of precipitation has a significant impact on the productivity of the sugar cane crop. The average growing environment for sugarcane can be described as moderate rainfall for Skeldon in the eastern coast (Mean Annual Rainfall 1615 mm) rising to 2693mm in the west at Uitvlugt. The quantity of rainfall is variable and is rarely consistent in successive years. The infrastructure for drainage and water management in the sugar estates has been developed to cope with the extreme events of heavy and deficient rainfall, both of which can adversely influence the growth of sugarcane. Excessive rainfall is more damaging as prolonged flooding, when this occurs will kill young cane stools. Wet conditions during harvesting create conditions for long term damage to soil physical properties.

8.2 During the past two decades increasing concern has been expressed over Global climate change. Guyana's low elevation coastal zone is acknowledged to be among the more vulnerable environments to progressively rising sea levels and unstable climatic variations.

8.3 A recent (2009) report to the United Nations Framework for Climate Change (UNFCCC) that was developed from data collected from Vulnerability Climatic Assessment Studies in 2008 has indicated from the application of two Atmospheric Oceanic Global Circulation Models (A-OGCM) that the medium term trend would be for a decreasing rainfall in coastal Guyana, with more intense storms during the "wet seasons" and extended droughty conditions in the drier seasons. During the same period higher tide levels and storm surges are predicted. The study has pointed to the importance of strengthening the coastal defence infrastructure to minimise risk to the country's major population centres and productive areas.

8.4 The implied risk to sugarcane can however be turned to an advantage by practising more effective water management including replacing high volume surface irrigation methods with more conservative drip or low volume overhead methods.

8.5 Guysuco maintains and monitors rainfall and climatic trends and collaborates with the Hydrometeorology Dept. in the interpretation of medium term climatic trends. The Industry has coped with severe drought and flood events. In both cases risks and management responses for each estate have been well documented.

8.6 This material is used as resource material for training and strategy planning sessions that are conducted whenever a risk of an extreme weather event is indicated. This practice should continue. The Industry's Climatologist and Hydraulics Engineer would be the responsible individuals.

8.7 There has however been little evidence for any definitive climatic change trend affecting the sugar industry, despite frequent assertions that these have been occurring over the recent years. Weather on the coast has always been very variable, particularly during the months of

January and February. The mean rainfall over the past 20 years has been consistent with the historical pattern, although it is evident that the past decade has been a period of above average rainfall for which there is also a precedent.

8.8 Uncertainty of rainfall or climate probably causes greater concern today because there is more dependence on machinery for agricultural operations during the cropping periods. Wet conditions restrict access to fields and will risk damage to the soil and crop by compacting effects of machinery traffic. The established custom in Guysuco is to plan for a combined operating crop period of 32 weeks in situations more dependent on machinery, it would be appropriate to determine and plan for the driest available weeks. Rainfall distributions can be analysed to highlight this as follows:




Table 8.1 Summary of wet months SKELDON ESTATE 1995 -2014

Month	% Incidence > 100 mm	% Incidence > 150 mm	% incidence > 200 mm
January	45%	25%	15%
February	50%	30%	15%
March	20%	10%	5%
April	60%	25%	10%
May	95%	85%	65%
June	95%	80%	45%
July	95%	70%	35%
August	55%	30%	5%
September	5%	5%	0%
October	20%	5%	0%
November	30%	0%	0%
December	65%	45%	25%

**Fig.2 ALBION ESTATE
Monthly Precipitation Totals (mm)
1995 - 2014**




Table 8.2 Summary of wet months ALBION ESTATE 1995 -2014

Month	% Incidence > 100 mm	% Incidence > 150 mm	% incidence > 200 mm
January	70%	60%	40%
February	45%	35%	25%
March	25%	10%	5%
April	60%	55%	45%
May	90%	75%	65%
June	90%	85%	65%
July	95%	80%	70%
August	70%	55%	30%
September	15%	5%	5%
October	20%	5%	5%
November	30%	15%	5%
December	75%	50%	35%

..

**Fig 8.3 ENMORE ESTATE
Monthly Precipitation Totals (mm)
1995 - 2014**




Table 8.3 Summary of wet months ENMORE ESTATE 1995 -2014

Month	% Incidence > 100 mm	% Incidence > 150 mm	% incidence > 200 mm
January	65%	55%	50%
February	40%	30%	20%
March	25%	10%	10%
April	70%	45%	20%
May	85%	80%	75%
June	95%	95%	70%
July	90%	80%	60%
August	80%	65%	20%
September	10%	5%	5%
October	10%	5%	5%
November	60%	40%	25%
December	70%	65%	50%

**Fig 8.4 UITVLUGT ESTATE
Monthly Precipitation Totals (mm)
1995 - 2014**




Table 8.4 Summary of wet months UITVLUGT ESTATE 1995 -2014

Month	% Incidence > 100 mm	% Incidence > 150 mm	% incidence > 200 mm
January	80%	65%	55%
February	50%	40%	30%
March	50%	25%	15%
April	70%	60%	45%
May	95%	95%	85%
June	100%	95%	80%
July	100%	100%	90%
August	80%	45%	40%
September	40%	15%	5%
October	50%	30%	10%
November	70%	55%	30%
December	85%	75%	75%

8.9 On the assumption that a monthly rainfall under 150mm would be sufficiently dry to permit harvesting in most cases, this analysis strongly suggests that with the dry month restriction the “Second Crop” harvest campaign should not commence before August on the majority of estates. In Uitvlugt with a 45% occurrence of August rainfall exceeding 200mm, would commence later than the other estates. This rainfall distribution does warrant consideration of a harvest campaign lasting from mid- August of one year through to the end of April of the succeeding year, with a short break during December and January. It would probably be advisable to keep factories in a state of readiness to resume operations as soon as conditions permit, following the year end rainfall, that is commonly unpredictable and perform major maintenance from May to July.

8.10 Skeldon is the only estate where conditions are indicated to be dry enough to consider an end of July start. The present conditions are at variance with this observation. It has been determined that the installed Skeldon external drainage is well below the design requirements. The activation of the new Manarabisi/No66 pump and drainage link should impact on this deficiency. However similar wet conditions prevail in the Crabwood Creek and Molsen Creek cane farming areas. The drainage infrastructure in these areas should be assessed and an appropriate plan prepared without further delay.

9 Environmental Matters

9.1 The Guyana Sugar Industry has carefully established a sound reputation for responsible environmental stewardship. The Industry had made significant progress towards certification under the ISO 14001 by 2008. Unfortunately the process has not been completed following the departure by migration of the former Manager of Analytical and Environmental Services who was the sponsor of the programme.

9.2 Notwithstanding the systems of monitoring by analyses of effluents and discharges from Factories and Agriculture activities has continued. The Guyana Environment Protection Agency has been coordinating this programme with full support from the Guysuco Analytical Services Section.

9.3 There have been no reports of water borne diseases or health hazards on GuySuCo's estates. Good quality of potable water is supplied at all times to field labour.

9.4 Crop Protection for the Industry is based on an Integrated Management approach that emphasises the use of agrichemicals, biological control and cultural practices as appropriate. Agrichemical usage is predominantly herbicides. There is minimal use of insecticides. Fipronil is usually recommended for treatment of termites although Chlorpyrifos has also been used as an alternative. Guidelines for agrichemicals usage, storage, and disposal were published by the Agrichemical Safety Committee in 1996. These continue to be followed. In 2008 the Agriculture Research Dept. published a Manual on rodent control, emphasising surveillance, prevention and baiting strategies. Both publications have been found useful as reference by other Industries

9.5 Aerial spraying is the method of choice for broadcast application of herbicides. This method ensures uniform cover and treatment, accuracy is guaranteed by the SATLOC GPS system. Large areas are achieved in a single day. This practice also minimise exposure of humans to chemicals there are strict rules governing aerial spraying. These include the proximity to housing areas and non-sugar cultivations. Increasing urban spread particularly in Demerara and farming in Berbice restricts the extent to which the equipment can be used. Care is taken to contain washings from spray aircraft, knapsack and boom spray equipment. These are treated in containment ponds that are tested prior to release.

9.6 The majority of the chemicals used on sugar estates are low dose chemicals of short life cycle or that are readily degraded. Two of the widely used chemicals in the Sugar Industry, glyphosate and 2,4D amine have recently (2015), been placed on the WHO's International Agency for Research on Cancer (IARC) list of possible carcinogens. There is however considerable evidence that does not support a link with cancer for either chemical.

9.7 In 2007, the US EPA issued a ruling that the available evidence does not support a link between 2,4D exposure and cancer in humans. The EPA reinforced this conclusion in 2012,

stating that new studies and the Agency's comprehensive review leads to the conclusion that 2,4-D tolerances were safe at "normal" exposure levels. The European Food Safety Authority has also concluded in a 2011 ruling that residue limits of 2,4D were not expected to be of concern to European consumers. This is however widespread agreement that the more volatile ester forms of 2,4D could constitute environmental hazards.

9.8 The IARC published risk with Glyphosate has generated considerable discussion which is to be expected, given the chemical's widespread use as a broad spectrum non selective herbicide. Most regulatory agencies have not endorsed the IARC position. The comprehensive Agriculture Health Study of the United States has found no evidence for association of glyphosate with the incidence of cancer among the large sample population of applicators (De Roos et al, 2005). The USA EPA is currently conducting a detailed review of the available data on glyphosate toxicity and epidemiology. The German Federal Institute for Risk Assessment published in 2013 a detailed Review of the toxicology of glyphosates that concluded that the available data did not support any labelling of glyphosates as carcinogens.

9.9 Small Sugar Industries such as Guyana will have to act in their best interest if they are to remain competitive. This includes using cost effective agronomic technology. The Industries should not panic over the recent alleged disclosures on its main herbicides but will have to remain vigilant on the growing evidence either for or against a cancer link over the next few years. In the meantime the Research Dept. will have to investigate the efficacy and cost implications of alternatives to these agrochemicals.

10 Opportunities for Diversification

10.1 The implications from market prospects suggest that Industries dependent on raw sugar exports will face an uncertain future unless they have access to favourable bilateral trade arrangements and can maintain low costs. While there is scope for significant cost reduction mainly by improved productivity in the Guyana sugar estates, these are unlikely to be sufficient to make this Industry profitable under a single commodity production model.

10.2 It is therefore necessary to explore alternative options for economic activity from the existing plant and lands under sugarcane cultivation. During the 1970's and 1980's, in consequence of reduction of the available quota from the USA, the Guyana Industry had embarked (with grant funding from the USA) on an ambitious programme of diversifying agriculture production. Several programmes were evaluated with varying levels of economic and productivity success. The more prominent were dairy cattle (for cheese), rice, aqua-culture and field grains. In the decades following with more emphasis on the core activity – sugarcane production, a number of studies were conducted on options for vertical diversification within the sugar cane crop.

10.3 ETHANOL

10.3.1 Between 2002 and 2006, in depth studies were conducted in Guysuco to assess the feasibility of Fuel ethanol (Davis et al, 2005). This was followed by a formal assessment of the scope of this work by an ECLAC consultant (Horta and Coviello, 2008). That report endorsed the findings of the Guysuco assessment that had concluded that while there was no cost incentive to substitute sugar production by ethanol, conversion of surplus molasses to fuel ethanol should be a cost effective measure to provide 11.3 M liters of anhydrous ethanol for blending into a 10% mix with gasoline. Productivity indices from this study are summarised in Tables 10.1

Table 10.1 Alternatives for modernization of a sugar mill in Guyana (2005)

Alternative	Sugar production (tons)	Molasses production (tons)	Ethanol production (thousands of litres)	Electric power generation (MWh)
Original situation	80,182	32,073	-	-
Sugar only	73,409	29,364	-	25,200
Sugar and ethanol from exhausted molasses	73,409	(14,098)	11,300	25,200
Sugar and ethanol from rich molasses	56,283	-	11,300	25,200

Table 10.2 Cost of production of ethanol from molasses (2005 study)

Component	Estimated cost (US\$/litre)
Raw material (molasses)	0.1731
Energy (steam and electric power)	0.0196
Chemicals	0.0303
Wages	0.0097
Maintenance	0.0082
Other fixed costs	0.0051
Total	0.2461

10.3.2 At the time this work was undertaken the analyses indicated that at a price of under US\$320 per tonne of sugar, the production of ethanol could be price competitive. This would be the projected price of sugar after 2017. However the price of oil has also fallen significantly and at current prices of US\$.28 per liter (equivalent to \$45 per Barrel) the price received for sugar would have to fall below \$170 per tonne for fuel ethanol from cane to offer an alternative to sugar. These prices are moreover significantly below the Guyana Sugar Industry cost of production.

10.3.3 The ECLAC and Guysuco analyses also indicated that at the extant price of fuel, production of fuel ethanol from molasses (after consideration of contract commitments) would be an advantageous value added prospect. The 2014 price received for molasses was US\$ 121 per tonne. This would be equivalent to a value of \$0.46 per liter converted to ethanol. At current fuel prices, further processing to fuel ethanol is not justified.

10.4 COGENERATED POWER

10.4.1 Over the production plan period, an increasing proportion of cane supplied to factories will be derived from machine harvested and loaded canes. This will inevitably require investments in the factories of the necessary equipment to cope with higher levels of extraneous matter and mud. Replacement of aging Boiler plant is projected in most cases. Estates should take advantage of this requirement to install high or medium pressure boilers

and perform the necessary modifications to the drives and process that will reduce power requirements and enable the export of power from each mill during the cropping season.

10.4.2 The Indicative cost for an Installed Boiler and Turbine Alternator equipment is US\$ 11.M The export of power was indicated to be a significant contributor to income in previous industry studies including the ECLAC (2008) study. Seasonal (6month) supply would enable the Utility to rest and service generating equipment in a phased predictable manner. The generation of power from bagasse will also be compatible with a base power production based on hydro-power that may be the likely medium term development plan for the Guyana Utility Company. The design of these projects and export potential would have to be determined in a detailed feasibility study.

Boiler Pressure	Operating Temperature	Export potential
31 Bar	440 Degrees C	76 kwh/t cane
45 Bar	440 Degrees C	92kwh/t cane
82 Bar	525 Degrees C	143 kwh/t cane

Table 10.3 Benchmarked Boiler and Power Export Indicators – Mauritius

10. 5 WHITE SUGAR

10. 5.1. Construction of a refinery is a medium term consideration in the Guysuco Strategic Plan. A lower cost alternative would be the production of plantation white sugar in a raw sugar factory using Ultra Filtration and poly anions processing aids. This technology was developed in the first decade of the 21st century and is claimed to have energy and environmental advantages over more conventional sulphitation, carbonation and “Blanco Directo” processes. This grade of sugar would satisfy the requirements of most food processers but not bottlers. The Factory Team has recommended evaluation of this option as well as that of a conventional refinery.

10.6 Several presentations sought to offer options for diversification of the field operations in the event of any factory closures. The options were classified as CROPS, LIVESTOCK and AQUACULTURE.

10.7 CROPS

10.7.1 The only other Crop that has the scale of land use similar to the Sugar Industry is Rice which has low labour requirements relative to the evolving Sugar Industry. The low labour input in rice cultivation is not attractive as an alternative to the operations in the cane fields.

10.7.2 The National Agriculture Research & Extension Institute is evaluating other crops that may have commercial potential for coastal agriculture. These include maize, soybeans, passion fruit and other orchard crops, Meringa and Quinoa among others. Some Wales Cane Farmers are also major suppliers and exporters of pineapple.

10.7.3 The product of any other crops on an extended scale will suffer from prices influenced by seasonal oversupply unless some form of processing is integrated in the production cycles.

10.7.4 It would be foolhardy to plan for any extensive farming that requires abundant labour which is one of the main reasons why the Cane Cultivation at Uitvlugt is so unproductive with a factory that can only work every other day.

10.8 LIVESTOCK

10.8.1 Proposals for Beef Cattle Units that can mature within 10 years have been considered, but to replace all the cane cultivation land in phases will require capital investments outside the scope of this inquiry and points once more to the involvement of private investment.

Parameters	1	2	3	4	5	6	7	8	9	10
Calving Rate (%)	60	60	60	60	70	70	70	70	75	75
Calf Mortality (%)	10	10	10	10	10	10	10	10	10	10
Culling Cows (%)	0	0	0	5	7	10	10	10	10	10
Culling Heifers (2-3 yrs.) (%)	0	0	0	0	0	0	0	0	0	0
Culling Bulls (%)	0	0	0	0	0	0	33	33	33	33
Mortality (9-24 mths) (%)	10	10	10	5	5	5	5	5	5	5
Mortality (Adult) (%)	5	5	5	5	5	5	5	5	5	5
Bull: Adult females	1:30	1:30	1:30	1:30	1:30	1:30	1:30	1:30	1:30	1:30

YEAR	0	1	2	3	4	5	6	7	8	9	10
HERD COMPOSITION											
Breeding Bulls	6	6	6	7	7	7	7	8	9	10	12
Breeding Cows (purchased)	200	190	180	171	194	212	221	235	273	311	352
Male Calves		51	49	46	53	67	70	75	88	107	121
Female Calves		51	49	46	53	67	70	75	88	107	121
Bulls/Steers (1-2 yrs.)		0	46	44	44	50	64	66	71	84	102
Bulls/Steers (2-3 yrs.)		0	0	41	42	41	47	60	62	67	79
Bulls/Steers (3-4 yrs.)		0	0	0	41	42	41	47	60	61	66
Heifers (1-2 yrs.)		0	46	44	44	50	64	66	71	84	102
Heifers (2-3 yrs.)		0	0	41	42	41	47	60	62	67	79
Total herd		298	376	440	520	577	631	692	784	898	1034
Total Animal Units (au)*	156	174	207	259	323	348	377	418	475	534	613

As a general comment, the physical land area would pose no problem for beef cattle development on areas already not producing harvestable cane. It is not envisioned that any cane cultivation would be closed to accommodate diversification of the land not in actual cane production.

The unit of 1,000 beef animals would require 650 hectares of land with the assumption that controlled rotational grazing would be the primary management system.

If feedstock has to be developed, other sugar industries have a broiler production capability utilizing bagasse as litter. The bagasse chicken litter is collected and stored, to be later mixed with molasses and fed to the cattle. Those broiler units can be contract farms supplying chicken to a processing entity like Bounty Farms.

Other options for livestock development would not utilize the land assets now under cane or temporarily abandoned lands and will require serious feasibility studies.

The contentious issue of the INVESTMENT required, points to the need for other agencies or private individuals having a stake in these diversification proposals.

10.9 AQUACULTURE

10.9.1 The Sugar Industry layout with fields surrounded by dam beds is considered an ideal opportunity for the development of aquaculture.

10.9.2 The intensive system which requires relatively dense fish populations will have to include feeding regimes to support those populations.

10.9.3 It has been posited that the water quality will have to be improved by forms of aeration requiring energy demanding options. Not enough detailed studies have been done so far to determine the variations in the water quality and the means by which it can be improved to acceptable high stock production levels.

10.9.4 Tractor powered PTO driven units have been offered as suitable means of achieving the optimal oxygen levels in the initial stages and could evolve into the more sophisticated aeration systems. The harvesting operations may dictate that there should be actual modification of the existing bed layout used for cultivating sugar cane and may become more attractive as the expansion proceeds.

10.9.5 Fortunately the supply of water or the drainage of the production ponds ought not to be critical factors as has been experienced in other aquaculture enterprises. Like the livestock proposals, sections of the cultivations temporarily abandoned especially in the Demerara Estates can be started as pilot projects preferably with private investment proposals.

11- Summary – Significant Observations and Recommendations

11.1. General

11.1.2 Since 2009 there has been a precipitate decline in cane yield and sugar output. Unsettled weather has not been a factor.

11.1.3 Restricted cash flows and poor credit arising from high expenditure on issues associated with the new Skeldon factory have led to reduced spending on inputs for agriculture.

11.1.4 There were reports of several instances of deviation from established guidelines for sound agricultural management. These have included, superficial tillage, planting outside of the recommended planting windows, and late timing of inputs.

11.1.6 -Attempts made to adjust fertilisation policy by reducing the rates of basal fertiliser contributed to a significant yield reductions in the succeeding seasons.

11.1.7. Severe weed infestation in East Demerara, Wales and Uitvlugt Estates have occurred because of poor management of inputs and neglect of the cultivation

11.1.8 The practice of bringing forward canes to achieve production targets, appears to have become institutionalised as a standard practice over the past 5 years. This practice not only sacrifices the potential production that may have resulted from harvesting those canes at maturity, it also risks compromising the subsequent development from those areas by exposure of the young developing stools to end of season rainfall and in some cases having adverse physiological impacts for subsequent crops.

11.1.9 Shortage of cash resulted in non- availability of fertilizer for over 6000 ha after completion of the 2015 First Crop

11.1.10. Subventions totalling G\$12B were allocated from the Central Government to support the Sugar Industry operating expenses.

11.1.11 *Central Government support will be necessary in the foreseeable short term, it is recommended the level of support should be agreed for the commencement of the production year and expenditure on agriculture should be linked to the attainment of progressive targets for a plan of improved production on each estate.*

11.1.12 *Emphasis of this programme will include adherence to agriculture guidelines on timing of operations and inputs, work quality, training and experience sharing, feedback from field inspection and surveillance to be included in planning for daily work programmes, resuscitation of seed nurseries and adherence to variety distribution agreed with the Breeding and Selection Dept.*

11.1.13 *Estates' management will be accountable for attainment of production targets for individual estate*

11.1.14 *The appointment of a Director of Agriculture is recommended. This individual would be ultimately accountable for attainment of the agriculture production objectives. The Director and his team would identify and address weaknesses in estates' efforts, including training, and will provide the leadership for the necessary changes required to modernize the Guyana Sugar Industry*

11.2 Production and Cost

11.2.1. With the information that financial support would continue to be provided for operating expenditure and justified critical capital, estimates of cane and sugar production were projected up to 2025. The projected expenditure US\$ 29M is significantly less than the requirement of US\$ 68 M.

11.2. 2. It is forecast that 3.5M tonnes of cane and 300,000 tonnes of sugar should be produced by 2020. This would increase to 3.8M tonnes of cane and 326,000 tonnes of sugar by 2025. Acquisition of new tillage equipment in 2016 and 2017 would enable the attainment of 3.5M tonnes of cane by 2019. The production of 3.8M tonnes of cane should be viewed as an indicator of steady state production. These estimates are of the same order of magnitude as those submitted by Guysuco.

11.2.3. Analyses of the production cost indicated that by 2020, average Industry agriculture cost of production should be 20¢ per pound of sugar. **In this scenario, even the lower cost Albion and Blairmont estates at 17¢ and 18¢ per pound respectively would not be profitable in the post 2017 European market for raw sugar.**

11.2.3. It is concluded that the production of raw sugar for export would not guarantee a sustainable future for the Guyana Sugar Industry

11.2.3 *It was recommended that the production of power for export should be considered for each factory. It is envisaged that the exported power would be seasonal. This project would require commitment on a Feed In Tariff (FIT) from GPL.*

11.2.4 *The production of food grade Plantation white sugar using a new technology, Ultra Filtration is also recommended for further consideration. There is a potential market of 200,000 tonnes for white sugar in CARICOM*

11.2.5 The 2020 production cost data also indicated that at prices for raw sugar, it would be cheaper for the Wales factory to purchase cane from farmers than to cultivate its own cane.

11.2. 6 It is also evident from the cane production estimates that there would be insufficient cane in West Demerara to satisfy the complete requirements for two factories.

11.2.7. *On this evidence, it is recommended that a formal evaluation of the financial implications for Guysuco and the farmers of transferring all of the Wales cane supply to farmers. The actual cost of production for farmers' canes would be an important factor for*

this work. The evaluation should also consider the feasibility of rationalising the West Demerara cane production around one factory.

11.3. Cane Farming

11.3.1 *The development of mechanised Cane Farming at Skeldon from 2007 has had more than its fair share of challenges combined with new Factory technology. This initial investment by private Cane Farmers was plagued by harvesting schedules way outside the original plan and by a relatively chronic erratic Factory Performance.*

11.3.2. *Other forms of private Cane Farmers investment initiated at Wales and Uitvlugt Estates in 2011 encouraged farmers to plant cane on the Estate temporary abandoned lands (TAB) and this should be analysed for the economic and financial returns.*

11.4 Skeldon Issues

11.4.1. Skeldon has experienced difficulty in harvesting its standing crop because of restricted access to fields and forced harvesting in wet soil conditions for successive seasons, with consequent soil compaction and damage to cane stools. Unreliability of the Factory has influenced late starts and reduced the crop duration. As a result has been increasing areas of over-age canes in both the estate' and farmers' cultivations.

11.4.2 These problems were influenced by inadequate drainage capacity for the expanded area and the fundamental error made from the onset of the programme in which only cursory attention was paid to land levelling.

11.4.3. In 2015 a 340 TPM drainage pump was installed by the NDIA on the banks of the Canje to drain the Manarabisi sections of the cultivation. The drainage canal to the estate at Sookram's Cross remains to be completed.

11.4.4. *It is recommended that Guysuco actively pursue the construction of the canal during the 2015 dry season and undertake the task if there is a delay in approval for funding from the NDIA.*

11.4.5. *Land levelling will be conducted on all fields scheduled for rehabilitation commencing the Second Crop of 2015. Guysuco has been advised to arrange for on-site training on operation and survey methods and interpretation by the laser system supplier.*

11.5- Mechanisation

11.5.1.. Mechanical loading of hand cut cane has been widely accepted by labour and is now the main contributor to the supply of cane. The task allows for greater harvesting productivity

and potential earnings. The rate of compensation for the practice has overestimated the effort and time involved for the output.

11.5.2 *An additional 15% of the set cut and load rate is paid to compensate for stacking that was intended to include field difficulties. This has been overlooked in practice. It is recommended that Guysuco should work with the Union to eliminate the additional payments for obstacles and extras still incurred in cut and Stack*

11.5.3. Progress has been made with the development of a commercial combine harvesting operation. At the commencement of operations at Skeldon, there were unfortunately several breakdowns and mechanical failures that could have been avoided if the mechanization support term had not been disbanded.


11.5.4. The advent of mechanically harvested and loaded canes has proven a challenge to the factories. Extraneous matter and excess soil from the field cause major problems with steam generation and processing.

11.5.5. Machine traffic in wet soil results in soil compaction, stool loss and inevitably has impacted on yield decline on fields so affected.

11.5.6. These problems and other issues will have to be solved and managed for this mode of operation to be adapted to the conditions that will prevail in coastal Guyana.

11.5.7. *The appointment of an experienced senior Agricultural Engineer as Mechanisation Coordinator is recommended.* This individual would co-opt as required, competent persons within the Industry to work with him in addressing the several technical and system development areas required for a robust and sustainable mechanised industry.

11.5.8. *The beneficial cost impacts of mechanization on various operations are already being reflected in the Industry Management Accounts. The transformation of the Industry to one in which the mechanized option becomes the method of choice will largely depend on the adaptability of the Management and Supervisory staff. It is recommended that the Industry seeks to recruit Mechanical Engineering graduates into the Field technical streams. On estates with a high extent of mechanization the following structure is proposed for the senior Agriculture organization:*



This structure simplifies the current Field Management structure and places greater emphasis on technology than people management. The Engineering Manager would be an experienced Agriculture Engineer and would through his reports hold responsibility for harvesting tillage and maintenance of the estates' infrastructure. The Crop Manager would also be required to be conversant with the application of machines to crop management such as planting, application of fertilizers and agrichemicals and cultivation. .

11. 6 Agriculture Procurement

11.6.1 The main agricultural items were identified as Fertiliser, Steel Plates mechanical spares, and Agrochemicals. The tender system is not really competitive as the number of compliant bids that satisfy the Corporation's payment terms rarely exceeds two. Those agencies remaining have been sympathetic to the financial constraints of the Corporation but still require payment upfront before delivery of the orders.

11.6.2 Unfortunately the delays in supplies have compromised too many of the routine operations which have been manifested by a combination of desperate alternatives in order to maintain sugar in the bag.

11.7. Research

11.7.1. The value of the Research Dept. and its potential for contribution to the operations of the Industry in a difficult period has been largely ignored. Support for capacity building such as subscriptions to journals and professional associations for the Technical staff were withdrawn

11.7.2 There has been no new commercial variety released to the industry since 2008, although 27 varieties have been released to estates for Stage VI evaluation. A major variety D93409 is being withdrawn from cultivation because of the smut disease. Two older varieties DB66113 and D7661 have been re-introduced to replace it. This is not a positive development.

11.7.3 *It is recommended that the Dept. and estates progress the pre-commercial and factory response evaluations on D 9584 and D 98633. One or both of these could gain acceptance within the cultivation as commercial canes.*

11.7.4 *This Dept. will need strong support from the Executive management if it is to effectively discharge its role. It is only fair that a decision be taken on the status of the Head of Research who has been acting for the past six years.*

11.8 Weather

11.8.1 Global Climatic Trends predict a drier climate for coastal Guyana, with more intense rainfall events in the wet seasons and extended droughty conditions in the dry seasons. The sugar industry has been a collaborator in the work leading to these predictions. The Industry and crop would be in a position to adapt to these changes

11.8.2. *Analyses of rainfall trends over the past two decades indicates that the middle of August would be the appropriate time for Estates to commence operations in the "Second Crop". In order to take advantage of the driest weeks of the year, a production schedule extending from mid-August to the end of April could be evaluated. Production would stop from the late December and January, but factories would be kept in readiness for continued operations as soon as the weather permits*

11.9. Environment

11.9.1. The International Agency for Research on Cancer (IARC) of the World Health Organisation (WHO) has listed 2,4D Amine and Glyphosate as possible carcinogens. These are the two most widely used agrichemicals in the Guyana Sugar Industry.

11.9.2. **The IARC findings on both chemicals have been disputed by several independent scientific studies and are not supported by the Environmental Regulatory Agencies of major Agricultural countries including the USA and Europe.** The controversy will very likely continue for the next several years.

11.9.3 *Small Industries like Guyana will have to act in their best Interests and keep a close eye on these developments. The available evidence on all positions should be made available to interested parties. In the meanwhile the Research Dept. would be required to search for and evaluate effective replacement chemicals.*

11.10. Diversification

11.10.1. *The production of fuel ethanol was considered using the production parameters of previous studies in 2005 and 2008. **The low prices of oil and its related products at this time are not in favour of substituting sugarcane nor molasses to fuel ethanol production.***

11.10.2. *Power export by cogeneration is the most stable value added product from sugarcane. The example of Mauritius is considered an example of a sugar Industry that has*

been transformed to a major power generation company. This project is discussed in Section 13 of the Factories Report.

11.10.3. The production of other crops on an extended scale will not engage the Field labour that is likely to be displaced by any form of contraction of field operations on any estate

11.10.4. Livestock in the form of Beef herds can be a viable option especially for estate cultivations with temporary abandoned lands without compromising the residual sugarcane production and factory supply. Aquaculture could be considered similarly but will require further feasibility study for a commercial operation.

11.11. Overall Recommendation

This study considers that with dedicated management and attention to detail, agriculture output will improve to acceptable levels. To secure stable agriculture performance additional Capital investment of US\$76.3M has been identified in addition to routine capital and maintenance requirements. The State has clearly stated that it will be unable to sustain subsidisation at these levels. The cost analyses for agriculture production indicate that no estate would be profitable at projected prices for raw sugar. It would therefore be necessary for economic value added production for a viable and sustainable future. Our study recognises the potential value of Cogeneration and power export as well as the opportunities that food grade white should present for markets within the region. These projects would entail significant capital investment that will be unavailable from the public funds. We therefore conclude that private investment and ownership is the way forward to transforming the Sugar Industry into a modern progressive business.

Bibliography:

Autrey, J.C. (2004) The re-engineering of the Mauritius Sugar Industry. Proceedings 28th WIST, Barbados

Autrey, J.C (2004) Co-generation plants in Mauritius. Proceedings 28th WIST, Barbados

Caribbean Development Bank (2014) Appraisal Report of Sugar Industry Development project-Guyana

Davis, H, Stuart, L and Bhim, P (2005) Potential for Fuel Ethanol in Guyana. Proceedings ISSCT 25th Congress, Guatemala

Davis, H.B., Friday, N.W and Dey, A.D (2005) Progress with mechanising field operations in the Guyana Sugar Industry. Proceedings ISSCT 25th Congress, Guatemala.

De Roos, A.J, Blair, A, Ruseicki, J.A, Hoppin, J.A, Svec, M, Dosemici, M, Sandler, D.P and Alavanja, M.C (2005) Cancer Incidence among Glyphosate exposed pesticide applicators in the Agricultural Health Study. Environmental Health Perspectives 113, 49-54.

GUYSUCO Agriculture Research Dept., (2008) Rodent Management manual

GUYSUCO Agrichemicals Safety Committee (1996) The safe use of pesticides

GUYANA – Second National Communication to the United Nations Framework Convention on Climate Change (UNFCCC), (2012), www.icds.gov.gy

Health Canada – Pest Management Regulatory Agency (2013) Re-evaluation update 2,4-D

Horta, L.A, and Coviello, M (2008) Biofuels in Guyana. Economic Commission for Latin America and the Caribbean (ECLAC)

International Agency for Research on Cancer (IARC) 2015 – Evaluation of five organophosphate insecticides and herbicides. IARC Monograph 112.

Kier, L.D and Kirkland, D.J (2013) Review of genotoxicity of glyphosate and glyphosate based formulations. Critical Reviews in Toxicology 43:4, 283-315.

Lau A.F, Kong Win Chan, K.T.F, and Guinness, D (2003) Factors influencing surplus electricity produced in cogeneration plants. ISSCT Co-Products Workshop, Sao Paulo, Brazil

McSweeney C, New, M and Lizcano, G (2012) UNDP Climate Change Country Profile – Guyana, <http://country-profiles.geog.ox.ac.uk>

Panday, V (2013) Probable Issues affecting cane yield. Guysuco Report

Schinasi, L and Leon M.E, (2014) Non Hodgkin Lymphoma and occupational exposure in agricultural pesticide chemical groups and active ingredients- a systemic review and meta-analysis. Int. J. of Environmental Research and Public Health 11 (4) 4449 -4527

Appendix 1

Industry Production Trends

Estate	Estate						Farmers						Industry Total						
	Harvest area (ha)	Tonnes sugar	Tonnes cane	tc/ha	ts/ha	tc/ts	Harvest area (ha)	Tonnes sugar	Tonnes cane	tc/ha	ts/ha	tc/ts	Harvest area (ha)	Tonnes sugar	Tonnes cane	tc/ha	ts/ha	tc/ts	
Year 2015																			
Skeldon	8,039.6	30360	459,395	57.14	3.78	15.13	2,408.1	8454	127,253	52.84	3.51	15.05	10,447.7	38,814	586,648	56.15	3.72	15.11	
Albion	8,964.5	54331	589,024	65.71	6.06	10.84	120.9	624	8174	67.61	5.16	13.10	9,085.4	54,955	597,198	65.73	6.05	10.87	
Rose Hall	6,305.1	28884	364,423	57.80	4.58	12.62	646.3	3069	40694	62.96	4.75	13.26	6,951.4	31,953	405,117	58.28	4.60	12.88	
Blairmont	5,732.3	35152	402,873	70.28	6.13	11.46	127.8	396	5,022	39.29	3.10	12.68	5,732.3	35,152	402,873	70.28	6.13	11.46	
Enmore	4,389.5	18928	231,484	52.74	4.31	12.23	2362.8	11009	139,034	58.84	4.66	12.63	4,517.3	19,324	236,506	52.36	4.28	12.24	
LBI	2,693.8	10060	127,048	47.16	3.73	12.63	66.8	267	3,592	53.78	3.99	13.46	2,760.6	10,327	130,641	47.32	3.74	12.65	
Wales	2739.6	10214	124,730	45.53	3.73	12.21	352.8	2299	30,524	86.52	6.52	13.28	5,102.4	21,223	263,764	51.69	4.16	12.43	
Ulivlught	3,934.8	13396	174,816	44.43	3.40	13.05	6,065.5	25,117	354,293	55.22	4.29	13.57	48,884.7	227,443	2,920,086	57.86	4.65	12.43	
INDUSTRY	42,799.2	201,327	2,473,793	57.80	4.70	12.29													

Estate	Estate						Farmers						Industry Total						
	Harvest area (ha)	Tonnes sugar	Tonnes cane	tc/ha	ts/ha	tc/ts	Harvest area (ha)	Tonnes sugar	Tonnes cane	tc/ha	ts/ha	tc/ts	Harvest area (ha)	Tonnes sugar	Tonnes cane	tc/ha	ts/ha	tc/ts	
Year 2016																			
Skeldon	8,358.7	33754	488,087	58.39	4.04	14.46	2,564.7	8621	129,312	50.42	3.36	15.00	10,923.4	42,375	617,399	56.52	3.88	14.57	
Albion	9,030.0	54954	616,092	68.23	6.09	11.21	127.9	630	7881	61.62	4.93	12.50	9,157.9	55,595	623,973	68.13	6.07	11.22	
Rose Hall	6,314.9	31062	395,573	62.64	4.92	12.74	646.7	2912	37,508.6	58.00	4.50	12.88	6,961.6	33,974	433,081	62.21	4.88	12.75	
Blairmont	5,666.2	33180	387,842	68.45	5.86	11.69							5,666.2	33,180	387,842	68.45	5.86	11.69	
Enmore	4,289.5	16964	221,826	51.71	3.95	13.08	183.5	608	8,346	45.48	3.31	13.73	4,473.0	17,572	230,172	51.46	3.93	13.10	
LBI	2,659.1	9934	141,652	53.27	3.74	14.26	53.0	94	1,325	25.00	1.76	14.17	2,712.1	10,027	142,977	52.72	3.70	14.26	
Wales	2934.4	11468	144,036	49.09	3.91	12.56	2370.1	10611	134,764	56.86	4.48	12.70	5,304.5	22,079	278,800	52.56	4.16	12.63	
Ulivlught	4,016.8	15625	205,862	51.25	3.89	13.18	639.6	3185	43,249	80.15	4.90	13.58	4,556.4	18,810	249,111	54.67	4.13	13.24	
INDUSTRY	43,269.6	206,951	2,500,970	60.11	4.78	12.57	6,485.5	26,661	362,385	55.88	4.11	13.59	49,755.1	233,612	2,963,356	59.56	4.70	12.68	

Estate	Estate						Farmers						Industry Total						
	Harvest area (ha)	Tonnes sugar	Tonnes cane	tc/ha	ts/ha	tc/ts	Harvest area (ha)	Tonnes sugar	Tonnes cane	tc/ha	ts/ha	tc/ts	Harvest area (ha)	Tonnes sugar	Tonnes cane	tc/ha	ts/ha	tc/ts	
Year 2017																			
Skeldon	8,482.0	39137	528,348	62.29	4.61	13.50	2,408.0	9288	130,032	54.00	3.86	14.00	10,890.0	48,425	658,380	60.46	4.45	13.60	
Albion	9,001.6	57432	626,010	69.54	6.38	10.90	128.0	635	7936	62.00	4.96	12.50	9,129.6	58,067	633,946	69.44	6.36	10.92	
Rose Hall	6,314.9	33203	415,032	65.72	5.26	12.50	646.0	2959	38760	60.00	4.58	13.10	6,960.9	36,161	453,792	65.19	5.19	12.55	
Blairmont	5,493.1	34125	385,615	70.20	6.21	11.30							5,493.1	34,125	385,615	70.20	6.21	11.30	
Enmore	4,472.3	19943	243,305	54.40	4.46	12.20	183.5	636	8,074	44.00	3.46	12.70	4,655.8	20,579	251,379	53.99	4.42	12.22	
LBI	2,758.0	12364	150,837	54.69	4.48	12.20	55.0	148	1,925	35.00	2.69	13.00	2,813.0	12,512	152,762	54.31	4.45	12.21	
Wales	3041.1	13794	166,911	54.89	4.54	12.10	2300.0	10222	128,800	56.00	4.44	12.60	5,341.1	24,017	295,711	55.37	4.50	12.31	
Ulivlught	4,110.0	17189	220,018	53.53	4.18	12.80	700.0	3977	52,500	75.00	5.68	13.20	4,810.0	21,166	272,518	56.66	4.40	12.88	
INDUSTRY	43,673.0	227,187	2,736,076	62.65	5.20	12.04	6,420.5	27,665	368,027	57.32	4.34	13.21	50,093.5	255,052	3,104,103	61.97	5.09	12.17	

Estate	Estate						Farmers						Industry Total						
	Harvest area (ha)	Tonnes sugar	Tonnes cane	tc/ha	ts/ha	tc/ts	Harvest area (ha)	Tonnes sugar	Tonnes cane	tc/ha	ts/ha	tc/ts	Harvest area (ha)	Tonnes sugar	Tonnes cane	tc/ha	ts/ha	tc/ts	
Year 2018																			
Skeldon	8,482.0	43330	563,284	66.41	5.11	13.00	2,500.0	10185	137,500	55.00	4.07	13.50	10,982.0	53,515	700,784	63.81	4.87	13.10	
Albion	9,001.6	59385	647,300	71.91	6.60	10.90	128.0	625	7808	61.00	4.88	12.50	9,129.6	60,010	655,108	71.76	6.57	10.92	
Rose Hall	6,314.9	35008	437,603	69.30	5.54	11.50	646.0	2982	38760	60.00	4.62	13.00	6,960.9	37,990	476,363	68.43	5.46	12.54	
Blairmont	5,493.1	36133	397,465	72.36	6.58	11.00							5,493.1	36,133	397,465	72.36	6.58	11.00	
Enmore	4,472.3	21979	263,752	59.97	4.91	12.00	183.0	634	8,052	44.00	3.46	12.70	4,655.3	22,613	271,804	58.39	4.86	12.02	
LBI	2,798.0	13434	161,206	57.61	4.80	12.00	55.0	172	2,200	40.00	3.13	12.80	2,853.0	13,606	163,406	57.28	4.77	12.01	
Wales	3066.1	15589	187,072	61.01	5.08	12.00	2300.0	10304	128,800	56.00	4.48	12.50	5,366.1	25,893	315,872	58.86	4.83	12.20	
Ulivlught	4,160.0	18893	238,051	57.22	4.54	12.60	850.0	4708	61,200	72.00	5.54	13.00	5,010.0	23,601	298,251	59.73	4.71	12.68	
INDUSTRY	43,788.0	245,752	2,895,732	66.13	5.57	11.88	6,652.0	29,609	384,320	57.69	4.44	12.98	50,450.0	273,361	3,280,052	65.02	6.42	12.00	

Estate	Estate						Farmers						Industry Total						
	Harvest area (ha)	Tonnes sugar	Tonnes cane	tc/ha	ts/ha	tc/ts	Harvest area (ha)	Tonnes sugar	Tonnes cane	tc/ha	ts/ha	tc/ts	Harvest area (ha)	Tonnes sugar	Tonnes cane	tc/ha	ts/ha	tc/ts	
Year 2019																			
Skeldon	8,532.0	46717	597,972	70.09	5.48	12.80	2,600	10947	145,600	56.00	4.21	13.30	11,132.0	57,664	743,572	66.80	5.18	12.89	
Albion	9,001.6	61088	665,856	73.97	6.79	10.90	128.0	625	7808	61.00	4.88	12.50	9,129.6	61,712	673,664	73.79	6.76	10.92	
Rose Hall	6,314.9	36630	457,877	72.51	5.80	12.50	646.0	2982	38780	60.00	4.62	13.00	6,960.9	39,612	496,637	71.35	5.69	12.54	
Blairmont	5,493.1	39168	430,851	78.43	7.13	11.00							5,493.1	39,168	430,851	78.43	7.13	11.00	
Enmore	4,472.3	23807	283,303	63.35	5.32	11.90	95.0	392	4,940	52.00	4.13	12.60	4,567.3	24,199	288,243	63.11	5.30	11.91	
LBI	2,798.0	14393	171,280	61.22	5.14	11.90	55.0	173	2,200	40.00	3.15	12.70	2,853.0	14,567	173,480	60.81	5.11	11.91	
Wales	3,091.1	17214	204,841	66.27	5.57	11.90	2300.0	10573	131,100	57.00	4.60	12.40	5,391.1	27,796	335,941	62.31	5.15	12.09	
Utilvult	4,190.0	20189	252,366	60.23	4.82	12.50	1,000.0	5349	69,000	69.00	5.35	12.90	5,190.0	25,538	321,366	61.92	4.92	12.58	
INDUSTRY	43,893.0	258,206	3,064,346	69.81	5.91	11.82	6,824.0	31,040	389,408	58.53	4.55	12.87	60,717.0	290,246	3,463,764	68.30	5.72	11.93	

Estate	Estate						Farmers						Industry Total						
	Harvest area (ha)	Tonnes sugar	Tonnes cane	tc/ha	ts/ha	tc/ts	Harvest area (ha)	Tonnes sugar	Tonnes cane	tc/ha	ts/ha	tc/ts	Harvest area (ha)	Tonnes sugar	Tonnes cane	tc/ha	ts/ha	tc/ts	
Year 2020																			
Skeldon	8,532.0	48891	625,805	73.35	5.73	12.80	2,600	10947	145,600	56.00	4.21	13.30	11,132.0	59,838	771,405	69.30	5.38	12.89	
Albion	9,001.6	62170	677,653	75.28	6.91	10.90	128.0	614	7680	60.00	4.80	12.50	9,129.6	62,784	685,333	75.07	6.88	10.92	
Rose Hall	6,314.9	37702	471,271	74.63	5.97	12.50	646.0	2982	38760	60.00	4.62	13.00	6,960.9	40,683	510,031	73.27	5.84	12.54	
Blairmont	5,493.1	40441	444,851	80.98	7.36	11.00							5,493.1	40,441	444,851	80.98	7.36	11.00	
Enmore	4,472.3	25751	301,288	67.37	5.76	11.70	95.0	392	4,940	52.00	4.13	12.60	4,567.3	26,143	306,228	67.05	5.72	11.71	
LBI	2,798.0	15412	183,402	65.55	5.51	11.90	55.0	173	2,200	40.00	3.15	12.70	2,853.0	15,585	185,602	65.06	5.46	11.91	
Wales	3,111.1	17993	214,117	68.82	5.78	11.90	2300.0	10573	131,100	57.00	4.60	12.40	5,411.1	28,566	345,217	63.80	5.28	12.09	
Utilvult	4,230.0	21384	267,300	63.19	5.06	12.50	1,000.0	5349	69,000	69.00	5.35	12.90	5,230.0	26,733	336,300	64.30	5.11	12.58	
INDUSTRY	43,953.0	269,744	3,185,687	72.48	6.14	11.81	6,824.0	31,030	389,280	58.51	4.55	12.87	60,777.0	300,774	3,584,967	70.60	5.92	11.92	

Estate	Estate						Farmers						Industry Total						
	Harvest area (ha)	Tonnes sugar	Tonnes cane	tc/ha	ts/ha	tc/ts	Harvest area (ha)	Tonnes sugar	Tonnes cane	tc/ha	ts/ha	tc/ts	Harvest area (ha)	Tonnes sugar	Tonnes cane	tc/ha	ts/ha	tc/ts	
Year 2021																			
Skeldon	8,532.0	50143	641,824	75.23	5.88	12.80	2,700	11571	153,900	57.00	4.29	13.30	11,232.0	61,714	795,724	70.84	5.49	12.89	
Albion	9,001.6	63667	687,599	76.39	7.07	10.80	128.0	614	7680	60.00	4.80	12.50	9,129.6	64,281	695,279	76.16	7.04	10.82	
Rose Hall	6,314.9	38651	475,404	75.28	6.12	12.30	646.0	3005	38760	60.00	4.65	12.90	6,960.9	41,655	514,164	73.86	5.98	12.34	
Blairmont	5,493.1	42516	459,178	83.59	7.74	10.80							5,493.1	42,516	459,178	83.59	7.74	10.80	
Enmore	4,472.3	26832	313,932	70.19	6.00	11.70	95.0	392	4,940	52.00	4.13	12.60	4,567.3	27,224	318,872	69.82	5.96	11.71	
LBI	2,798.0	15964	189,970	67.89	5.71	11.90	55.0	173	2,200	40.00	3.15	12.70	2,853.0	16,137	192,170	67.36	5.66	11.91	
Wales	3,111.1	18477	219,873	70.67	5.94	11.90	2300.0	11129	138,000	60.00	4.84	12.40	5,411.1	29,606	357,873	66.14	5.47	12.09	
Utilvult	4,230.0	22558	277,460	65.59	5.33	12.30	1,000.0	5976	75,900	69.00	5.43	12.70	5,330.0	28,534	353,360	66.30	5.35	12.38	
INDUSTRY	43,953.0	278,806	3,255,240	74.29	6.34	11.71	7,024.0	32,861	421,380	59.99	4.68	12.82	60,977.0	311,868	3,886,920	72.32	6.11	11.83	

Estate	Estate						Farmers						Industry Total						
	Harvest area (ha)	Tonnes sugar	Tonnes cane	tc/ha	ts/ha	tc/ts	Harvest area (ha)	Tonnes sugar	Tonnes cane	tc/ha	ts/ha	tc/ts	Harvest area (ha)	Tonnes sugar	Tonnes cane	tc/ha	ts/ha	tc/ts	
Year 2022																			
Skeldon	8,532.0	50748	649,574	76.13	5.95	12.80	2,800	12000	159,600	57.00	4.29	13.30	11,332.0	62,748	809,174	71.41	5.54	12.90	
Albion	9,001.6	64022	691,432	76.81	7.11	10.80	128.0	614	7680	60.00	4.80	12.50	9,129.6	64,636	699,112	76.58	7.08	10.82	
Rose Hall	6,314.9	38996	479,646	75.95	6.18	12.30	646.0	3005	38760	60.00	4.65	12.90	6,960.9	42,000	518,406	74.47	6.03	12.34	
Blairmont	5,493.1	43765	472,658	86.05	7.97	10.80							5,493.1	43,765	472,658	86.05	7.97	10.80	
Enmore	4,472.0	27501	321,760	71.95	6.15	11.70	95.0	392	4,940	52.00	4.13	12.60	4,567.0	27,893	326,700	71.53	6.11	11.71	
LBI	2,798.0	16415	195,344	69.82	5.87	11.90	55.0	173	2,200	40.00	3.15	12.70	2,853.0	16,589	197,544	69.24	5.81	11.91	
Wales	3,111.1	18755	223,184	71.74	6.03	11.90	2300.0	11129	138,000	60.00	4.84	12.40	5,411.1	29,884	361,184	66.75	5.52	12.09	

Ulivlught	4,230.0	23159	284,850	67.34	5.47	12.30	1,100.0	5976	75,900	69.00	5.43	12.70	5,330.0	29,135	360,750	67.68	5.47	12.38
INDUSTRY	43,952.7	283,359	3,318,448	76.50	6.45	11.71	7,124.0	35,290	427,080	59.95	4.67	12.53	51,076.7	316,649	3,745,528	73.33	6.20	11.83

Estates	Estate						Farmers						Industry Total						
	Harvest area (ha)	Tonnes sugar	Tonnes cane	tc/ha	ts/ha	tc/ts	Harvest area (ha)	Tonnes sugar	Tonnes cane	tc/ha	ts/ha	tc/ts	Harvest area (ha)	Tonnes sugar	Tonnes cane	tc/ha	ts/ha	tc/ts	
Year 2023																			
Skeldon	8,532.0	51012	652,948	76.53	5.98	12.80	2,950	12865	171,100	58.00	4.36	13.30	11,482.0	63,876	824,048	71.77	5.56	12.90	
Albion	9,001.0	64074	691,994	76.88	7.12	10.80	128.0	614	7680	60.00	4.80	12.50	9,129.0	64,688	699,674	76.64	7.09	10.82	
Rose Hall	6,314.9	38996	479,646	75.95	6.18	12.30	646.0	3005	38760	60.00	4.65	12.90	6,960.9	42,000	518,406	74.47	6.03	12.34	
Blairmont	5,493.1	43799	473,030	86.11	7.97	10.80							5,493.1	43,799	473,030	86.11	7.97	10.80	
Enmore	4,472.0	27759	324,782	72.63	6.21	11.70	95.0	392	4,940	52.00	4.13	12.60	4,567.0	28,151	329,722	72.20	6.16	11.71	
LBI	2,798.0	16604	197,592	70.62	5.93	11.90	55.0	173	2,200	40.00	3.15	12.70	2,853.0	16,778	199,792	70.03	5.88	11.91	
Wales	3111.1	18835	224,135	72.04	6.05	11.90	2300.0	11129	138,000	60.00	4.84	12.40	5,411.1	29,964	362,135	66.92	5.54	12.09	
Ulivlught	4,230.0	23630	290,650	68.71	5.59	12.30	1,100.0	5976	75,900	69.00	5.43	12.70	5,330.0	29,606	366,550	68.77	5.55	12.38	
INDUSTRY	43,952.1	284,708	3,334,776	76.87	6.48	11.71	7,274.0	34,154	438,580	60.29	4.70	12.84	51,226.1	316,863	3,773,356	73.86	6.22	11.83	

Estates	Estate						Farmers						Industry Total						
	Harvest area (ha)	Tonnes sugar	Tonnes cane	tc/ha	ts/ha	tc/ts	Harvest area (ha)	Tonnes sugar	Tonnes cane	tc/ha	ts/ha	tc/ts	Harvest area (ha)	Tonnes sugar	Tonnes cane	tc/ha	ts/ha	tc/ts	
Year 2024																			
Skeldon	8,532.0	51012	652,948	76.53	5.98	12.80	3,050	13530	179,950	59.00	4.44	13.30	11,582.0	64,542	832,898	71.91	5.57	12.90	
Albion	9,001.0	64074	691,994	76.88	7.12	10.80	128.0	614	7680	60.00	4.80	12.50	9,129.0	64,688	699,674	76.64	7.09	10.82	
Rose Hall	6,314.9	38996	479,646	75.95	6.18	12.30	646.0	3005	38760	60.00	4.65	12.90	6,960.9	42,000	518,406	74.47	6.03	12.34	
Blairmont	5,493.1	43799	473,030	86.11	7.97	10.80							5,493.1	43,799	473,030	86.11	7.97	10.80	
Enmore	4,472.0	27882	326,220	72.95	6.23	11.70	95.0	392	4,940	52.00	4.13	12.60	4,567.0	28,274	331,160	72.51	6.19	11.71	
LBI	2,798.0	16692	198,632	70.99	5.97	11.90	55.0	173	2,200	40.00	3.15	12.70	2,853.0	16,865	200,832	70.39	5.91	11.91	
Wales	3111.1	18843	224,235	72.08	6.06	11.90	2300.0	11129	138,000	60.00	4.84	12.40	5,411.1	29,972	362,235	66.94	5.54	12.09	
Ulivlught	4,230.0	23787	292,580	69.17	5.62	12.30	1,100.0	5976	75,900	69.00	5.43	12.70	5,330.0	29,763	368,480	69.13	5.58	12.38	
INDUSTRY	43,952.1	285,084	3,339,284	76.98	6.49	11.71	7,374.0	34,820	447,430	60.68	4.72	12.85	51,326.1	319,904	3,786,714	73.78	6.23	11.84	

Estates	Estate						Farmers						Industry Total						
	Harvest area (ha)	Tonnes sugar	Tonnes cane	tc/ha	ts/ha	tc/ts	Harvest area (ha)	Tonnes sugar	Tonnes cane	tc/ha	ts/ha	tc/ts	Harvest area (ha)	Tonnes sugar	Tonnes cane	tc/ha	ts/ha	tc/ts	
Year 2025																			
Skeldon	8,532.0	51012	652,948	76.53	5.98	12.80	3,100	13752	182,900	59.00	4.44	13.30	11,632.0	64,763	835,848	71.86	5.57	12.91	
Albion	9,001.0	64074	691,994	76.88	7.12	10.80	128.0	614	7680	60.00	4.80	12.50	9,129.0	64,688	699,674	76.64	7.09	10.82	
Rose Hall	6,314.9	38996	479,646	75.95	6.18	12.30	646.0	3005	38760	60.00	4.65	12.90	6,960.9	42,000	518,406	74.47	6.03	12.34	
Blairmont	5,493.1	43799	473,030	86.11	7.97	10.80							5,493.1	43,799	473,030	86.11	7.97	10.80	
Enmore	4,472.0	27908	326,520	73.01	6.24	11.70	95.0	392	4,940	52.00	4.13	12.60	4,567.0	28,300	331,460	72.58	6.20	11.71	
LBI	2,798.0	16713	198,882	71.08	5.97	11.90	55.0	173	2,200	40.00	3.15	12.70	2,853.0	16,886	201,082	70.48	5.92	11.91	
Wales	3111.1	18843	224,235	72.08	6.06	11.90	2300.0	11129	138,000	60.00	4.84	12.40	5,411.1	29,972	362,235	66.94	5.54	12.09	
Ulivlught	4,230.0	23787	292,580	69.17	5.62	12.30	1,100.0	5976	75,900	69.00	5.43	12.70	5,330.0	29,763	368,480	69.13	5.58	12.38	
INDUSTRY	43,952.1	285,130	3,339,834	76.99	6.49	11.71	7,424.0	35,042	450,380	60.67	4.72	12.85	51,376.1	320,172	3,790,214	73.77	6.23	11.84	

Guyana Sugar Corporation Inc.
Production Forecast 2015 -2020
Albion

	Unit	2012	2013	2014	2015	2016	2017	2018	2019	2020	2023	2025
Cane yields (combines FF & P&P yields)												
Plants	tc/ha	59.06	75.05	83.76	79.62	85.00	87.00	88.00	89.00	90.00	96.00	97.00
1 ratoon	tc/ha	64.36	59.52	74.94	73.80	74.00	80.00	81.00	82.00	83.00	86.00	86.00
2 ratoon	tc/ha	58.15	58.12	58.71	67.66	70.00	70.00	75.00	75.00	77.00	78.00	79.00
3 ratoon	tc/ha	56.35	56.87	56.13	64.42	65.00	66.00	67.00	71.00	71.00	72.00	73.00
4 ratoon	tc/ha	47.18	61.60	60.66	57.26	61.00	62.00	63.00	64.00	67.00	67.00	68.00
5 ratoon	tc/ha	46.87	46.55	54.45	54.99	55.00	56.00	57.00	57.00	58.00	58.00	58.00
6 ratoon	tc/ha											
7+ ratoon	tc/ha											
mean potential	tc/ha	56.12	58.21	63.76	65.71	67.19	69.17	71.65	73.29	75.48	78.54	79.92
	tc/ha	75.00	83.00	83.00	83.00	83.00	83.00	83.00	83.00	83.00	83.00	83.00
Cane Production (combines FF & P & P yields)	tonne											
Plants	tonne	107,924	73,596	113,794	137,559	108,290	113,100	130,240	131,720	153,000	163,200	170,235
1 ratoon	tonne	131,637	107,199	85,523	99,874	135,494	110,240	117,450	133,660	135,290	159,100	165,550
2 ratoon	tonne	111,328	99,670	101,273	67,910	94,710	128,170	103,350	108,750	125,510	127,140	128,770
3 ratoon	tonne	74,321	108,936	90,538	81,813	65,260	89,298	122,677	97,838	102,950	117,360	118,990
4 ratoon	tonne	49,838	49,468	93,296	84,917	77,470	62,248	85,239	119,744	92,326	97,150	110,840
5 ratoon	tonne	86,248	75,554	82,987	116,953	130,350	119,616	86,070	68,001	70,412	43,036	25,056
6 ratoon	tonne	-	-	-	-	-	-	-	-	-	-	-
7+ ratoon	tonne	-	-	-	-	-	-	-	-	-	-	-
Estate cane production	tonne	561,296	514,423	567,411	589,026	611,574	622,672	645,026	659,713	679,488	706,986	719,441
Farmers' Cane Production	tonne	6,803	8,739	8,142	8,174	6,480	8,550	8,250	9,520	11,600	12,400	12,400
Total Cane Production	tonne	568,099	523,162	575,553	597,200	618,054	631,222	653,276	669,233	691,088	719,386	731,841
Percent estate canes	%	98.80	98.33	98.59	98.63	98.95	98.65	98.74	98.58	98.32	98.28	98.31
Percent farmers cane	%	1.20	1.67	1.41	1.37	1.05	1.35	1.26	1.42	1.68	1.72	1.69
Pol. % cane - Estate	%	11.00	11.00	10.74	11.20	11.20	11.30	11.30	11.30	11.30	11.30	11.50
Pol. % cane - Farmers	%	9.70	10.00	9.40	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00
Tc/Ts Estate Cane	tc/ts	10.49	11.03	11.24	10.97	10.90	10.50	10.30	10.30	10.30	10.20	10.20
Tc/Ts Farmers' Cane	tc/ts	12.74	14.26	13.29	12.39	12.50	12.50	12.50	12.50	12.50	12.50	12.50
Farmers' HA	Ha	131.0	125.50	121.90	119.40	120.00	150.00	150.00	170.00	200.00	200.00	200.00
TCHA (Farmers)	tc/ha	51.93	69.63	66.79	51.38	54.00	57.00	55.00	56.00	58.00	62.00	62.00
Sugar Production - Estate	tonne	53,508	46,644	50,467	53,692	56,108	59,302	62,624	64,050	65,970	69,312	70,533
Sugar Production - Farmers	tonne	534	613	612	660	518	684	660	762	928	992	992
Total sugar production	tonne	54,042	47,257	51,080	54,352	56,626	59,986	63,284	64,811	66,898	70,304	71,525
Vary Production												
Estate hectares harvested		10,002.6	8,837.9	8,899.6	8,964.5	9,102.0	9,002.0	9,002.0	9,002.0	9,002.0	9,002.0	9,002.0
Farmers hectares harvested		131.0	125.5	121.9	119.4	120.0	150.0	150.0	170.0	200.0	200.0	200.0
Total Hectares Harvested		10,133.60	8,963.40	9,021.50	9,083.90	9,222.00	9,152.00	9,152.00	9,172.00	9,202.00	9,202.00	9,202.00
Estate cane production		561,296	514,423	567,411	589,026	611,574	622,672	645,026	659,713	679,488	706,986	719,441
Farmers' Cane Production		6,803	8,739	8,142	8,174	6,480	8,550	8,250	9,520	11,600	12,400	12,400
Total Cane Production		568,099	523,162	575,553	597,200	618,054	631,222	653,276	669,233	691,088	719,386	731,841
Sugar Production - Estate		53,508	46,644	50,467	53,692	56,108	59,302	62,624	64,050	65,970	69,312	70,533
Sugar Production - Farmers		534	613	612	660	518	684	660	762	928	992	992
Total sugar production		54,042	47,257	51,080	54,352	56,626	59,986	63,284	64,811	66,898	70,304	71,525
		-	-	-	-	-	-	-	-	0.00	(0.00)	(0.00)
TOTAL TCH		56.06	58.37	63.80	65.74	67.02	68.97	71.38	72.96	75.10	78.18	79.53
TOTAL TCTS		10.51	11.07	11.27	10.99	10.91	10.52	10.32	10.33	10.33	10.23	10.23
TOTAL TSH		5.33	5.27	5.66	5.98	6.14	6.55	6.91	7.07	7.27	7.64	7.77

Guyana Sugar Corporation Inc.
Production Forecast 2015 - 2020
Blairmont

	2012	2013	2014	2015	2016	2017	2018	2019	2020	2023	2025
Cane yields (combines FF & P&P yields)											
Plants	77.55	78.921	86.26	79.87	84.00	86.00	88.00	90.00	92.00	97.00	103.00
1 ratoon	69.03	61.884	75.90	84.00	76.00	79.00	81.00	84.00	86.00	87.00	89.00
2 ratoon	60.61	55.774	64.68	69.28	78.00	74.00	75.00	76.00	80.00	82.00	80.00
3 ratoon	63.99	66.402	61.40	66.33	66.00	74.00	71.00	71.00	72.00	73.00	75.00
4 ratoon	61.02	55.188	61.03	63.42	63.00	64.00	69.00	66.00	67.00	69.00	71.00
5 ratoon	66.52	53.646	61.20	63.17	61.00	60.00	61.00	60.00	61.00	61.00	64.00
6 ratoon											
7+ ratoon											
mean	66.61	59.16	67.25	70.28	71.08	72.40	73.58	77.90	76.44	81.15	82.83
potential	85.00	85.00	85.00	85.00	85.00	85.00	85.00	85.00	85.00	85.00	85.00
Cane Production (combines FF & P & P yields)											
Plants	77,306	53,706	66,250	95,085	69,216	62,780	64,240	74,700	81,880	86,330	91,670
1 ratoon	83,883	60,807	60,095	54,802	101,080	76,156	70,470	73,080	83,420	84,390	86,330
2 ratoon	90,192	49,745	62,881	52,750	50,856	98,420	72,300	66,120	69,600	79,540	77,600
3 ratoon	45,084	82,432	42,704	52,125	50,226	48,248	94,430	68,444	62,640	70,810	72,750
4 ratoon	31,946	36,231	71,578	38,991	49,518	48,704	44,988	87,780	64,588	66,930	68,870
5 ratoon	80,489	62,766	76,882	109,126	69,540	63,360.00	57,767.00	57,767.00	57,767.00	57,767.00	57,767.00
6 ratoon											
7+ ratoon											
Estate cane production	408,901	345,687	380,390	402,878	390,436	397,668	404,195	427,891	419,895	445,767	454,987
Farmers' Cane Production											
Total Cane Production	408,901	345,687	380,390	402,878	390,436	397,668	404,195	427,891	419,895	445,767	454,987
Percent estate canes	100.00	100.00	100.00	100.00	100.00	100.00	100.00	100.00	100.00	100.00	100.00
Percent farmers cane											
Poi % cane - Estate	10.80	11.00	10.85	11.80	11.80	11.80	11.80	11.80	11.80	11.80	11.80
Tc/Ts Estate Cane	11.29	12.12	11.36	11.23	10.80	10.40	10.40	10.40	10.40	10.40	10.40
Tc/Ts Farmers' Cane											
Farmers' HA											
TCHA (Farmers)											
Sugar Production - Estate	36,218	28,528	33,499	35,872	36,151	38,237	38,865	41,143	40,375	42,862	43,749
Sugar Production - Farmers											
Total sugar production	36,218	28,528	33,499	35,872	36,151	38,237	38,865	41,143	40,375	42,862	43,749
Vary Production											
Estate hectares harvested	6,138.40	5,843.0	5,656.6	5,732.2	5,493.0	5,493.0	5,493.0	5,493.0	5,493.0	5,493.0	5,493.0
Farmers hectares harvested											
Estate cane production	408,900.94	345,687	380,390	402,878	390,436	397,668	404,195	427,891	419,895	445,767	454,987
Farmers' Cane Production											
Total Cane Production	408,900.94	345,687	380,390	402,878	390,436	397,668	404,195	427,891	419,895	445,767	454,987
Sugar Production - Estate	36,217.98	28,528	33,499	35,872	36,151	38,237	38,865	41,143	40,375	42,862	43,749
Sugar Production - Farmers											
Total sugar production	36,217.98	28,528	33,499	35,872	36,151	38,237	38,865	41,143	40,375	42,862	43,749
TOTAL TCH	66.61	59.16	67.25	70.28	71.08	72.40	73.58	77.90	76.44	81.15	82.83
TOTAL TCS	11.29	12.12	11.36	11.23	10.80	10.40	10.40	10.40	10.40	10.40	10.40
TOTAL TSH	5.90	4.88	5.92	6.26	6.58	6.96	7.08	7.49	7.35	7.80	7.96

Guyana Sugar Corporation Inc.
Production Forecast 2015 -2020
Enmore

	Unit	2012	2013	2014	2015	2016	2017	2018	2019	2020	2023	2025
Cane yields (combines FF & P&P yields)												
Plants	te/ha	79.44	76.80	67.56	3,823.10	75.00	78.00	82.00	84.00	86.00	89.00	91.00
1 ratoon	te/ha	58.85	64.00	57.20	56.41	67.00	70.00	73.00	76.00	78.00	80.00	83.00
2 ratoon	te/ha	51.22	50.74	48.16	51.34	53.00	63.00	66.00	69.00	72.00	72.00	73.00
3 ratoon	te/ha	47.99	53.38	44.25	49.10	48.00	50.00	60.00	63.00	66.00	67.00	68.00
4 ratoon	te/ha	39.84	47.12	46.47	45.25	46.00	46.00	48.00	54.00	60.00	60.00	62.00
5 ratoon	te/ha	41.85	49.56	43.77	51.00	47.00	46.00	48.00	50.00	52.00	53.00	57.00
7+ ratoon	te/ha											
mean potential	te/ha	53.88	55.26	49.92	52.90	54.16	56.56	60.83	64.83	68.67	73.13	75.31
	te/ha	80.00	80.00	80.00	80.00	80.00	80.00	80.00	80.00	80.00	80.00	80.00
Cane Production (combines FF & P & P yields)												
Plants	tonne	48,632.00	26,211.39	46,597.00	38,423.31	46,050.00	43,446.00	49,528.00	58,632.00	62,780.00	74,760.00	76,440.00
1 ratoon	tonne	48,307.00	35,863.39	39,684.73	21,717.85	42,344.00	49,980.00	47,961.00	53,504.00	62,244.00	75,200.00	78,020.00
2 ratoon	tonne	30,806.00	43,780.39	39,967.73	28,283.21	20,405.00	39,816.00	47,124.00	45,333.00	50,688.00	67,680.00	68,620.00
3 ratoon	tonne	31,833.00	34,927.39	38,383.73	33,810.26	26,448.00	19,250.00	37,920.00	44,982.00	43,362.00	55,610.00	63,920.00
4 ratoon	tonne	16,819.00	24,148.39	44,708.73	31,285.85	31,694.00	25,346.00	18,480.00	34,128.00	42,840.00	42,240.00	43,400.00
5 ratoon	tonne	28,859.00	25,456.00	53,316.73	76,867.20	75,247.00	75,118.00	71,040.00	53,350.00	45,188.00	11,554.00	6,384.00
6 ratoon	tonne											
7+ ratoon	tonne											
Estate cane production	tonne	205,256	190,387	262,659	230,388	242,188	252,956	272,053	289,929	307,102	327,044	336,784
Farmers' Cane Production	tonne	3,638	4,472	4,723	4,772	5,369	6,862	4,940	5,320	5,320	5,320	5,320
Total Cane Production	tonne	208,894	194,859	267,382	235,160	247,557	259,818	276,993	295,249	312,422	332,364	342,104
Percent estate canes	%	98.26	97.71	98.23	97.97	97.83	97.47	98.22	98.20	98.30	98.44	98.44
Percent farmers cane	%	1.74	2.29	1.77	2.03	2.17	2.53	1.78	1.80	1.70	1.60	1.56
Pol % cane - Estate	%	9.80	9.10	9.00	10.20	10.20	10.50	11.00	11.00	11.00	11.00	11.00
Pol % cane - Farmers	%	9.80	9.80	9.80	9.80	9.80	9.80	10.00	10.00	10.00	10.00	10.00
Tc/18 Estate Cane	te/18	12.17	14.56	13.62	12.80	12.80	12.60	12.40	12.40	12.40	12.40	12.40
Tc/18 Farmers' Cane	te/18	15.71	15.37	13.64	13.00	13.00	12.80	12.80	12.80	12.80	12.80	12.80
Farmers HA	Ha	79.00	102.10	99.30	119.30	119.30	119.30	95.00	95.00	95.00	95.00	95.00
TCHA (Farmers)	te/ha	46.05	43.80	47.56	40.00	45.00	55.00	52.00	56.00	56.00	56.00	56.00
Sugar Production - Estate	tonne	16,866	13,077	19,290	17,999	18,921	20,076	21,940	23,381	24,766	26,375	27,160
Sugar Production - Farmers	tonne	232	291	346	367	413	513	386	416	416	416	416
Total sugar production	tonne	17,097	13,368	19,636	18,366	19,334	20,588	22,326	23,797	25,182	26,790	27,576
Vary Production												
Estate hectares harvested		3,809.60	3,445.0	5,261.2	4,355.5	4,472.0	4,472.0	4,472.0	4,472.0	4,472.0	4,472.0	4,472.0
Farmers hectares harvested		79.00	102.1	99.3	119.3	119.3	119.3	95.0	95.0	95.0	95.0	95.0
Total Hectares Harvested		3,888.60	3,547.10	5,360.50	4,474.80	4,591.30	4,591.30	4,567.00	4,567.00	4,567.00	4,567.00	4,567.00
Estate cane production		205,256	190,387	262,659	230,388	242,188	252,956	272,053	289,929	307,102	327,044	336,784
Farmers' Cane Production		3,638	4,472	4,723	4,772	5,369	6,862	4,940	5,320	5,320	5,320	5,320
Total Cane Production		208,894	194,859	267,382	235,160	247,557	259,818	276,993	295,249	312,422	332,364	342,104
Sugar Production - Estate		16,866	13,077	19,290	17,999	18,921	20,076	21,940	23,381	24,766	26,375	27,160
Sugar Production - Farmers		232	291	346	367	413	513	386	416	416	416	416
Total sugar production		17,097	13,368	19,636	18,366	19,334	20,588	22,326	23,797	25,182	26,790	27,576
TOTAL TCH		53.72	54.93	49.88	52.55	53.92	56.52	60.65	64.65	68.41	72.78	74.91
TOTAL TCFS		12.22	14.58	13.62	12.80	12.80	12.60	12.41	12.41	12.41	12.41	12.41
TOTAL TSH		4.40	3.77	3.66	4.10	4.21	4.48	4.89	5.21	5.51	5.87	6.04

Guyana Sugar Corporation Inc.
Production Forecast 2015-2020

	2012	2013	2014	2015	2016	2017	2018	2019	2020	2023	2025
Planting - FF - Commercial	-	150.00	485.00	475.00	475.00	475.00	425.00	425.00	425.00	425.00	425.00
Planting - FF - Dam bed seed	-	-	55.00	55.00	55.00	55.00	50.00	50.00	50.00	50.00	50.00
Planting - PP - Commercial	4,939.40	4,993.60	6,059.00	5,988.00	5,851.00	6,469.00	6,915.00	7,544.00	7,881.00	7,881.00	7,881.00
Planting - PP - Seed Cane	893.10	909.00	917.00	904.00	940.00	955.00	955.00	978.00	978.00	978.00	978.00
Total Planting	5,832.50	6,052.60	7,516.00	7,422.00	7,321.00	7,954.00	8,345.00	8,997.00	9,334.00	9,334.00	9,334.00
Estates' Hectares Harvested	43,615.95	40,703.85	45,302.36	42,745.20	43,479.00	43,378.00	43,328.00	43,411.00	43,411.00	43,411.00	43,411.00
Farmers' Hectares Harvested	5,386.90	5,287.40	5,667.42	5,786.40	6,178.30	6,438.30	6,875.70	7,195.70	7,325.70	7,325.70	7,325.70
Total Hectares Harvested	49,002.85	45,991.25	50,969.78	48,531.60	49,657.30	49,816.30	50,203.70	50,606.70	50,736.70	50,736.70	50,736.70
Estates' Canes Harvested	2,405,853	2,166,246	2,529,824	2,479,158	2,592,830	2,691,622	2,829,375	2,976,116	3,083,461	3,232,627	3,307,882
Farmers' Canes Harvested	303,505	294,836	307,074	325,538	356,071	384,544	414,291	441,720	454,550	454,550	454,550
Total Canes Harvested	2,709,358	2,461,082	2,836,898	2,804,696	2,948,901	3,076,166	3,243,666	3,417,836	3,538,011	3,719,165	3,802,820
Estates' Sugar Production	196,677	166,958	195,225	199,136	213,129	228,634	243,164	256,325	266,984	280,693	284,759
Farmers' Sugar Production	21,342	19,797	21,133	23,929	26,607	29,633	31,965	34,098	35,755	35,755	35,755
Total Sugar Production	218,019	186,755	216,358	223,064	239,736	258,266	275,130	290,423	302,739	319,013	326,132
Estates' tch	55.16	53.22	55.84	58.00	59.63	62.05	65.30	68.56	71.03	74.47	76.20
Farmers' tch	56.34	55.76	54.18	56.26	57.63	59.73	60.25	61.39	62.05	62.05	62.05
Total TCH	55.29	53.51	55.66	57.79	59.39	61.75	64.61	67.54	69.73	73.30	74.95
Estates' tcts	12.23	12.97	12.96	12.45	12.17	11.77	11.64	11.61	11.55	11.52	11.62
Farmers' tcts	14.22	14.89	14.53	13.60	13.38	12.98	12.96	12.95	12.71	12.71	12.71
Total TCTS	12.43	13.18	13.11	12.57	12.30	11.91	11.79	11.77	11.69	11.66	11.66
Estates' tsh	4.51	4.10	4.31	4.66	4.90	5.27	5.61	5.90	6.15	6.47	6.56
Farmers' tsh	3.96	3.74	3.73	4.14	4.31	4.60	4.65	4.74	4.88	4.88	4.88
Total TSH	€ 4.45	€ 4.06	€ 4.24	€ 4.60	€ 4.83	€ 5.18	€ 5.48	€ 5.74	€ 5.97	€ 6.29	€ 6.43

Guyana Sugar Corporation Inc.
Production Forecast 2015 -2020
Wales

	2012	2013	2014	2015	2016	2017	2018	2019	2020	2023	2025
Summary of areas											
Area in Canes											
Harvest	2,332.50	3,305.80	2,894.96		2,833.00	2,833.00	2,833.00	2,915.00	2,915.00	2,915.00	2,915.00
C/over,b/f	244.50										
Draw Down	30.00	84.20	65.00	65.00	65.00	65.00	65.00	65.00	65.00	65.00	65.00
Full 6 month fallow	-	-	120.00	30.00	30.00	30.00	30.00	30.00	30.00	30.00	30.00
Prepared land	363.90	392.20	418.80	120.00	120.00	120.00	120.00	120.00	120.00	120.00	120.00
Area in cultivation	3,356.10	3,356.10	3,356.10	3,356.10	3,356.10	3,356.10	3,356.10	3,356.10	3,356.10	3,356.10	3,356.10
Area in cul excl. F/fallow.@31/12	2,992.20	2,963.90	2,937.30	3,236.10	3,236.10	3,236.10	3,236.10	3,236.10	3,236.10	3,236.10	3,236.10
Flood Fallow prepared during the year											
Flood Fallow @31/12	-	-	120.00	85.00	85.00	85.00	30.00	30.00	30.00	30.00	30.00
Draw Down during the year	140.00	180.00	165.00	165.00	165.00	165.00	165.00	165.00	165.00	165.00	165.00
Planting during the year	566.60	512.20	484.90	580.00	620.00	620.00	672.00	672.00	672.00	672.00	672.00
% planting	17%	15%	14%	17%	18%	18%	20%	20%	20%	20%	20%
Flood Fallowing % planting	-	-	24.75	14.66	13.71	13.71	4.46	4.46	4.46	4.46	4.46
Planting from FF											
Commercial											
Dambed seed											
Total											
Planting P & P											
Commercial	516.60	462.20	284.00	450.00	490.00	490.00	597.00	597.00	597.00	597.00	597.00
Seed cane	50.00	50.00	30.00	45.00	45.00	45.00	45.00	45.00	45.00	45.00	45.00
Total	566.60	512.20	314.00	495.00	535.00	535.00	642.00	642.00	642.00	642.00	642.00
Total planting FF + P & P											
Check	566.60	512.20	434.00	580.00	620.00	620.00	672.00	672.00	672.00	672.00	672.00
%Planting											
% Seed Cane											
Putting land under water from FF											
FF Land											
Total mechanical Tillage											
Plants excl. seed canes											
1 ratoon	348.20	568.80	412.06	438.30	535.00	575.00	575.00	627.00	627.00	627.00	627.00
2 ratoon	737.20	397.60	607.70	330.50	468.00	580.00	620.00	620.00	620.00	620.00	620.00
3 ratoon	303.00	857.20	398.10	609.90	331.00	468.00	580.00	620.00	620.00	620.00	620.00
4 ratoon	305.20	550.30	441.40	311.70	610.00	331.00	468.00	580.00	620.00	620.00	620.00
5 ratoon	403.30	200.60	422.80	337.60	312.00	610.00	331.00	468.00	376.00	300.00	200.00
6 ratoon	235.60	731.30	612.90	689.20	627.00	319.00	309.00			196.00	
7+ ratoon											
Total	2,332.50	3,305.80	2,894.96	2,717.20	2,883.00	2,883.00	2,883.00	2,915.00	2,915.00	2,915.00	2,915.00

Guyana Sugar Corporation Inc.
Production Forecast 2015-2020
Wales

	Unit	2012	2013	2014	2015	2016	2017	2018	2019	2020	2023	2025
Cane yields (combines FF & P&P yields)				2,482.90								
Plants	te/ha											
1 ratoon	te/ha	77.30	68.33	80.10	79.11	80.00	82.00	84.00	86.00	86.00	91.00	91.00
2 ratoon	te/ha	56.71	54.97	43.13	66.11	67.00	68.00	72.00	74.00	76.00	76.00	76.00
3 ratoon	te/ha	43.23	44.40	38.70	38.61	59.00	60.00	61.00	65.00	66.00	67.00	68.00
4 ratoon	te/ha	47.79	32.89	34.47	30.20	36.00	36.00	51.00	51.00	51.00	62.00	64.00
5 ratoon	te/ha	40.30	43.60	37.62	42.60	38.00	38.00	38.00	-	51.00	51.00	52.00
6 ratoon	te/ha											
7+ ratoon	te/ha											
mean	te/ha	51.44	48.09	43.95	48.29	52.48	57.91	63.37	67.19	68.97	70.39	71.46
target	te/ha	76.00	84.00	84.00	84.00	84.00	84.00	84.00	84.00	84.00	84.00	84.00
Cane Production (combines FF & P & P yields)												
Plants	tonne	26,916.70	38,867.23	33,005.37	34,673.91	42,800.00	47,150.00	48,300.00	53,922.00	53,922.00	57,057.00	57,057.00
1 ratoon	tonne	41,805.97	21,858.03	26,208.12	21,849.36	31,356.00	39,440.00	44,640.00	45,880.00	51,072.00	51,072.00	51,072.00
2 ratoon	tonne	13,099.40	38,055.50	15,406.86	23,548.24	19,529.00	28,080.00	35,380.00	40,300.00	40,920.00	41,540.00	42,160.00
3 ratoon	tonne	9,383.88	21,698.29	14,982.14	11,595.24	22,570.00	18,205.00	25,740.00	31,900.00	35,960.00	31,000.00	38,400.00
4 ratoon	tonne	19,274.09	6,598.66	14,574.20	10,195.52	11,232.00	21,960.00	16,881.00	23,868.00	19,176.00	15,300.00	10,400.00
5 ratoon	tonne	9,495.76	31,887.07	23,055.45	29,359.92	23,826.00	12,122.00	11,742.00	-	-	9,212.00	9,212.00
6 ratoon	tonne											
7+ ratoon	tonne											
Estate cane production	tonne	119,976	158,965	127,232	131,222	151,313	166,957	182,683	195,870	201,050	205,181	208,301
Farmers' Cane Production	tonne	113,785	128,167	124,629	117,987	127,600	136,400	158,061	163,000	165,470	177,818	177,818
Total Cane Production	tonne	233,761	287,132	251,861	249,209	278,913.0	303,357.0	340,743.8	358,870.2	366,519.9	382,999.4	386,119.4
Percent estate canes	%	51.32	55.36	50.52	54.25	54.25	55.04	53.61	54.58	54.85	53.57	53.95
Percent farmers cane	%	48.68	44.64	49.48	47.34	45.75	44.96	46.39	45.42	45.15	46.43	46.05
Pol. % cane - Estate	%	10.30	9.76	9.39	10.00	10.20	10.20	10.20	10.20	10.20	10.20	10.20
Pol. % cane - Farmers	%	10.00	9.80	9.41	9.80	10.00	10.00	10.00	10.00	10.00	10.00	10.00
Tc/Is Estate Cane	te/Is	12.04	12.48	13.46	12.50	12.40	12.40	12.40	12.40	12.40	12.40	12.40
Tc/Is Farmers' Cane	te/Is	12.25	12.81	13.20	12.70	12.70	12.70	12.70	12.70	12.70	12.70	12.70
Farmers' HA	Ha	2,055.00	2,244.90	2,255.82	2,126.00	2,200.00	2,200.00	2,200.00	2,469.70	2,469.70	2,469.70	2,469.70
TCHA (Farmers)	te/ha	55.37	57.10	55.25	55.50	58.00	62.00	64.00	66.00	67.00	72.00	72.00
Sugar Production - Estate	tonne	9,965	12,742	9,456	10,498	12,203	13,464	14,733	15,796	16,214	16,547	16,798
Sugar Production - Farmers	tonne	9,289	10,004	9,441	9,290	10,047	10,740	12,446	12,835	13,029	14,001	14,001
Total sugar production	tonne	19,253	22,746	18,897	19,788	22,250	24,204	27,178	28,631	29,243	30,548	30,800
Vary Production												
Estate hectares harvested		2,332.5	3,305.8	2,895.0	2,717.2	2,883.0	2,883.0	2,883.0	2,915.0	2,915.0	2,915.0	2,915.0
Farmers hectares harvested		2,055.0	2,244.9	2,255.8	2,126.0	2,200.0	2,200.0	2,469.7	2,469.7	2,469.7	2,469.7	2,469.7
Total Hectares Harvested		4,387.50	5,550.70	5,150.78	4,843.20	5,083.00	5,083.00	5,352.70	5,384.70	5,384.70	5,384.70	5,384.70
Estate cane production		119,976	158,965	124,629	131,222	151,313	166,957.00	182,683.00	195,870.00	201,050.00	205,181.00	208,301.00
Farmers' Cane Production		113,785	128,167	124,629	117,987	127,600	136,400.00	158,060.80	163,000.20	165,470.00	177,818.00	177,818.00
Total Cane Production		233,761	287,132	251,861	249,209	278,913	303,357.00	340,743.80	358,870.20	366,520.00	382,999.00	386,119.00
Sugar Production - Estate		9,965	12,742	9,456	10,498	12,203	13,464.27	14,732.50	15,795.97	16,084.00	16,547.00	16,798.00
Sugar Production - Farmers		9,289	10,004	9,441	9,290	10,047	10,740.16	12,445.73	12,834.66	13,039.00	14,001.00	14,001.00
Total sugar production		19,253	22,746	18,897	19,788	22,250	24,204.43	27,178.23	28,630.63	29,243.00	30,548.00	30,800.00
										0.00	(0.00)	0.00
TOTAL TCH		53.28	51.73	48.90	51.46	54.87	59.68	63.66	66.65	68.07	71.13	71.71
TOTAL TCTS		12.14	12.62	13.33	12.59	12.54	12.53	12.54	12.53	12.53	12.54	12.54

Guyana Sugar Corporation Inc.
Production Forecast 2015-2020
Uitvlugt

	2012	2013	2014	2015	2016	2017	2018	2019	2020	2023	2025
Summary of areas											
Area in Cane											
Harvest	5,057.50	4,795.70	4,379.30	3,933.00	3,933.00	3,933.00	3,933.00	3,984.00	3,984.00	3,984.00	3,984.00
Cover,b/f											
Draw Down	50.00	100.00	90.00	90.00	90.00	90.00	90.00	90.00	90.00	90.00	90.00
Full 6 month fallow											
Prepared land	1,041.80	300.00	547.30	50.00	50.00	50.00	150.00	150.00	150.00	150.00	150.00
Area in cultivation	6,005.90	5,505.90	4,634.30	4,500.00	4,500.00	4,500.00	4,500.00	4,500.00	4,500.00	4,500.00	4,500.00
Area in cul excl. F/fallow @31/12	4,964.10	5,205.90	4,087.00	4,450.00	4,450.00	4,450.00	4,350.00	4,350.00	4,350.00	4,350.00	4,350.00
Flood Fallow prepared during the year											
Flood Fallow @31/12											
Draw Down during the year	120.00	280.00	300.00	250.00	225.00	225.00	225.00	225.00	225.00	225.00	225.00
Planting during the year	519.30	731.8	874.6	750.0	750.0	800.0	800.0	900.0	900.0	900.0	900.0
% planting	9%	13%	19%	17%	17%	18%	18%	20%	20%	20%	20%
Flood Fallowing % planting											
Planting from FF											
Commercial											
Dambed seed											
Total											
Planting P & P											
Commercial	469.30	656.80	771.60	675.0	675.0	720.0	720.0	797.0	797.0	797.0	797.0
Seed cane	50.00	75.00	103.00	75.0	75.0	80.0	80.0	103.0	103.0	103.0	103.0
Total	519.30	731.80	874.60	750.0	750.0	800.0	800.0	900.0	900.0	900.0	900.0
Total planting FF + P & P	519.30	731.80	874.60	750.0	750.0	800.0	800.0	900.0	900.0	900.0	900.0
Check	519.30	731.80	874.60	750.0	750.0	800.0	800.0	900.0	900.0	900.0	900.0
% Planting											
% Seed Cane											
Putting land under water from FF											
FF Land	0%	0%									
Total mechanical Tillage	519.30	649.00	891.20	750.00	750.00	800.00	800.00	900.00	900.00	900.00	900.00
Harvest area											
Plants excl. seed canes	937.70	518.6	659.80	860.90	675.00	675.00	720.00	720.00	797.00	797.00	797.00
1 ratoon	686.20	1,024.4	460.10	575.20	964.00	750.00	750.00	800.00	800.00	800.00	800.00
2 ratoon	717.10	756.3	944.30	405.90	575.00	964.00	750.00	750.00	800.00	800.00	800.00
3 ratoon	892.60	554.3	558.40	621.00	406.00	575.00	964.00	750.00	750.00	750.00	750.00
4 ratoon	791.60	773.6	455.00	402.00	621.00	406.00	575.00	964.00	750.00	700.00	700.00
5 ratoon	1,032.10	1,196.5	1,301.70	1,067.50	692.00	563.00	174.00	87.00	87.00	137.00	137.00
6 ratoon											
7+ ratoon											
Total	5,057.30	4,823.7	4,379.30	3,932.50	3,933.00	3,933.00	3,933.00	3,984.00	3,984.00	3,984.00	3,984.00

Gaviana Sugar Corporation Inc.
Production Forecast 2015 -2020
litivlugt

	2012	2013	2014	2015	2016	2017	2018	2019	2020	2023	2025
Cane yields (combines FF & P&P)											
Plants	62.98	56.03	54.85	61.42	65.00	68.00	70.00	72.00	75.00	83.00	85.00
1 ratoon	54.16	42.40	49.94	55.55	55.00	57.00	59.00	62.00	65.00	71.00	73.00
2 ratoon	44.75	36.40	30.38	44.30	51.00	51.00	52.00	53.00	57.00	61.00	64.00
3 ratoon	38.26	38.71	34.86	31.86	41.00	47.00	48.00	49.00	50.00	51.00	55.00
4 ratoon	40.32	34.50	41.54	41.43	32.00	39.00	45.00	46.00	47.00	48.00	50.00
5 ratoon	35.44	36.13	38.86	33.21	38.00	34.00	37.00	44.00	44.00	44.00	48.00
6 ratoon											
7+ ratoon											
mean	45.67	39.68	40.37	44.43	48.06	50.80	53.96	55.79	58.72	62.66	65.30
target	69.00	69.00	69.00	69.00	69.00	69.00	69.00	69.00	69.00	69.00	69.00
Cane Production (combines FF & P & P)											
yields)											
Plants	59,053.97	29,057.83	36,193.00	52,876.48	43,875.00	45,900.00	50,400.00	51,840.00	59,775.00	66,151.00	67,745.00
1 ratoon	37,164.15	43,437.66	22,979.00	31,952.36	53,020.00	42,750.00	44,250.00	49,600.00	52,000.00	56,800.00	58,400.00
2 ratoon	32,087.06	27,530.05	28,687.00	17,981.37	29,325.00	49,164.00	39,000.00	39,750.00	45,600.00	48,800.00	51,200.00
3 ratoon	34,151.81	21,459.30	19,466.00	19,785.06	16,646.00	27,025.00	46,272.00	36,750.00	37,500.00	38,250.00	41,250.00
4 ratoon	31,920.09	26,692.83	18,900.00	16,654.86	19,872.00	15,834.00	25,875.00	44,344.00	35,250.00	33,600.00	35,000.00
5 ratoon	36,578.17	43,229.55	50,583.00	35,451.68	26,296.00	19,142.00	6,438.00		3,828.00	6,028.00	6,576.00
6 ratoon											
7+ ratoon											
Estate cane production	230,955	191,407	176,808	174,702	189,034.00	199,815.00	212,235.00	222,284.00	233,953.00	249,629.00	260,171.00
Farmers' Cane Production	-	-	7,312	24,208	45,000	57,600	56,000	70,000	72,000	72,000	72,000
Total Cane Production	230,955	191,407	184,120	198,910	234,034.00	257,415.00	268,235.00	292,284.00	305,953.00	321,629.00	332,171.00
Percent estate canes	100.00	100.00	96.03	87.83	80.77	77.62	79.12	76.05	76.47	77.61	78.32
Percent farmers cane	-	-	3.97	12.17	19.23	22.38	20.88	23.95	23.53	22.39	21.68
Pol % cane - Estate	9.50	9.50	9.18	9.50	9.50	9.80	9.80	10.20	10.20	10.20	10.20
Pol % cane - Farmers	-	-	9.10	9.20	9.50	9.80	9.80	10.00	10.00	10.00	10.00
Tc/Ts Estate Cane	13.65	13.76	13.22	12.79	12.80	12.60	12.60	12.40	12.40	12.40	12.40
Tc/Ts Farmers' Cane	-	-	13.43	13.11	12.80	12.60	12.60	12.60	12.40	12.40	12.40
Farmers' HA			71.3	284.8	600.0	800.0	800.0	1,000.0	1,000.0	1,000.0	1,000.0
TCHA (Farmers)			102.6	85.0	75.0	72.0	70.0	70.0	72.0	72.0	72.0
Sugar Production - Estate	16,920	13,909	13,372	13,659	14,768	15,858	16,844	17,926	18,867	20,131	20,982
Sugar Production - Farmers	-	-	544	1,847	3,516	4,571	4,444	5,556	5,806	5,806	5,806
Total sugar production	16,920	13,909	13,916	15,506	18,284	20,430	21,288	23,482	24,674	25,938	26,788
Vary Production											
Estate hectares harvested	5,057.30	4,823.7	4,379.3	3,932.5	3,933.0	3,933.0	3,933.0	3,984.0	3,984.0	3,984.0	3,984.0
Farmers hectares harvested	-	-	71.30	284.80	600.00	800.00	800.00	1,000.00	1,000.00	1,000.00	1,000.00
Total Hectares Harvested	5,057.30	4,823.70	4,450.60	4,217.30	4,533.00	4,733.00	4,733.00	4,984.00	4,984.00	4,984.00	4,984.00
Estate cane production	230,955.25	191,407	176,808	174,702	189,034	199,815	212,235	222,284	233,953	249,629	260,171
Farmers Cane Production	-	-	7,312	24,208	45,000	57,600	56,000	70,000	72,000	72,000	72,000
Total Cane Production	230,955.25	191,407	184,120	198,910	234,034	257,415	268,235	292,284	305,953	321,629	332,171
Sugar Production - Estate	16,919.80	13,909	13,372	13,659	14,768	15,858	16,844	17,926	18,867	20,131	20,982
Sugar Production - Farmers	-	-	544	1,847	3,516	4,571	4,444	5,556	5,806	5,806	5,806
Total sugar production	16,919.80	13,909	13,916	15,506	18,284	20,430	21,288	23,482	24,674	25,938	26,788
TOTAL TCH	45.67	39.68	41.37	47.17	51.63	54.39	56.67	58.64	61.39	64.53	66.65
TOTAL TCHS	13.65	13.76	13.23	12.83	12.80	12.60	12.60	12.40	12.40	12.40	12.40

Guyana Sugar Corporation Inc.
Production Forecast 2015 -2020
LBI

	2012	2013	2014	2015	2016	2017	2018	2019	2020	2023	2025
Cane yields (combines FF & P&P yields)											
Plants	1,581	1,744	3,054	2,046	2,373	2,319					
1 ratoon	71,28	73,69	61,31	65,54	70,00	74,00	78,00	80,00	82,00	84,00	86,00
2 ratoon	50,63	53,63	51,96	57,06	60,00	65,00	69,00	73,00	74,00	74,00	74,00
3 ratoon	45,22	43,93	42,17	47,62	53,00	56,00	61,00	64,00	68,00	68,00	68,00
4 ratoon	39,49	38,50	43,71	41,03	49,40	50,00	54,00	59,00	60,00	60,00	64,00
5 ratoon	33,80	42,20	43,56	35,99	40,00	42,00	48,00	51,00	56,00	56,00	58,00
6 ratoon	44,45	45,73	41,09	40,07	37,00	39,00	40,00	46,00	48,00	52,00	54,00
7+ ratoon											
mean	48,37	51,97	46,31	47,35	48,82	52,51	57,56	62,84	66,22	69,00	70,57
potential	82,00	82,00	82,00	82,00	82,00	82,00	82,00	82,00	82,00	82,00	82,00
Cane Production (combines FF & P & P yields)											
Plants	21,170	27,636	19,649	42,778	22,820	28,120	35,880	38,400	42,640	47,040	48,160
1 ratoon	22,290	21,396	32,999	5,267	39,900	23,790	28,980	36,500	38,480	44,400	44,400
2 ratoon	19,982	20,688	26,984	21,039	4,876	37,340	22,326	26,880	34,000	40,800	40,800
3 ratoon	9,599	15,850	38,159	17,425	19,448	4,600	35,910	21,594	25,200	31,200	35,840
4 ratoon	7,792	5,904	21,846	20,147	17,000	18,564	4,416	33,915	20,496	14,000	11,600
5 ratoon	10,022	18,647	16,604	21,128.91	27,713	29,406	27,840.00	12,328.00	17,904.00	8,788.00	9,666.00
6 ratoon											
7+ ratoon											
Estate cane production	90,854	110,122	156,240	127,785	131,757.00	141,720	155,352	169,617	178,720	186,228	190,466
Farmers' Cane Production	2,383	1,546	3,079	3,640	3,240	3,240	3,240	3,240	3,240	3,240	3,240
Total Cane Production	93,237	111,668	159,319	131,425	134,997.00	144,960	158,592	172,857	181,960	189,468	193,706
Percent estate canes	97.44	98.62	98.07	97.23	97.60	97.76	97.96	98.13	98.22	98.29	98.33
Percent farmers cane	2.56	1.38	1.93	2.77	2.40	2.24	2.04	1.87	1.78	1.71	1.67
Pol % cane - Estate	9.50	9.10	9.17	10.10	10.20	10.40	10.40	10.60	10.60	10.60	10.60
Pol % cane - Farmers	9.00	8.65	9.16	9.70	9.80	10.00	10.00	10.20	10.20	10.20	10.20
Tc/Is Estate Cane	13.68	15.29	14.11	12.90	12.80	12.60	12.60	12.60	12.60	12.60	12.60
Tc/Is Farmers' Cane	15.59	15.03	14.11	13.50	13.50	13.00	13.00	13.00	13.00	13.00	13.00
Farmers' HA	53.30	39.10	98.30	82.10	81.00	81.00	81.00	81.00	81.00	81.00	81.00
TCHA (Farmers)	44.70	39.55	31.32	44.34	40.00	40.00	40.00	40.00	40.00	40.00	40.00
Sugar Production - Estate	6,641	7,203	11,076	9,906	10,294	11,248	12,330	13,462	14,184	14,780	15,116
Sugar Production - Farmers	153	103	218	270	240	249	249	249	249	249	249
Total sugar production	6,794	7,306	11,294	10,175	10,534	11,497	12,579	13,711	14,433	15,029	15,366
Vary Production											
Estate hectares harvested	1,878.2	2,119	3,374	2,699	2,699	2,699	2,699	2,699	2,699	2,699	2,699
Farmers hectares harvested	53.3	39.10	98.30	82.10	81.00	81.00	81.00	81.00	81.00	81.00	81.00
Total Hectares Harvested	1,931.45	2,158.1	3,472.30	2,780.70	2,780.00	2,780.00	2,780.00	2,780.00	2,780.00	2,780.00	2,780.00
Estate cane production	90,854	110,122	156,240	127,785	131,757	141,720	155,352	169,617	178,720	186,228	190,466
Farmers' Cane Production	2,383	1,546	3,079	3,640	3,240	3,240	3,240	3,240	3,240	3,240	3,240
Total Cane Production	93,237	111,668	159,319	131,425	134,997	144,960	158,592	172,857	181,960	189,468	193,706
Sugar Production - Estate	6,641	7,203	11,076	9,906	10,294	11,248	12,330	13,462	14,184	14,780	15,116
Sugar Production - Farmers	153	103	218	270	240	249	249	249	249	249	249
Total sugar production	6,794	7,306	11,294	10,175	10,534	11,497	12,579	13,711	14,433	15,029	15,366
TOTAL TCH	48,27	51,74	45,88	47,26	48,56	52,14	57,05	62,18	65,45	68,15	69,68
TOTAL TCTS	13,72	15,28	14,11	12,92	12,82	12,61	12,61	12,61	12,61	12,61	12,61
TOTAL TSH	3,52	3,39	3,25	3,66	3,79	4,14	4,52	4,93	5,19	5,41	5,53

Guyana Sugar Corporation Inc.
Production Forecast 2015-2020
Rosehall

	Unit	2012	2013	2014	2015	2016	2017	2018	2019	2020	2023	2025
Cane yields (combines FF & P & P yields)				6,040.00	5,036.30							
Plants	tc/ha	61.98	64.90	72.30	73.00	76.00	79.00	81.00	84.00	86.00	92.00	94.00
1 ratoon	tc/ha	61.01	55.47	71.97	67.00	67.00	69.00	75.00	79.00	78.00	79.00	80.00
2 ratoon	tc/ha	60.53	52.00	56.77	56.00	60.00	62.00	65.00	69.00	70.00	70.00	72.00
3 ratoon	tc/ha	56.35	50.16	55.48	55.00	53.00	57.00	59.00	62.00	65.00	65.00	65.00
4 ratoon	tc/ha	52.67	47.25	50.62	53.00	51.00	50.00	54.00	55.00	60.00	60.00	60.00
5 ratoon	tc/ha	50.85	41.91	49.71	50.00	50.00	49.00	48.00	49.00	50.00	54.00	54.00
6 ratoon	tc/ha											
7+ ratoon	tc/ha											
mean	tc/ha	57.08	50.91	57.53	57.70	59.82	60.77	62.80	65.81	69.25	72.06	74.17
potential	tc/ha	82.00	82.00	82.00	82.00	82.00	82.00	82.00	82.00	82.00	82.00	82.00
Cane Production (combines FF & P & P yields)	tonne											
Plants	tonne	75,128	52,177	49,166	92,622	86,640	67,545	69,255	83,160	102,340	109,480	111,860
1 ratoon	tonne	78,281	59,759	71,379	27,219	95,073	89,010	73,365	75,375	88,920	105,860	107,200
2 ratoon	tonne	58,119	61,459	63,204	56,868	25,500	87,978	83,850	69,345	70,350	79,800	96,480
3 ratoon	tonne	50,727	61,264	58,855	52,575	53,848	24,225	83,721	79,980	65,325	65,325	87,100
4 ratoon	tonne	43,924	43,141	61,210	44,668	48,756	50,800	22,950	78,045	76,110	60,300	60,300
5 ratoon	tonne	81,289	61,389	82,763	89,840	67,900	64,141	63,360	29,645	34,200	34,236	5,346
6 ratoon	tonne											
7+ ratoon	tonne											
Estate cane production	tonne	387,468	339,189	386,577	363,793	377,717	383,699	396,501	415,550	437,245	455,001	468,286
Farmers' Cane Production	tonne	36,115	33,299	41,678	39,513	38,350	42,160	40,800	39,440	40,120	42,160	42,160
Total Cane Production	tonne	423,583	372,488	428,255	403,306	416,067	425,859	437,301	454,990	477,365	497,161	510,446
Percent estate canes	%	91.47	91.06	90.27	90.20	90.78	90.10	90.67	91.33	91.60	91.52	91.74
Percent farmers cane	%	8.53	8.94	9.73	9.80	9.22	9.90	9.33	8.67	8.40	8.48	8.26
Pol % cane - Estate	%	9.50	9.60	9.43	9.50	9.80	10.20	10.40	10.60	10.80	10.80	10.80
Pol % cane - Farmers	%	9.80	9.12	9.10	9.80	9.80	10.00	10.20	10.20	10.20	10.20	10.20
Tc/Is Estate Cane	tc/s	12.33	13.25	13.40	13.00	13.00	12.20	12.40	11.80	11.80	11.80	11.80
Tc/Is Farmers' Cane	tc/s	12.01	13.51	14.00	13.00	13.20	13.00	12.80	12.80	12.80	12.80	12.80
Farmers' HA	Ha	651.90	656.40	644.10	646.70	650.00	680.00	680.00	680.00	680.00	680.00	680.00
TCHA (Farmers)	tc/ha	55.40	50.73	64.71	61.10	59.00	62.00	60.00	58.00	59.00	62.00	62.00
Sugar Production - Estate	tonne	31,425	25,633	29,168	27,149	29,055	29,976	31,976	34,061	37,055	38,559	39,685
Sugar Production - Farmers	tonne	3,007	2,465	2,977	3,041	2,905	3,243	3,188	3,134	3,294	3,294	3,294
Total sugar production	tonne	34,432	28,098	32,145	30,189	31,960	33,220	35,163	37,143	40,189	41,853	42,979
Vary Production												
Estate hectares harvested		6,788.1	6,662.5	6,720.0	6,305.1	6,314.0	6,314.0	6,314.0	6,314.0	6,314.0	6,314.0	6,314.0
Farmers hectares harvested		651.9	656.4	644.1	646.7	650.0	680.0	680.0	680.0	680.0	680.0	680.0
Total Hectares Harvested		7,440.00	7,318.9	7,364.10	6,951.80	6,964.00	6,994.00	6,994.00	6,994.00	6,994.00	6,994.00	6,994.00
Estate cane production		387,468	339,189	386,577	363,793	377,717	383,699	396,501	415,550	437,245	455,001	468,286
Farmers' Cane Production		36,115	33,299	41,678	39,513	38,350	42,160	40,800	39,440	40,120	42,160	42,160
Total Cane Production		423,583	372,488	428,255	403,306	416,067	425,859	437,301	454,990	477,365	497,161	510,446
Sugar Production - Estate		31,425	25,633	29,168	27,149	29,055	29,976	31,976	34,061	37,055	38,559	39,685
Sugar Production - Farmers		3,007	2,465	2,977	3,041	2,905	3,243	3,188	3,081	3,134	3,294	3,294
Total sugar production		34,432	28,098	32,145	30,189	31,960	33,220	35,163	37,143	40,189	41,853	42,979
										(0.00)		(0.00)
TOTAL TCH		56.93	50.89	58.15	58.01	59.75	60.89	62.53	65.05	68.25	71.08	72.98
TOTAL TCTS		12.30	13.26	13.32	13.36	13.02	12.82	12.44	12.25	11.88	11.88	11.88
TOTAL TSH		4.63	3.84	4.37	4.34	4.59	4.75	5.03	5.31	5.75	5.98	6.15

Guyana Sugar Industry
Production Forecast 2015 -2020
Skeldon

	2012	2013	2014	2015	2016	2017	2018	2019	2020	2023	2025
Summary of areas											
Area in Canes											
Harvest	7,609.3	5,667.00	8,116.70	8,039.60	8,582.00	8,582.00	8,532.00	8,532.00	8,532.00	8,532.00	8,532.00
C/over,b/f											
Draw Down	94.50	170.00	170.00	170.00	170.00	170.00	170.00	170.00	170.00	170.00	170.00
Full 6 month fallow											
Prepared land	530.60	441.90	491.90	150.00	200.00	200.00	200.00	200.00	200.00	200.00	200.00
Area in cultivation	8,858.40	8,902.60	8,902.60	8,902.00	8,902.00	8,902.00	8,902.00	8,902.00	8,902.00	8,902.00	8,902.00
Area in cul excl F/fallow @31/12	8,327.80	8,460.70	8,410.70	8,752.00	8,752.00	8,702.00	8,702.00	8,702.00	8,702.00	8,702.00	8,702.00
Flood Fallow prepared during the year											
Flood Fallow @31/12											
Draw Down during the year	239.20	300.00	340.00	412.00	412.00	412.00	412.00	412.00	412.00	412.00	412.00
Planting during the year	1,233.1	894.90	723.70	1,335.00	1,514.00	1,780.00	1,780.00	1,780.00	1,780.00	1,780.00	1,780.00
% planting	14%	10%	8%	15%	17%	20%	20%	20%	20%	20%	20%
Flood Fallowing % planting											
Planting from FF											
Commercial											
Dambed seed											
Total											
Planting P & P											
Commercial	1,000.0	644.90	473.70	1,085.00	1,264.00	1,530.00	1,530.00	1,530.00	1,530.00	1,530.00	1,530.00
Seed cane	233.1	250.00	250.00	250.00	250.00	250.00	250.00	250.00	250.00	250.00	250.00
Total	1,233.1	894.90	723.70	1,335.00	1,514.00	1,780.00	1,780.00	1,780.00	1,780.00	1,780.00	1,780.00
Total planting FF + P & P											
Check	1,233.1	894.90	723.70	1,335.00	1,514.00	1,780.00	1,780.00	1,780.00	1,780.00	1,780.00	1,780.00
%Planting	14%	10%	8%	15%	17%	20%	20%	20%	20%	20%	20%
% Seed Cane	3%	3%	3%	3%	3%	3%	3%	3%	0%	0%	0%
Putting land under water from FF											
FF Land											
Total mechanical Tillage											
1,364.80	894.90	837.00	1,335.00	1,514.00	1,780.00	1,780.00	1,780.00	1,780.00	1,780.00	1,780.00	1,780.00
Harvest area											
Plants excl seed canes	1,025.6	877.6	1,069.10	635.90	1,165.00	1,264.00	1,530.00	1,530.00	1,530.00	1,530.00	1,530.00
1 ratoon	1,442.5	507.8	1,376.20	921.00	804.00	1,415.00	1,514.00	1,780.00	1,780.00	1,780.00	1,780.00
2 ratoon	560.3	863.9	1,110.90	1,355.20	921.00	804.00	1,415.00	1,514.00	1,780.00	1,780.00	1,780.00
3 ratoon	648.9	324.1	804.10	974.70	1,355.00	921.00	804.00	1,415.00	1,514.00	1,780.00	1,780.00
4 ratoon	388.8	184.5	466.70	771.80	975.00	1,355.00	921.00	804.00	1,415.00	1,315.00	1,460.00
5 ratoon	3,543.2	2,909.1	3,289.70	3,381.00	3,363.00	2,823.00	2,348.00	1,489.00	513.00	347.00	202.00
6 ratoon											
7+ ratoon											
Total	7,609.3	5,667.0	8,116.70	8,039.60	8,583.00	8,582.00	8,532.00	8,532.00	8,532.00	8,532.00	8,532.00

Guyana Sugar Industry
Production Forecast 2015-2020
Sheddon

	2012	2013	2014	2015	2016	2017	2018	2019	2020	2023	2025
Cane yields (combines FF & P & P)											
Units											
Cane yields (yields)											
Plants	62.67	73.98	68.39	71.69	75.00	80.00	83.00	87.00	90.00	95.00	97.00
1 ratoon	57.93	58.07	64.88	67.05	68.00	71.00	75.00	77.00	81.00	83.00	84.00
2 ratoon	51.68	44.68	56.03	62.00	64.00	65.00	67.00	71.00	72.00	75.00	77.00
3 ratoon	52.68	52.37	51.03	53.07	59.00	60.00	61.00	64.00	67.00	70.00	71.00
4 ratoon	47.24	51.94	42.02	52.47	51.00	56.00	57.00	58.00	61.00	65.00	66.00
5 ratoon	48.49	53.80	56.91	51.99	50.00	50.00	53.00	54.00	55.00	58.00	58.00
6 ratoon											
7+ ratoon											
mean	52.72	55.77	58.21	57.14	58.12	61.31	65.79	69.77	73.37	76.98	78.46
potential	77.00	83.00	83.00	83.00	83.00	83.00	83.00	83.00	83.00	83.00	83.00
Cane Production (combines FF & P & P)											
Yields											
Plants	64,271.0	64,925.0	73,119.0	45,587.7	87,375.0	101,120.0	126,990.0	133,110.0	137,700.0	145,350.0	148,410.0
1 ratoon	83,557.0	29,489.0	89,283.0	61,753.1	54,672.0	100,465.0	113,550.0	137,060.0	144,180.0	147,740.0	149,520.0
2 ratoon	28,958.0	38,600.0	62,239.0	84,022.4	58,944.0	52,260.0	94,805.0	107,494.0	128,160.0	133,500.0	137,060.0
3 ratoon	34,182.0	16,973.0	41,035.0	51,727.3	79,945.0	55,260.0	49,044.0	90,560.0	101,438.0	124,600.0	126,380.0
4 ratoon	18,365.0	9,583.0	19,611.0	40,496.3	49,725.0	75,880.0	52,497.0	46,632.0	86,315.0	85,475.0	96,360.0
5 ratoon	171,814.0	156,496.0	187,220.0	175,778.2	168,150.0	141,150.0	124,444.0	80,406.0	28,215.0	20,126.0	11,716.0
6 ratoon											
7+ ratoon											
Estate cane production	401,147.0	316,066.0	472,507.0	459,365.0	498,811.0	526,135.0	561,330.0	595,262.0	626,008.0	656,791.0	669,446.0
Farmers' Cane Production	140,781.0	118,613.0	117,511.0	127,244.0	130,032.0	130,032.0	143,000.0	151,200.0	156,800.0	173,600.0	182,000.0
Total Cane Production	541,928.0	434,679.0	590,018.0	586,609.0	628,843.0	656,167.0	704,330.0	746,462.0	782,808.0	830,391.0	843,046.0
Percent estate canes	74.02%	72.71%	80.08%	78.31%	79.32%	80.18%	79.70%	79.74%	79.97%	79.09%	79.41%
Percent farmers cane	25.98%	27.29%	19.92%	21.69%	20.68%	19.82%	20.30%	20.26%	20.03%	20.91%	21.59%
Pol % cane - Estate	9.5%	8.5%	8.4%	8.4%	9.2%	10.2%	10.5%	10.5%	10.5%	10.5%	10.5%
Pol % cane - Farmers	9.0%	8.2%	8.2%	8.9%	9.0%	9.8%	9.8%	9.8%	9.8%	10.0%	10.0%
Te/Ts Estate Cane	15.96	16.44	16.35	15.13	14.00	13.00	12.80	12.80	12.60	12.60	12.60
Te/Ts Farmers' Cane	17.32	18.76	16.80	15.05	14.50	13.50	13.50	13.50	13.00	12.80	12.80
Farmers' HA	2,416.7	2,119.40	3,376.7	2,408.1	2,408.0	2,408.0	2,600.0	2,700.00	2,800.00	2,800.00	2,800.00
TCHA (Farmers)	58.25	55.97	49.44	52.84	54.00	54.00	55.00	56.00	56.00	62.00	65.00
Sugar Production - Estate	25,135.0	19,223.0	28,897.0	30,361.0	35,629.0	40,472.0	43,854.0	46,504.84	49,683.17	52,126.27	53,130.63
Sugar Production - Farmers	8,128.0	6,321.0	6,993.0	8,455.0	8,968.0	9,632.0	10,593.0	11,200.00	12,061.54	13,562.50	14,218.75
Total sugar production	33,263.0	25,544.0	35,890.0	38,816.0	44,597.0	50,104.0	54,446.0	57,704.84	61,744.71	65,688.77	67,349.38
Vary Production											
Estate hectares harvested	7,609.30	5,667.0	8,116.7	8,039.6	8,583.0	8,582.0	8,532.0	8,532.0	8,532.0	8,532.0	8,532.0
Farmers hectares harvested	2,416.70	2,119.4	2,377.0	2,408.0	2,408.0	2,408.0	2,600.0	2,700.0	2,800.0	2,800.0	2,800.0
TOTAL Hectares Harvested	10,026.00	7,786.40	10,493.40	10,447.70	10,991.00	10,990.00	11,132.00	11,232.00	11,332.00	11,332.00	11,332.00
Estate cane production	401,147.0	316,066.0	472,507.0	459,365.0	498,811.0	526,135.0	561,330.0	595,262.0	626,008.0	656,791.0	669,446.0
Farmers' Cane Production	140,781.0	118,613.0	117,511.0	127,244.0	130,032.0	130,032.0	143,000.0	151,200.0	156,800.0	173,600.0	182,000.0
Total Cane Production	541,928.0	434,679.0	590,018.0	586,609.0	628,843.0	656,167.0	704,330.0	746,462.0	782,808.0	830,391.0	851,446.0
Sugar Production - Estate	25,135.0	19,223.0	28,897.0	30,361.0	35,629.0	40,472.0	43,854.0	46,505.0	49,683.0	52,126.0	53,131.0
Sugar Production - Farmers	8,128.0	6,321.0	6,993.0	8,455.0	8,968.0	9,632.0	10,593.0	11,200.0	12,062.0	13,563.0	14,219.0
Total sugar production	33,263.0	25,544.0	35,890.0	38,816.0	44,597.0	50,104.0	54,446.0	57,705.0	61,745.0	65,689.0	67,349.0
TOTAL TCH	54.05	55.83	56.23	56.15	57.21	59.71	63.27	66.46	69.08	73.28	75.14
TOTAL TCTS	16.29	17.02	16.44	15.11	14.10	13.10	12.94	12.94	12.68	12.64	12.64

Appendix 2

Agriculture Operating Costs and Capital Requirements

ACCESSIBILITY & CANE TRANSPORT INVESTMENTS					
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M
Skeldon	All weather roads	25	120000	3000000	615
Skeldon	Cane Punts	700	4878	3414600	700.0
Skeldon	45/66 Tractor JD	8	33980	271840	55.7
Skeldon	55 HP tractors With Winch	12	70000	840000	172.2
Skeldon	Vehicles	10	30000	300000	61.5
Skeldon	Motor Cycle	30	1500	45000	9.2
ALBION	45 HP Tractor	15	48544	728160	149.3
ALBION	Cane Punts	380	4878	1853640	380.0
ALBION	Paddle tug Engines	5	7318	36590	7.5
ALBION	All weather road	30	97561	2926830	600.0
ALBION	Vehicles	10	3000	30000	6.2
ALBION	Motor Cycle	30	1500	45000	9.2
ROSE HALL	Prime Mover-Mahendra Tractor	2	48544	97088	19.9
ROSE HALL	Cane Punts	350	4878	1707300	350.0
ROSE HALL	45/66 Tractor JD	10	33980	339800	69.7
ROSE HALL	Motor Grader	1	97087	97087	19.9
ROSE HALL	All weather road	25	24272	606800	124.4
ROSE HALL	Vehicles	10	3000	30000	6.2
ROSE HALL	Motor Cycle	30	1500	45000	9.2
Blairmont	Cane Punts	300	4878	1463400	300.0
Blairmont	All weather road	25	24272	606800	124.4
Blairmont	45/66 Tractor JD	8	33980	271840	55.7
Blairmont	55 Hp Tractor	4	24390	97561	20.0
Blairmont	Vehicles	7	3000	21000	4.3
Blairmont	Motor Cycle	25	1500	37500	7.7
East Demerara	Cane Transport - 45 hp tractor	10	19512	195122	40.0
East Demerara	All weather roads	30	61789	1853659	380.0
East Demerara	Establishing new link rear end of LBI	1	200000	200000	41.0
East Demerara	Punts	280	4878	1365840	280.0
East Demerara	Vehicles	8	3000	24000	4.9
East Demerara	Motor Cycle	26	1500	39000	8.0
Wales	ALL WEATHER ROADS	15	50000	750000	153.8
Wales	CANE PUNTS	180	4390	790244	162.0
Wales	DUMP LORRY	1	30000	30000	6.2
Wales	Cane Transport - 45 hp tractor	10	19512	195122	40.0
Wales	Vehicles	6	3000	18000	3.7
Wales	Motor Cycle	20	1500	30000	6.2
Uitvlugt	Cane Punts	300	4878	1463400	300.0
Uitvlugt	All weather road	30	24272	728160	149.3
Uitvlugt	45/66 Tractor JD	10	33980	339800	69.7
Uitvlugt	55 Hp Tractor	5	24390	121951	25.0
Uitvlugt	Vehicles	8	3000	24000	4.9
Uitvlugt	Motor Cycle	23	1500	34500	7.1
TOTAL				27115634	5558.7

ALL WEATHER ROADS						
ESTATE	Description	Quantity KM	Unit Price US\$	Cost US\$	Cost G\$M	
ROADS	Skeldon	All weather roads	25	120000	3000000	615
	ALBION	All weather road	30	97561	2926830	600.0
	ROSE HALL	All weather road	25	24272	606800	124.4
	Blairmont	All weather road	25	24272	606800	124.4
	East Demerara	All weather roads	30	61789	1853659	380.0
	Wales	ALL WEATHER ROADS	15	50000	750000	153.8
	Uitvlugt	All weather road	30	24272	728160	149.3
	East Demerara	Establishing new link rear end of LBI	1	200000	200000	41.0
					10672249	2187.8

CANE PUNTS						
ESTATE	Description	Quantity Each	Unit Price US\$	Cost US\$	Cost G\$M	
CANE PUNTS	Skeldon	Cane Punts	700	4878	3414600	700.0
	ALBION	Cane Punts	380	4878	1853640	380.0
	ROSE HALL	Cane Punts	350	4878	1707300	350.0
	Blairmont	Cane Punts	300	4878	1463400	300.0
	East Demerara	Punts	280	4878	1365840	280.0
	Wales	CANE PUNTS	180	4390	790244	162.0
	Uitvlugt	Cane Punts	300	4878	1463400	300.0
					12058424	2472.0

CANE TRANSPORT TRACTORS						
ESTATE	Description	Quantity Each	Unit Price US\$	Cost US\$	Cost G\$M	
TRACTORS	Skeldon	45/66 Tractor JD	8	33980	271840	55.7
	Skeldon	55 HP tractors With Winch	12	70000	840000	172.2
	ALBION	45 HP Tractor	15	48544	728160	149.3
	ROSE HALL	Prime Mover-Mahendra Tractor	2	48544	97088	19.9
	ROSE HALL	45/66 Tractor JD	10	33980	339800	69.7
	Blairmont	45/66 Tractor JD	8	33980	271840	55.7
	Blairmont	55 Hp Tractor	4	24390	97561	20.0
	East Demerara	Cane Transport - 45 hp tractor	10	19512	195122	40.0
	Wales	Cane Transport - 45 hp tractor	10	19512	195122	40.0
	Uitvlugt	45/66 Tractor JD	10	33980	339800	69.7
	Uitvlugt	55 Hp Tractor	5	24390	121951	25.0
	TOTAL		94		3498284	717.1

TUGS						
ESTATE	Description	Quantity Each	Unit Price US\$	Cost US\$	Cost G\$M	
TUGS	ALBION	Paddle tug Engines	5	7318	36590	7.5
	TOTAL		5		36590	7.5

GRADER						
ESTATE	Description	Quantity Each	Unit Price US\$	Cost US\$	Cost G\$M	
GRADER	ROSE HALL	Motor Grader	1	97087	97087	19.9
	TOTAL		1		97087	19.9

DUMP LORRY						
ESTATE	Description	Quantity Each	Unit Price US\$	Cost US\$	Cost G\$M	
Dump Lorry	Wales	DUMP LORRY	1	30000	30000	6.2
	TOTAL		1		30000	6.2

VEHICLES						
ESTATE	Description	Quantity Each	Unit Price US\$	Cost US\$	Cost G\$M	
Vehicles	Skeldon	Vehicles	10	30000	300000	61.5
	ALBION	Vehicles	10	3000	30000	6.2
	ROSE HALL	Vehicles	10	3000	30000	6.2
	Blairmont	Vehicles	7	3000	21000	4.3
	East Demerara	Vehicles	8	3000	24000	4.9
	Wales	Vehicles	6	3000	18000	3.7
	Uitvlugt	Vehicles	8	3000	24000	4.9
	TOTAL				447000	91.6

MOTOR CYCLES						
ESTATE	Description	Quantity Each	Unit Price US\$	Cost US\$	Cost G\$M	
Motor Cycles	Skeldon	Motor Cycle	30	1500	45000	9.2
	ALBION	Motor Cycle	30	1500	45000	9.2
	ROSE HALL	Motor Cycle	30	1500	45000	9.2
	Blairmont	Motor Cycle	25	1500	37500	7.7
	East Demerara	Motor Cycle	26	1500	39000	8.0
	Wales	Motor Cycle	20	1500	30000	6.2
	Uitvlugt	Motor Cycle	23	1500	34500	7.1
					276000	56.6

GRAND TOTAL				Cost US\$	Cost G\$M
				27115634	5558.7

CIVILS INFRASTRUCTURE INVESTMENTS					
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M
Skeldon	High bridges	16	68293	1092688	224.0
Skeldon	Aqueducts	7	46341	324387	66.5
Skeldon	Heavy duty revetment - Meters	1000	830	830000	170.2
Skeldon	Heavy duty revetment Meters	1000	830	830000	170.2
Skeldon	Light duty revetment Meters	10000	162	1620000	332.1
ALBION	High bridges	16	68293	1092688	224.0
ALBION	Aqueducts	8	46341	370728	76.0
ALBION	Heavy duty revetment - Meters	2000	830	1660000	340.3
ALBION	Heavy duty revetment : Meters	1000	830	830000	170.2
ALBION	Light duty revetment : Meters	12000	162	1944000	398.5
ROSE HALL	Heavy duty revetment – Meters	1500	830	1245000	255.2
ROSE HALL	Heavy duty revetment :- Meters	1200	830	996000	204.2
ROSE HALL	Light duty revetment :- Meters	11000	162	1782000	365.3
ROSE HALL	Check Sluices to control water in low lying areas	10	19417	194170	39.8
ROSE HALL	Installing two worms at EV and GBL Sluices	2	7282	14564	3.0
Blairmont	Heavy duty revetment Meters	1000	830	830000	170.2
Blairmont	Light duty revetment Meters	10000	162	1620000	332.1
Blairmont	Aqueduct	4	146341	585366	120.0
Blairmont	High bridges	10	68293	682930	140.0
Blairmont	Sluice	1	146341	146341	30.0
East Demerara	Modification of building/ facilities			97561	20.0
East Demerara	Admin building			195122	40.0
East Demerara	Fertilizer bond Building			195122	40.0
East Demerara	High Bridges - Concrete	12	58537	702439	144.0
East Demerara	Flat Bridges - Concrete	10	24390	243902	50.0
East Demerara	Light duty revetment along CNC Meters	8000	162	1296000	265.7
East Demerara	Replacement of aqueduct	3	146341	439024	90.0
Wales	FLAT BRIDGES	8	48780	195122	40.0
Wales	LIGHT DUTY revetment : Meters	6000	162	972000	199.3
Wales	HIGH BRIDGES	8	58537	292683	60.0
Uitvlugt	High Bridges	10	70000	700000	143.5
Uitvlugt	Aqueducts	6	100000	600000	123.0
TOTAL				24619838	5047.1

CIVILS INFRACTURE INVESTMENTS BY TYPE

BRIDGES						
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M	
BRIDGES	Skeldon	High bridges	16	68293	1092688	224.0
	ALBION	High bridges	16	68293	1092688	224.0
	Blairmont	High bridges	10	68293	682930	140.0
	East Demerara	High Bridges - Concrete	12	58537	702439	144.0
	East Demerara	Flat Bridges - Concrete	10	24390	243902	50.0
	Wales	FLAT BRIDGES	8	48780	195122	40.0
	Wales	HIGH BRIDGES	8	58537	292683	60.0
	Uitvlugt	High Bridges	10	70000	700000	143.5
	TOTAL		90		5002452	1025.5

AQUEDUCT						
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M	
AQUEDUCTS	Skeldon	Aqueducts	7	46341	324387	66.5
	ALBION	Aqueducts	8	46341	370728	76.0
	Blairmont	Aqueduct	4	146341	585366	120.0
	East Demerara	Replacement of aqueduct	3	146341	439024	90.0
	Uitvlugt	Aqueducts	6	100000	600000	123.0
	TOTAL		28		2319505	475.5

REVETMENT						
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M	
REVETMENT	Skeldon	Heavy duty revetment - Meters	1000	830	830000	170.2
	Skeldon	Heavy duty revetment Meters	1000	830	830000	170.2
	Skeldon	Light duty revetment Meters	10000	162	1620000	332.1
	ALBION	Heavy duty revetment - Meters	2000	830	1660000	340.3
	ALBION	Heavy duty revetment : Meters	1000	830	830000	170.2
	ALBION	Light duty revetment : Meters	12000	162	1944000	398.5
	ROSE HALL	Heavy duty revetment – Meters	1500	830	1245000	255.2
	ROSE HALL	Heavy duty revetment :- Meters	1200	830	996000	204.2
	ROSE HALL	Light duty revetment :- Meters	11000	162	1782000	365.3
	Blairmont	Heavy duty revetment Meters	1000	830	830000	170.2
	Blairmont	Light duty revetment along CNC Meters	10000	162	1620000	332.1
	East Demerara	Light duty revetment along CNC Meters	8000	162	1296000	265.7
	Wales	LIGHT DUTY revetment : Meters	6000	162	972000	199.3
	TOTAL		65700		16455000	3373.3

SLUICES						
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M	
SLUICE	ROSE HALL	Check Sluices to control water in low lying areas	10	19417	194170	39.8
	ROSE HALL	Installing two worms at EV and GBL Sluices	2	7282	14564	3.0
	Blairmont	Sluice	1	146341	146341	30.0
	TOTAL		13		355075	72.8

BUILDINGS					
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M
BUILDINGS	East Demerara	Modification of building/ facilities		97561	20.0
	East Demerara	Admin building		195122	40.0
	East Demerara	Fertilizer bond Building		195122	40.0
	TOTAL			487805	100.0

ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M
GRAND TOTAL				24619838	5047.1

DRAINAGE & IRRIGATION INVESTMENTS					
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M
Skeldon	Overhead Irrigators	8	97561	780488	160
ROSE HALL	Irrigator	10	72815	728150	149.3
ROSE HALL	Self-driven dam bed pumps- Irrigators	9	48543	436887	89.6
ROSE HALL	Irrigator/Tugs	6	48500	291000	59.7
East Demerara	Drainage - Excavator	6	170732	682927	140.0
Wales	Drainage - Excavator	6	170732	682927	140.0
Uitvlugt	Drainage Pumps	2	650000	1300000	266.5
Uitvlugt	Irrigators	10	50000	500000	102.5
TOTAL				5402378	1107.5

DRAINAGE & IRRIGATION INVESTMENTS BY MACHINE TYPE

IRRIGATORS					
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M
Skeldon	Overhead Irrigators	8	97561	780488	160.0
ROSE HALL	Irrigator	10	72815	728150	149.3
ROSE HALL	Self-driven dam bed pumps- Irrigators	9	48543	436887	89.6
ROSE HALL	Irrigator/Tugs	6	48500	291000	59.7
Uitvlugt	Irrigators	10	50000	500000	102.5
TOTAL		43		2736525	561.0

IRRIGATORS

EXCAVATOR					
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M
East Demerara	Drainage - Excavator	6	170732	682927	140
Wales	Drainage - Excavator	6	170732	682927	140
TOTAL		12		1365854	280

EXCAVATORS

DRAINAGE PUMPS					
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M
Uitvlugt	Drainage Pumps	2	650000	1300000	266.5
TOTAL		2		1300000	266.5

DRAINAGE PUMPS

ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M
GRAND TOTAL				5402378	1107.5

ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M	Cat
Skeldon	All weather roads	25	120000	3000000	615	ACC
Skeldon	Cane Punts	700	4878	3414600	699.993	ACC
Skeldon	45/66 Tractor JD	8	33980	271840	55.7272	ACC
Skeldon	55 HP tractors With Winch	12	70000	840000	172.2	ACC
Skeldon	Vehicles	10	30000	300000	61.5	ACC
Skeldon	Motor Cycle	30	1500	45000	9.225	ACC
Skeldon	ACCIBILITY & CANE TRANSPORT				1613.6452	
Skeldon	High bridges	16	68293	1092688	224.00104	CV
Skeldon	Aqueducts	7	46341	324387	66.499335	CV
Skeldon	Heavy duty revetment - Meters	1000	830	830000	170.15	CV
Skeldon	Heavy duty revetment Meters	1000	830	830000	170.15	CV
Skeldon	Light duty revetment Meters	10000	162	1620000	332.1	CV
Skeldon	CIVIL STRUCTURES				962.900375	
Skeldon	Overhead Irrigators	8	97560.97561	780488	160	DI
Skeldon	DRAINAGE & IRRIGATION				160	
Skeldon	Harvesters and associated equipment	4	750000	3000000	615	MECH
Skeldon	Excavators	8	176850	1414797	290.0	MECH
Skeldon	Tractors - Fertilising	10	82142.85714	821428.5714	168.4	MECH
Skeldon	Boom Sprayer Implement	5	7000	35000	7.2	MECH
Skeldon	Land Conversion	2000	1500	3000000	615.0	MECH
Skeldon	Bell Loader	3	75000	225000	46.1	
Skeldon	MECHANIZATION				1741.7	
Skeldon	Tillage tractors	9	70000	630000	129.15	TP
Skeldon	Trailing Final Harrow	9	9709	87381	17.913105	TP
Skeldon	Plows	9	7540	67860	13.9113	TP
Skeldon	TILLAGE & PLANTING				160.974405	
ALBION	45 HP Tractor	15	48544	728160	149.2728	ACC
ALBION	Cane Punts	380	4878	1853640	379.9962	ACC
ALBION	Paddle tug Engines	5	7318	36590	7.50095	ACC
ALBION	All weather road	30	97561	2926830	600.00015	ACC
ALBION	Vehicles	10	3000	30000	6.15	ACC
ALBION	Motor Cycle	30	1500	45000	9.225	ACC
ALBION	ACCIBILITY & CANE TRANSPORT				1152.1451	
ALBION	High bridges	16	68293	1092688	224.00104	CV
ALBION	Aqueducts	8	46341	370728	75.99924	CV
ALBION	Heavy duty revetment - Meters	2000	830	1660000	340.3	CV
ALBION	Heavy duty revetment : Meters	1000	830	830000	170.15	CV
ALBION	Light duty revetment : Meters	12000	162	1944000	398.52	CV
ALBION	CIVIL STRUCTURES				1208.97028	
ALBION	Super long reach excavator	8	176849.6842	1414797.474	290.0	MECH
ALBION	Spring Tines Implement	4	9709	38836	8.0	MECH
ALBION	Planting trailer Implement	4	12135	48540	10.0	MECH
ALBION	Furrow coverer Implement	2	14563	29126	6.0	MECH
ALBION	Harvesters and associated equipment	2	780488	1560976	320.0	MECH
ALBION	Tractors LGRP Spreader	8	82390.33333	659122.6667	135.1	MECH
ALBION	LGRP SPREADER Implement	5	24390	121950	25.0	MECH
ALBION	Land Conversion	1000	1500	1500000	307.5	MECH
ALBION	Dump lorry- 10 Ton Tools	3	31707	95121	19.5	MECH
ALBION	Trolley jack- 20 ton Tools	2	8536	17072	3.5	MECH
ALBION	FWS Service unit Tools	1	72816	72816	14.9	MECH
ALBION	Portable welding plant Tools	2	2184	4368	0.9	MECH
ALBION	Lathe Tools	1	24272	24272	5.0	MECH
ALBION	Distilling unit Tools	1	1951	1951	0.4	MECH
ALBION	Heavy duty tool kit Tools	8	2439	19512	4.0	MECH
ALBION	Floor crane Tools	1	19512	19512	4.0	MECH
ALBION	Air compressor Tools	2	3902	7804	1.6	MECH
ALBION	Lighting plant Tools	6	8780	52680	10.8	MECH
ALBION	Bell Loader	3	75000	225000	46.1	
ALBION	MECHANIZATION				1212.3	
ALBION	160 HP Tractor	12	58252	699024	143.29992	TP
ALBION	Trailing Final Harrow	10	9709	97090	19.90345	TP
ALBION	Plows	10	7540	75400	15.457	TP
ALBION	Tractor 100hp	10	38835	388350	79.61175	TP
ALBION	TILLAGE & PLANTING				258.27212	

ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M	Cat
ROSE HALL	Prime Mover-Mahendra Tractor	2	48544	97088	19.90304	ACC
ROSE HALL	Cane Punts	350	4878	1707300	349.9965	ACC
ROSE HALL	45/66 Tractor JD	10	33980	339800	69.659	ACC
ROSE HALL	Motor Grader	1	97087	97087	19.902835	ACC
ROSE HALL	All weather road	25	24272	606800	124.394	ACC
ROSE HALL	Vehicles	10	3000	30000	6.15	ACC
ROSE HALL	Motor Cycle	30	1500	45000	9.225	ACC
ROSE HALL	ACCIBILITY & CANE TRANSPORT				599.230375	
ROSE HALL	Heavy duty revetment – Meters	1500	830	1245000	255.225	CV
ROSE HALL	Heavy duty revetment :- Meters	1200	830	996000	204.18	CV
ROSE HALL	Light duty revetment :- Meters	11000	162	1782000	365.31	CV
ROSE HALL	Check Sluices to control water in low lying areas	10	19417	194170	39.80485	CV
ROSE HALL	Installing two worms at EV and GBL Sluices	2	7282	14564	2.98562	CV
ROSE HALL	CIVIL STRUCTURES				867.50547	
ROSE HALL	Irrigator	10	72815	728150	149.27075	DI
ROSE HALL	Self-driven dam bed pumps- Irrigators	9	48543	436887	89.561835	DI
ROSE HALL	Irrigator/Tugs	6	48500	291000	59.655	DI
ROSE HALL	DRAINAGE & IRRIGATION				298.487585	
ROSE HALL	100 HP tractor	7	48544	339808	69.7	MECH
ROSE HALL	Spring Tines Implement	3	9709	29127	6.0	MECH
ROSE HALL	80/66 Tractor JD	4	38835	155340	31.8	MECH
ROSE HALL	Land conversion Cultivation	2000	1500	3000000	615.0	MECH
ROSE HALL	Excavator LR	7	176849.6842	1237947.789	253.8	MECH
ROSE HALL	Front end loader	1	121360	121360	24.9	MECH
ROSE HALL	Fertilizer applicator Implement	3	58252	174756	35.8	MECH
ROSE HALL	LGPL spreader Implement	3	58252	174756	35.8	MECH
ROSE HALL	Planting trailer Implement	4	12135	48540	10.0	MECH
ROSE HALL	Furrow opener Implement	4	7282	29128	6.0	MECH
ROSE HALL	Furrow coverer Implement	4	14563	58252	11.9	MECH
ROSE HALL	Tyre repair machine Tools	1	48550	48550	10.0	MECH
ROSE HALL	Trench cleaner Tractor	1	72815	72815	14.9	MECH
ROSE HALL	Backhoe Excavator	1	38835	38835	8.0	MECH
ROSE HALL	FWS Service unit Tools	1	72816	72816	14.9	MECH
ROSE HALL	Portable welding plant - Electrical Tools	6	19420	116520	23.9	MECH
ROSE HALL	Portable welding plant - Portable Tools	2	24270	48540	10.0	MECH
ROSE HALL	Lathe Tools	1	24272	24272	5.0	MECH
ROSE HALL	Boom Sprayer Implement	3	9709	29127	6.0	MECH
ROSE HALL	Bell Loader	4	75000	300000	61.5	
ROSE HALL	MECHANIZATION				1254.7	
ROSE HALL	180 HP Tractor	10	72815	728150	149.27075	TP
ROSE HALL	Mould Board Plow	10	9709	97090	19.90345	TP
ROSE HALL	Tandem Harrow	8	9709	77672	15.92276	TP
ROSE HALL	Low bed trailer	1	121360	121360	24.8788	TP
ROSE HALL	10/32 inverted harrow	4	29125	116500	23.8825	TP
ROSE HALL	TILLAGE & PLANTING				233.85826	

ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M	Cat
Blairmont	Cane Punts	300	4878	1463400	299.997	ACC
Blairmont	All weather road	25	24272	606800	124.394	ACC
Blairmont	45/66 Tractor JD	8	33980	271840	55.7272	ACC
Blairmont	55 Hp Tractop	4	24390.2439	97560.97561	20	ACC
Blairmont	Vehicles	7	3000	21000	4.305	ACC
Blairmont	Motor Cycle	25	1500	37500	7.6875	ACC
Blairmont	ACCIBILITY & CANE TRANSPORT				512.1107	
Blairmont	Heavy duty revetment Meters	1000	830	830000	170.15	CV
Blairmont	Light duty revetment Meters	10000	162	1620000	332.1	CV
Blairmont	Aqueduct	4	146341.4634	585365.8537	120	CV
Blairmont	High bridges	10	68293	682930	140.00065	CV
Blairmont	Sluice	1	146341.4634	146341.4634	30	CV
Blairmont	CIVIL STRUCTURES				792.25065	
Blairmont	Harvesters and associated equipment	2	780488	1560976	320	MECH
Blairmont	Tractors LGRP Spreader	4	80085	320341	65.7	MECH
Blairmont	LGRP SPREADER Implement	3	24390	73171	15.0	MECH
Blairmont	Boom Sprayer Implement	3	9756	29268	6.0	MECH
Blairmont	Fertilizer Hopper Implement	3	4878	14634	3.0	MECH
Blairmont	Land Development (840 Ha) Conversion	1056.74	1500	1585110	324.9	MECH
Blairmont	110 Hp Tractor	6	58537	351220	72.0	MECH
Blairmont	Bell Loader	3	75000	225000	46.1	
Blairmont	MECHANIZATION				852.7	
Blairmont	Dundi Ditcher	10	5000	50000	10.25	TP
Blairmont	160 HP Tractor	10	58252	582520	119.4166	TP
Blairmont	Trailing Final Harrow	8	9709	77672	15.92276	TP
Blairmont	Plows	10	7540	75400	15.457	TP
Blairmont	TILLAGE & PLANTING				161.04636	
East Demerara	Cane Transport - 45 hp tractor	10	19512	195122	40	ACC
East Demerara	All weather roads	30	61789	1853659	380	ACC
East Demerara	Establishing new link rear end of LBI	1	200000	200000	41	ACC
East Demerara	Punts	280	4878	1365840	279.9972	ACC
East Demerara	Vehicles	8	3000	24000	4.92	ACC
East Demerara	Motor Cycle	26	1500	39000	7.995	ACC
East Demerara	ACCIBILITY & CANE TRANSPORT				753.9122	
East Demerara	Modification of building/ facilities			97560.97561	20	CV
East Demerara	Admin building			195121.9512	40	CV
East Demerara	Fertilizer bond Building			195121.9512	40	CV
East Demerara	High Bridges - Concrete	12	58536.58537	702439	144	CV
East Demerara	Flat Bridges - Concrete	10	24390.2439	243902	50	CV
East Demerara	Light duty revetment along CNC Meters	8000	162	1296000	265.68	CV
East Demerara	Replacement of aqueduct	3	146341.4634	439024	90	CV
East Demerara	CIVIL STRUCTURES				649.68	
East Demerara	Drainage - Excavator	6	170731.7073	682926.8293	140	DI
East Demerara	DRAINAGE & IRRIGATION				140	
East Demerara	Crop Care - 100 hp Tractor - Repair work	12	80038	960455	196.9	MECH
East Demerara	Crop Care - 100 hp + boom sprayer Implement	6	82927	497561	102.0	MECH
East Demerara	Crop Care - 100 hp + dondi Implement	8	87805	702439	144.0	MECH
East Demerara	100 hp +fertilizer hopper Implement	6	82927	497561	102.0	MECH
East Demerara	Retooling of FWS Tools	1	73171	73171	15.0	MECH
East Demerara	Harvesters and associated equipment	3	750000	2250000	461.3	MECH
East Demerara	Bell Loader	3	75000	225000	46.1	
East Demerara	MECHANIZATION				1067.3	
East Demerara	Tillage - 100 hp Tractor with dondi	12	82926.82927	995122	204	TP
East Demerara	100 hp Tractor	8	68292.68293	546341	112	TP
East Demerara	Mould Board Plow	10	9709	97090	19.90345	TP
East Demerara	Tillage -150 hp tractor	13	82926.82927	1078049	221	TP
East Demerara	TILLAGE & PLANTING				556.90345	

ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M	Cat
Wales	ALL WEATHER ROADS	15	50000	750000	153.75	ACC
Wales	CANE PUNTS	180	4390.243902	790244	162	ACC
Wales	DUMP LORRY	1	30000	30000	6.15	ACC
Wales	Cane Transport - 45 hp tractor	10	19512.19512	195122	40	ACC
Wales	Vehicles	6	3000	18000	3.69	ACC
Wales	Motor Cycle	20	1500	30000	6.15	ACC
Wales	ACCIBILITY & CANE TRANSPORT				371.74	
Wales	FLAT BRIDGES	8	48780.4878	195121.9512	40	CV
Wales	LIGHT DUTY revetment : Meters	6000	162	972000	199.26	CV
Wales	HIGH BRIDGES	8	58536.58537	292682.9268	60	CV
Wales	CIVIL STRUCTURES				299.26	
Wales	Drainage - Excavator	6	170732	682927	140	DI
Wales	DRAINAGE & IRRIGATION				140	
Wales	110 Hp Tractor	7	69921.95122	489453.6585	100.338	MECH
Wales	MECHANIZATION				100.338	
Wales	Dundi Ditcher	8	5000	40000	8.2	TP
Wales	160 HP Tractor	8	58252	466016	95.53328	TP
Wales	Trailing Final Harrow	7	9709	67963	13.932415	TP
Wales	Plows	7	7540	52780	10.8199	TP
WALES	TILLAGE & PLANTING				128.485595	
Uitvlugt	Cane Punts	300	4878	1463400	299.997	ACC
Uitvlugt	All weather road	30	24272	728160	149.2728	ACC
Uitvlugt	45/66 Tractor JD	10	33980	339800	69.659	ACC
Uitvlugt	55 Hp Tractop	5	24390.2439	121951.2195	25	ACC
Uitvlugt	Vehicles	8	3000	24000	4.92	ACC
Uitvlugt	Motor Cycle	23	1500	34500	7.0725	ACC
Uitvlugt	ACCIBILITY & CANE TRANSPORT				555.9213	
Uitvlugt	High Bridges	10	70000	700000	143.5	CV
Uitvlugt	Acqueducts	6	100000	600000	123	CV
Uitvlugt	CIVIL STRUCTURES				266.5	
Uitvlugt	Drainage Pumps	2	650000	1300000	266.5	DI
Uitvlugt	Irrigators	10	50000	500000	102.5	DI
Uitvlugt	DRAINAGE & IRRIGATION				369	
Uitvlugt	Implements - Tillage	15	15000	225000	46.1	MECH
Uitvlugt	Excavators -	4	176850	707399	145.0	MECH
Uitvlugt	Tractors - LGRP	6	70000	420000	86.1	MECH
Uitvlugt	Spreaders - LGRP Implement	6	10000	60000	12.3	MECH
Uitvlugt	Tractors - Fertilising	4	69922	279688	57.3	MECH
Uitvlugt	Hoppers/Spreaders - Fertilising Implement	4	12000	48000	9.8	MECH
Uitvlugt	Tractors - Spraying	4	70000	280000	57.4	MECH
Uitvlugt	Boom Sprayers - Spraying Implement	4	7000	28000	5.7	MECH
Uitvlugt	Tractors - Inter Row Cultivation	4	70000	280000	57.4	MECH
Uitvlugt	Implements - Inter Row Cultivation	4	5000	20000	4.1	MECH
Uitvlugt	Harvesters with associated equipment	3	750000	2250000	461.3	MECH
Uitvlugt	Laser Leveling Implement	1	35000	35000	7.2	MECH
Uitvlugt	Extension and Upgrade of Workshop	1	1000000	1000000	205.0	MECH
Uitvlugt	Bell Loader	3	75000	225000	46.1	MECH
Uitvlugt	MECHANIZATION			5633087	1200.9	
Uitvlugt	Tractors - Planting	12	70000	840000	172.2	TP
Uitvlugt	Bell Loaders - Planting	3	80000	240000	49.2	TP
Uitvlugt	Trailers - Planting	10	5000	50000	10.25	TP
Uitvlugt	Dondi Tractors - Planting	6	70000	420000	86.1	TP
Uitvlugt	Dondi Ditchers - Planting	6	20000	120000	24.6	TP
Uitvlugt	TILLAGE & PLANTING			1670000	342.35	

MECHANIZATION INVESTMENTS					
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M
Skeldon	Harvesters and associated equipment	4	750000	3000000	615
Skeldon	Excavators	8	176850	1414797	290.0
Skeldon	Tractors - Fertilising	10	82143	821429	168.4
Skeldon	Boom Sprayer Implement	5	7000	35000	7.2
Skeldon	Land Conversion	2000	1500	3000000	615.0
Skeldon	Bell Loader	3	75000	225000	46.1
ALBION	Super long reach excavator	8	176850	1414797	290.0
ALBION	Spring Tines Implement	4	9709	38836	8.0
ALBION	Planting trailer Implement	4	12135	48540	10.0
ALBION	Furrow coverer Implement	2	14563	29126	6.0
ALBION	Harvesters and associated equipment	2	780488	1560976	320.0
ALBION	Tractors LGRP Spreader	8	82390	659123	135.1
ALBION	LGRP SPREADER Implement	5	24390	121950	25.0
ALBION	Land Conversion	1000	1500	1500000	307.5
ALBION	Dump lorry- 10 Ton Tools	3	31707	95121	19.5
ALBION	Trolley jack- 20 ton Tools	2	8536	17072	3.5
ALBION	FWS Service unit Tools	1	72816	72816	14.9
ALBION	Portable welding plant Tools	2	2184	4368	0.9
ALBION	Lathe Tools	1	24272	24272	5.0
ALBION	Distilling unit Tools	1	1951	1951	0.4
ALBION	Heavy duty tool kit Tools	8	2439	19512	4.0
ALBION	Floor crane Tools	1	19512	19512	4.0
ALBION	Air compressor Tools	2	3902	7804	1.6
ALBION	Lighting plant Tools	6	8780	52680	10.8
ALBION	Bell Loader	3	75000	225000	46.1
ROSE HALL	100 HP tractor	7	48544	339808	69.7
ROSE HALL	Spring Tines Implement	3	9709	29127	6.0
ROSE HALL	80/66 Tractor JD	4	38835	155340	31.8
ROSE HALL	Land conversion Cultivation	2000	1500	3000000	615.0
ROSE HALL	Excavator LR	7	176850	1237948	253.8
ROSE HALL	Front end loader Excavator	1	121360	121360	24.9
ROSE HALL	Fertilizer applicator Implement	3	58252	174756	35.8
ROSE HALL	LGPL spreader Implement	3	58252	174756	35.8
ROSE HALL	Planting trailer Implement	4	12135	48540	10.0
ROSE HALL	Furrow opener Implement	4	7282	29128	6.0
ROSE HALL	Furrow coverer Implement	4	14563	58252	11.9
ROSE HALL	Tyre repair machine Tools	1	48550	48550	10.0
ROSE HALL	Trench cleaner Tractor	1	72815	72815	14.9
ROSE HALL	Backhoe Excavator	1	38835	38835	8.0
ROSE HALL	FWS Service unit Tools	1	72816	72816	14.9
ROSE HALL	Portable welding plant - Electrical Tools	6	19420	116520	23.9
ROSE HALL	Portable welding plant - Portable Tools	2	24270	48540	10.0
ROSE HALL	Lathe Tools	1	24272	24272	5.0
ROSE HALL	Boom Sprayer Implement	3	9709	29127	6.0
ROSE HALL	Bell Loader	4	75000	300000	61.5
Blairmont	Harvesters and associated equipment	2	780488	1560976	320.0
Blairmont	Tractors LGRP Spreader	4	80085	320341	65.7
Blairmont	LGRP SPREADER Implement	3	24390	73171	15.0
Blairmont	Boom Sprayer Implement	3	9756	29268	6.0
Blairmont	Fertilizer Hopper Implement	3	4878	14634	3.0
Blairmont	Land Development (840 Ha) Conversion	1056.74	1500	1585110	324.9
Blairmont	110 Hp Tractor	6	58537	351220	72.0
Blairmont	Bell Loader	3	75000	225000	46.1
East Demerara	Crop Care - 100 hp Tractor - Repair work	12	80038	960455	196.9
East Demerara	Crop Care - 100 hp + boom sprayer Implement	6	82927	497561	102.0
East Demerara	Crop Care - 100 hp + dondi Implement	8	87805	702439	144.0
East Demerara	100 hp +fertilizer hopper Implement	6	82927	497561	102.0
East Demerara	Retooling of FWS Tools	1	73171	73171	15.0
East Demerara	Harvesters and associated equipment	3	750000	2250000	461.3
East Demerara	Bell Loader	3	75000	225000	46.1
Wales	110 Hp Tractor	7	69922	489454	100.3
Uitvlugt	Implements - Tillage	15	15000	225000	46.1
Uitvlugt	Excavators -	4	176850	707399	145.0
Uitvlugt	Tractors - LGRP	6	70000	420000	86.1
Uitvlugt	Spreaders - LGRP Implement	6	10000	60000	12.3
Uitvlugt	Tractors - Fertilising	4	69922	279688	57.3
Uitvlugt	Hoppers/Spreaders - Fertilising Implement	4	12000	48000	9.8
Uitvlugt	Tractors - Spraying	4	70000	280000	57.4
Uitvlugt	Boom Sprayers - Spraying Implement	4	7000	28000	5.7
Uitvlugt	Tractors - Inter Row Cultivation	4	70000	280000	57.4
Uitvlugt	Implements - Inter Row Cultivation	4	5000	20000	4.1
Uitvlugt	Harvesters with associated equipment	3	750000	2250000	461.3
Uitvlugt	Laser Leveling Implement	1	35000	35000	7.2
Uitvlugt	Extension and Upgrade of Workshop	1	1000000	1000000	205.0
Uitvlugt	Bell Loader	3	75000	225000	46.1
TOTAL				36243619	7429.9

MECHANIZATION INVESTMENTS BY MACHINE TYPE

BILLET HARVESTERS & ASSOCIATED EQUIPMENT						
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M	
HARVESTER & ASSOCIATED EQUIPMENT	Skeldon	Harvesters and associated equipment	4	750000	3000000	615
	ALBION	Harvesters and associated equipment	2	780488	1560976	320.0
	Blairmont	Harvesters and associated equipment	2	780488	1560976	320.0
	East Demerara	Harvesters and associated equipment	3	750000	2250000	461.3
	Uitvlugt	Harvesters with associated equipment	3	750000	2250000	461.3
	TOTAL		14		10621952	2177.5

EXCAVATOR						
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M	
EXCAVATOR	Skeldon	Excavators	8	176850	1414797	290.0
	ALBION	Super long reach excavator	8	176850	1414797	290.0
	ROSE HALL	Excavator LR	7	176850	1237948	253.8
	ROSE HALL	Front end loader Excavator	1	121360	121360	24.9
	ROSE HALL	Backhoe Excavator	1	38835	38835	8.0
	Uitvlugt	Excavators -	4	176850	707399	145.0
	TOTAL		29		4935136	1011.7

TRACTORS						
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M	
TRACTORS	Skeldon	Tractors - Fertilising	10	82143	821429	168.4
	ALBION	Tractors LGRP Spreader implement	8	82390	659123	135.1
	ROSE HALL	100 HP tractor	7	48544	339808	69.7
	ROSE HALL	80/66 Tractor JD	4	38835	155340	31.8
	ROSE HALL	Trench cleaner Tractor	1	72815	72815	14.9
	Blairmont	Tractors LGRP Spreader	4	80085	320341	65.7
	Blairmont	110 Hp Tractor	6	58537	351220	72.0
	East Demerara	Crop Care - 100 hp Tractor - Repair work	12	80038	960455	196.9
	Wales	110 Hp Tractor	7	69922	489454	100.3
	Uitvlugt	Tractors - LGRP	6	70000	420000	86.1
	Uitvlugt	Tractors - Fertilising	4	69922	279688	57.3
	Uitvlugt	Tractors - Spraying	4	70000	280000	57.4
	Uitvlugt	Tractors - Inter Row Cultivation	4	70000	280000	57.4
	TOTAL		77		5429672	1113.1

IMPLEMENTS						
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M	
IMPLEMENTS	Skeldon	Boom Sprayer Implement	5	7000	35000	7.2
	ALBION	Spring Tines Implement	4	9709	38836	8.0
	ALBION	Planting trailer Implement	4	12135	48540	10.0
	ALBION	Furrow coverer Implement	2	14563	29126	6.0
	ALBION	LGRP SPREADER Implement	5	24390	121950	25.0
	ROSE HALL	Spring Tines Implement	3	9709	29127	6.0
	ROSE HALL	Fertilizer applicator Implement	3	58252	174756	35.8
	ROSE HALL	LGPL spreader Implement	3	58252	174756	35.8
	ROSE HALL	Planting trailer Implement	4	12135	48540	10.0
	ROSE HALL	Furrow opener Implement	4	7282	29128	6.0
	ROSE HALL	Furrow coverer Implement	4	14563	58252	11.9
	ROSE HALL	Boom Sprayer Implement	3	9709	29127	6.0
	Blairmont	LGRP SPREADER Implement	3	24390	73171	15.0
	Blairmont	Boom Sprayer Implement	3	9756	29268	6.0
	Blairmont	Fertilizer Hopper Implement	3	4878	14634	3.0
	East Demerara	Crop Care - 100 hp + boom sprayer Implement	6	82927	497561	102.0
	East Demerara	Crop Care - 100 hp + dondi Implement	8	87805	702439	144.0
	East Demerara	100 hp +fertilizer hopper Implement	6	82927	497561	102.0
	Uitvlugt	Implements - Tillage	15	15000	225000	46.1
	Uitvlugt	Spreaders - LGRP Implement	6	10000	60000	12.3
	Uitvlugt	Hoppers/Spreaders - Fertilising Implement	4	12000	48000	9.8
	Uitvlugt	Boom Sprayers - Spraying Implement	4	7000	28000	5.7
	Uitvlugt	Implements - Inter Row Cultivation	4	5000	20000	4.1
	Uitvlugt	Laser Leveling Implement	1	35000	35000	7.2
	TOTAL				3047772	624.8

LAND CONVERSION						
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M	
LAND CONVERSION	Skeldon	Land Conversion	2000	1500	3000000	615.0
	ALBION	Land Conversion	1000	1500	1500000	307.5
	ROSE HALL	Land conversion Cultivation	2000	1500	3000000	615
	Blairmont	Land Development (840 Ha) Conversion	1056.74	1500	1585110	324.9
	TOTAL		6057		9085110	1862.4

TOOLS						
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M	
TOOLS	ALBION	Dump lorry- 10 Ton Tools	3	31707	95121	19.5
	ALBION	Trolley jack- 20 ton Tools	2	8536	17072	3.5
	ALBION	FWS Service unit Tools	1	72816	72816	14.9
	ALBION	Portable welding plant Tools	2	2184	4368	0.9
	ALBION	Lathe Tools	1	24272	24272	5.0
	ALBION	Distilling unit Tools	1	1951	1951	0.4
	ALBION	Heavy duty tool kit Tools	8	2439	19512	4.0
	ALBION	Floor crane Tools	1	19512	19512	4.0
	ALBION	Air compressor Tools	2	3902	7804	1.6
	ALBION	Lighting plant Tools	6	8780	52680	10.8
	ROSE HALL	Tyre repair machine Tools	1	48550	48550	10.0
	ROSE HALL	FWS Service unit Tools	1	72816	72816	14.9
	ROSE HALL	Portable welding plant - Electrical Tools	6	19420	116520	23.9
	ROSE HALL	Portable welding plant - Portable Tools	2	24270	48540	10.0
	ROSE HALL	Lathe Tools	1	24272	24272	5.0
	East Demerara	Retooling of FWS Tools	1	73171	73171	15.0
	TOTAL				698977	143.3

BELL LOADERS						
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M	
BELL LOADERS	Skeldon	Bell Loader	3	75000	225000	46.1
	ALBION	Bell Loader	3	75000	225000	46.1
	ROSE HALL	Bell Loader	4	75000	300000	61.5
	Blairmont	Bell Loader	3	75000	225000	46.1
	East Demerara	Bell Loader	3	75000	225000	46.1
	Uitvlugt	Bell Loader	3	75000	225000	46.1
	TOTAL				1425000	292.1

FIELD WORKSHOP UPGRADE						
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M	
FIELD WORKSHOP UPGRADE	Uitvlugt	Extension and Upgrade of Workshop	1	1000000	1000000	205
	TOTAL				1000000	205.0

ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M	
GRAND TOTAL				36243619	7429.9	

AGRICULTURE CAPITAL INVESTMENT									
ESTATE	Description	AGRIC CAPITAL G\$M					TOTAL	TOTAL US \$	TOTAL G\$M
		2016	2017	2018	2019	2020			
Skeldon	ACCESSIBILITY & CANE TRANSPORT	322.7	322.7	322.7	322.7	322.7	1613.6	7871440	1613.6
	CIVIL STRUCTURES	192.6	192.6	192.6	192.6	192.6	962.9	4697075	962.9
	DRAINAGE & IRRIGATION	32.0	32.0	32.0	32.0	32.0	160.0	780488	160.0
	MECHANIZATION	348.3	348.3	348.3	348.3	348.3	1741.7	8496226	1741.7
	TILLAGE & PLANTING	32.2	32.2	32.2	32.2	32.2	161.0	785241	161.0
TOTAL	SKELDON	927.8	927.8	927.8	927.8	927.8	4639.2	22630470	4639.2
Albion	ACCESSIBILITY & CANE TRANSPORT	230.4	230.4	230.4	230.4	230.4	1152.1	5620220	1152.1
	CIVIL STRUCTURES	241.8	241.8	241.8	241.8	241.8	1209.0	5897416	1209.0
	MECHANIZATION	242.5	242.5	242.5	242.5	242.5	1212.3	5913456	1212.3
	TILLAGE & PLANTING	51.7	51.7	51.7	51.7	51.7	258.3	1259864	258.3
	TOTAL	ALBION	766.3	766.3	766.3	766.3	766.3	3831.6	18690956
Rose Hall	ACCESSIBILITY & CANE TRANSPORT	119.8	119.8	119.8	119.8	119.8	599.2	2923075	599.2
	CIVIL STRUCTURES	173.5	173.5	173.5	173.5	173.5	867.5	4231734	867.5
	DRAINAGE & IRRIGATION	59.7	59.7	59.7	59.7	59.7	298.5	1456037	298.5
	MECHANIZATION	250.9	250.9	250.9	250.9	250.9	1254.7	6120490	1254.7
	TILLAGE & PLANTING	46.8	46.8	46.8	46.8	46.8	233.9	1140772	233.9
TOTAL	ROSE HALL	650.8	650.8	650.8	650.8	650.8	3253.8	15872108	3253.8
Blairmont	ACCESSIBILITY & CANE TRANSPORT	102.4	102.4	102.4	102.4	102.4	512.1	2498101	512.1
	CIVIL STRUCTURES	158.5	158.5	158.5	158.5	158.5	792.3	3864637	792.3
	MECHANIZATION	170.5	170.5	170.5	170.5	170.5	852.7	4159720	852.7
	TILLAGE & PLANTING	32.2	32.2	32.2	32.2	32.2	161.0	785592	161.0
TOTAL	Blairmont	463.6	463.6	463.6	463.6	463.6	2318.2	11308050	2318.2
East Demerara	ACCESSIBILITY & CANE TRANSPORT	150.8	150.8	150.8	150.8	150.8	753.9	3677620	753.9
	CIVIL STRUCTURES	129.9	129.9	129.9	129.9	129.9	649.7	3169171	649.7
	DRAINAGE & IRRIGATION	28.0	28.0	28.0	28.0	28.0	140.0	682927	140.0
	MECHANIZATION	213.5	213.5	213.5	213.5	213.5	1067.3	5206187	1067.3
	TILLAGE & PLANTING	111.4	111.4	111.4	111.4	111.4	556.9	2716602	556.9
TOTAL	East Demerara	633.6	633.6	633.6	633.6	633.6	3167.8	15452507	3167.8
Wales	ACCESSIBILITY & CANE TRANSPORT	74.3	74.3	74.3	74.3	74.3	371.7	1813366	371.7
	CIVIL STRUCTURES	59.9	59.9	59.9	59.9	59.9	299.3	1459805	299.3
	DRAINAGE & IRRIGATION	28.0	28.0	28.0	28.0	28.0	140.0	682927	140.0
	MECHANIZATION	20.1	20.1	20.1	20.1	20.1	100.3	489454	100.3
	TILLAGE & PLANTING	25.7	25.7	25.7	25.7	25.7	128.5	626759	128.5
TOTAL	WALES	208.0	208.0	208.0	208.0	208.0	1039.8	5072310	1039.8
Uitvlugt	ACCESSIBILITY & CANE TRANSPORT	111.2	111.2	111.2	111.2	111.2	555.9	2711811	555.9
	CIVIL STRUCTURES	53.3	53.3	53.3	53.3	53.3	266.5	1300000	266.5
	DRAINAGE & IRRIGATION	73.8	73.8	73.8	73.8	73.8	369.0	1800000	369.0
	MECHANIZATION	240.2	240.2	240.2	240.2	240.2	1200.9	5858087	1200.9
	TILLAGE & PLANTING	68.5	68.5	68.5	68.5	68.5	342.4	1670000	342.4
TOTAL	Uitvlugt	546.9	546.9	546.9	546.9	546.9	2734.7	13339898	2734.7
INDUSTRY	ACCESSIBILITY & CANE TRANSPORT	1111.7	1111.7	1111.7	1111.7	1111.7	5558.7	27115634	5558.7
	CIVIL STRUCTURES	1009.4	1009.4	1009.4	1009.4	1009.4	5047.1	24619838	5047.1
	DRAINAGE & IRRIGATION	221.5	221.5	221.5	221.5	221.5	1107.5	5402378	1107.5
	MECHANIZATION	1486.0	1486.0	1486.0	1486.0	1486.0	7429.9	36243619	7429.9
	TILLAGE & PLANTING	368.4	368.4	368.4	368.4	368.4	1841.9	8984830	1841.9
TOTAL		4197.0	4197.0	4197.0	4197.0	4197.0	20985.1	102366299	20985.1

TILLAGE & PLANTING INVESTMENTS					
Estate	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M
Skeldon	Tillage tractors	9	70000	630000	129.2
Skeldon	Trailing Final Harrow	9	9709	87381	17.9
Skeldon	Plows	9	7540	67860	13.9
ALBION	160 HP Tractor	12	58252	699024	143.3
ALBION	Trailing Final Harrow	10	9709	97090	19.9
ALBION	Plows	10	7540	75400	15.5
ALBION	Tractor 100hp	10	38835	388350	79.6
ROSE HALL	180 HP Tractor	10	72815	728150	149.3
ROSE HALL	Mould Board Plow	10	9709	97090	19.9
ROSE HALL	Tandem Harrow	8	9709	77672	15.9
ROSE HALL	Low bed trailer	1	121360	121360	24.9
ROSE HALL	10/32 inverted harrow	4	29125	116500	23.9
Blairmont	Dundi Ditcher	10	5000	50000	10.3
Blairmont	160 HP Tractor	10	58252	582520	119.4
Blairmont	Trailing Final Harrow	8	9709	77672	15.9
Blairmont	Plows	10	7540	75400	15.5
East Demerara	Tillage - 100 hp Tractor with dondi	12	82927	995122	204
East Demerara	100 hp Tractor	8	68293	546341	112
East Demerara	Mould Board Plow	10	9709	97090	19.9
East Demerara	Tillage -150 hp tractor	13	82927	1078049	221
Wales	Dundi Ditcher	8	5000	40000	8.2
Wales	160 HP Tractor	8	58252	466016	95.5
Wales	Trailing Final Harrow	7	9709	67963	13.9
Wales	Plows	7	7540	52780	10.8
Uitvlugt	Tractors - Planting	12	70000	840000	172.2
Uitvlugt	Bell Loaders - Planting	3	80000	240000	49.2
Uitvlugt	Trailers - Planting	10	5000	50000	10.3
Uitvlugt	Dondi Tractors - Planting	6	70000	420000	86.1
Uitvlugt	Dondi Ditchers - Planting	6	20000	120000	24.6
TOTAL				8984830	1841.9

TILLAGE & PLANTING INVESTMENTS BY MACHINE TYPE

TRACTORS						
Estate	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M	
TRACTORS	Skeldon	Tillage tractors	9	70000	630000	129.2
	ALBION	160 HP Tractor	12	58252	699024	143.3
	ALBION	Tractor 100hp	10	38835	388350	79.6
	ROSE HALL	180 HP Tractor	10	72815	728150	149.3
	Blairmont	160 HP Tractor	10	58252	582520	119.4
	East Demerara	Tillage - 100 hp Tractor with dondi	12	82927	995122	204
	East Demerara	100 hp Tractor	8	68293	546341	112
	East Demerara	Tillage -150 hp tractor	13	82927	1078049	221
	Wales	160 HP Tractor	8	58252	466016	95.5
	Uitvlugt	Tractors - Planting	12	70000	840000	172.2
	Uitvlugt	Dondi Tractors - Planting	6	70000	420000	86.1
	TOTAL		110		7373572	1511.6

HARROW						
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M	
HARROW	Skeldon	Trailing Final Harrow	9	9709	87381	17.9
	ALBION	Trailing Final Harrow	10	9709	97090	19.9
	ROSE HALL	Tandem Harrow	8	9709	77672	15.9
	ROSE HALL	10/32 inverted harrow	4	29125	116500	23.9
	Blairmont	Trailing Final Harrow	8	9709	77672	15.9
	Wales	Trailing Final Harrow	7	9709	67963	13.9
	TOTAL		46		524278	107.5

PLOWS						
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M	
PLOWS	Skeldon	Plows	9	7540	67860	13.9
	ALBION	Plows	10	7540	75400	15.5
	ROSE HALL	Mould Board Plow	10	9709	97090	19.9
	Blairmont	Plows	10	7540	75400	15.5
	East Demerara	Mould Board Plow	10	9709	97090	19.90345
	Wales	Plows	7	7540	52780	10.8
	TOTAL		56		465620	95.5

TRAILERS						
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M	
TRAILERS	ROSE HALL	Low bed trailer	1	121360	121360	24.9
	Uitvlugt	Trailers - Planting	10	5000	50000	10.3
	TOTAL		11		171360	35.1

DITCHERS						
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M	
DITCHERS	Blairmont	Dundi Ditcher	10	5000	50000	10.3
	Wales	Dundi Ditcher	8	5000	40000	8.2
	Uitvlugt	Dondi Ditchers - Planting	6	20000	120000	24.6
	TOTAL		24		210000	43.05

BELL LOADER						
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M	
BELL LOADERS	Uitvlugt	Bell Loaders - Planting	3	80000	240000	49.2
	TOTAL		3		240000	49.2

ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M	
GRAND TOTAL				8984830	1841.9	

ACCESSIBILITY & CANE TRANSPORT INVESTMENTS					
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M
Skeldon	All weather roads	20	120000	2400000	492
Skeldon	Cane Punts	400	4878	1951200	400.0
Skeldon	45/66 Tractor JD	5	33980	169900	34.8
Skeldon	Husbandry tractors	10	70000	700000	143.5
ALBION	45 HP Tractor	10	48544	485440	99.5
ALBION	Cane Punts	250	4878	1219500	250.0
ALBION	Paddle tugs	3	7318	21954	4.5
ALBION	All weather road	15	97561	1463415	300.0
ROSE HALL	Prime Mover-Mahendra Tractor	1	48544	48544	10.0
ROSE HALL	Cane Punts	250	4878	1219500	250.0
ROSE HALL	45/66 Tractor JD	5	33980	169900	34.8
ROSE HALL	Motor Grader	1	97087	97087	19.9
ROSE HALL	All weather road	15	24272	364080	74.6
Blairmont	Cane Punts	160	4878	780480	160.0
Blairmont	All weather road	10	24272	242720	49.8
Blairmont	45/66 Tractor JD	5	33980	169900	34.8
Blairmont	55 Hp Tractor	2	24390.2439	48780	10.0
East Demerara	Cane Transport - 45 hp tractor	6	19512	117073	24.0
East Demerara	All weather roads	15	61789	926829	190.0
East Demerara	Establishing new link Road rear end of LBI	1	200000	200000	41.0
East Demerara	Punts	150	4878	731700	150.0
Wales	ALL WEATHER ROADS	3	50000	150000	30.8
Wales	CANE PUNTS	100	4390.243902	439024	90.0
Wales	DUMP LORRY	1	30000	30000	6.2
Wales	Cane Transport - 45 hp tractor	6	19512.19512	117073	24.0
Uitvlugt	Cane Punts	160	4878	780480	160.0
Uitvlugt	All weather road	10	24272	242720	49.8
Uitvlugt	45/66 Tractor JD	5	33980	169900	34.8
Uitvlugt	55 Hp Tractor	2	24390.2439	48780	10.0
TOTAL				15505981	3178.7

ALL WEATHER ROADS						
ESTATE	Description	Quantity KM	Unit Price US\$	Cost US\$	Cost G\$M	
ROADS	Skeldon	All weather roads	20	120000	2400000	492
	ALBION	All weather road	15	97561	1463415	300.0
	ROSE HALL	All weather road	15	24272	364080	74.6
	Blairmont	All weather road	10	24272	242720	49.8
	East Demerara	All weather roads	15	61788.61789	926829	190.0
	East Demerara	Establishing new link Road rear end of LBI	1	200000	200000	41.0
	Wales	ALL WEATHER ROADS	3	50000	150000	30.8
	Uitvlugt	All weather road	10	24272	242720	49.8
	TOTAL		89		5989764	1227.9

CANE PUNTS						
ESTATE	Description	Quantity Each	Unit Price US\$	Cost US\$	Cost G\$M	
CANE PUNTS	Skeldon	Cane Punts	400	4878	1951200	400.0
	ALBION	Cane Punts	250	4878	1219500	250.0
	ROSE HALL	Cane Punts	250	4878	1219500	250.0
	Blairmont	Cane Punts	160	4878	780480	160.0
	East Demerara	Punts	150	4878	731700	150.0
	Wales	CANE PUNTS	100	4390	439024	90.0
	Uitvlugt	Cane Punts	160	4878	780480	160.0
	TOTAL		1470		7121884	1460.0

CANE TRANSPORT TRACTORS						
ESTATE	Description	Quantity Each	Unit Price US\$	Cost US\$	Cost G\$M	
TRACTORS	Skeldon	45/66 Tractor JD	5	33980	169900	34.8
	Skeldon	55 HP tractors With Winch	10	70000	700000	143.5
	ALBION	45 HP Tractor	10	48544	485440	99.5
	ROSE HALL	Prime Mover-Mahendra Tractor	1	48544	48544	10.0
	ROSE HALL	45/66 Tractor JD	5	33980	169900	34.8
	Blairmont	45/66 Tractor JD	5	33980	169900	34.8
	Blairmont	55 Hp Tractor	2	24390.2439	48780	10.0
	East Demerara	Cane Transport - 45 hp tractor	6	19512.19512	117073	24.0
	Wales	Cane Transport - 45 hp tractor	6	19512.19512	117073	24.0
	Uitvlugt	45/66 Tractor JD	5	33980	169900	34.8
	Uitvlugt	55 Hp Tractor	2	24390.2439	48780	10.0
	TOTAL		57		2245291	460.3

TUGS						
ESTATE	Description	Quantity Each	Unit Price US\$	Cost US\$	Cost G\$M	
TUGS	ALBION	Paddle tug engines	3	7318	21954	4.5
	TOTAL		3		21954	4.5

GRADER						
ESTATE	Description	Quantity Each	Unit Price US\$	Cost US\$	Cost G\$M	
GRADER	ROSE HALL	Motor Grader	1	97087	97087	19.9
	TOTAL		1		97087	19.9

DUMP LORRY						
ESTATE	Description	Quantity Each	Unit Price US\$	Cost US\$	Cost G\$M	
Dump Lorry	Wales	DUMP LORRY	1	30000	30000	6.2
	TOTAL		1		30000	6.2

				Cost US\$	Cost G\$M
GRAND TOTAL				15505981.0	3178.7

CIVIL INFRASTRUCTURE INVESTMENTS						
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M	
Skeldon	High bridges	8	68,293	546,344	112.0	
Skeldon	Aqueducts	6	46,341	278,046	57.0	
Skeldon	Heavy duty revetment - Meters	1000	830	830,000	170.2	
Skeldon	Heavy duty revetment Meters	1000	830	830,000	170.2	
Skeldon	Light duty revetment Meters	4000	162	648,000	132.8	
ALBION	High bridges	10	68,293	682,930	140.0	
ALBION	Aqueducts	6	46,341	278,046	57.0	
ALBION	Heavy duty revetment - Meters	2000	830	1,660,000	340.3	
ALBION	Heavy duty revetment : Meters	1000	830	830,000	170.2	
ALBION	Light duty revetment : Meters	7000	162	1,134,000	232.5	
ROSE HALL	Heavy duty revetment – Meters	1000	830	830,000	170.2	
ROSE HALL	Heavy duty revetment :- Meters	1000	830	830,000	170.2	
ROSE HALL	Light duty revetment :- Meters	6000	162	972,000	199.3	
ROSE HALL	Check Sluices to control water in low lying areas	8	19,417	155,336	31.8	
ROSE HALL	Installing two worms at EV and GBL Sluices	2	7,282	14,564	3.0	
Blairmont	Heavy duty revetment Meters	500	830	415,000	85.1	
Blairmont	Light duty revetment Meters	2000	162	324,000	66.4	
Blairmont	Aqueduct	4	146,341	585,366	120.0	
Blairmont	High bridges	4	68,293	273,172	56.0	
Blairmont	Sluice	1	146,341	146,341	30.0	
East Demerara	Modification of building/ facilities			97,561	20.0	
East Demerara	Admin building			195,122	40.0	
East Demerara	Fertilizer bond- Building			195,122	40.0	
East Demerara	High Bridges - Concrete	4	58,537	234,146	48.0	
East Demerara	Flat Bridges - Concrete	4	24,390	97,561	20.0	
East Demerara	Light duty revetment along CNC Meters	2000	162	324,000	66.4	
East Demerara	Replacement of aqueduct	1	146,341	146,341	30.0	
Wales	FLAT BRIDGES	4	48,780	195,122	40.0	
Wales	LIGHT DUTY revetment : Meters	2000	162	324,000	66.4	
Wales	HIGH BRIDGES	5	58,537	292,683	60.0	
Uitvlugt	High Bridges	6	70,000	420,000	86.1	
Uitvlugt	Aqueducts	5	100,000	500,000	102.5	
TOTAL				15,284,804	3133.4	

CIVILS INFRACTURE INVESTMENTS BY TYPE

BRIDGES						
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M	
BRIDGES	Skeldon	High bridges	8	68,293	546,344	112
	ALBION	High bridges	10	68,293	682,930	140
	Blairmont	High bridges	4	68,293	273,172	56
	East Demerara	High Bridges - Concrete	4	58,537	234,146	48
	East Demerara	Flat Bridges - Concrete	4	24,390	97,561	20
	Wales	FLAT BRIDGES	4	48,780	195,122	40
	Wales	HIGH BRIDGES	5	58,537	292,683	60
	Uitvlugt	High Bridges	6	70,000	420,000	86
	TOTAL		45		2,741,958.20	562

AQUEDUCT						
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M	
AQUEDUCTS	Skeldon	Aqueducts	6	46341	278,046	57
	ALBION	Aqueducts	6	46341	278,046	57
	Blairmont	Aqueduct	4	146341	585,366	120
	East Demerara	Replacement of aqueduct	1	146341	146,341	30
	Uitvlugt	Aqueducts	5	100000	500,000	103
	TOTAL		22		1,787,799.32	366

REVETMENT						
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M	
REVETMENT	Skeldon	Heavy duty revetment - Meters	1000	830	830,000	170
	Skeldon	Heavy duty revetment Meters	1000	830	830,000	170
	Skeldon	Light duty revetment Meters	4000	162	648,000	133
	ALBION	Heavy duty revetment - Meters	2000	830	1,660,000	340
	ALBION	Heavy duty revetment : Meters	1000	830	830,000	170
	ALBION	Light duty revetment : Meters	7000	162	1,134,000	232
	ROSE HALL	Heavy duty revetment – Meters	1000	830	830,000	170
	ROSE HALL	Heavy duty revetment :- Meters	1000	830	830,000	170
	ROSE HALL	Light duty revetment :- Meters	6000	162	972,000	199
	Blairmont	Heavy duty revetment Meters	500	830	415,000	85
	Blairmont	Light duty revetment Meters	2000	162	324,000	66
	East Demerara	Light duty revetment along CNC Meters	2000	162	324,000	66
	Wales	LIGHT DUTY revetment : Meters	2000	162	324,000	66
	TOTAL		30500		9,951,000.00	2,040

SLUICES						
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M	
SLUICE	ROSE HALL	Building Check Sluices to control water in low lying areas	8	19417	155,336	32
	ROSE HALL	Installing two worms at EV and GBL Sluices	2	7282	14,564	3
	Blairmont	Sluice	1	146341	146,341	30
	TOTAL		11		316,241.46	65

BUILDINGS						
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M	
BUILDINGS	East Demerara	Modification of building/ facilities			97,561	20
	East Demerara	Admin building			195,122	40
	East Demerara	Fertilizer bond- Building			195,122	40
	TOTAL				487,804.88	100

ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M	
GRAND TOTAL				15,284,804	3,133	

DRAINAGE & IRRIGATION INVESTMENTS					
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M
Skeldon	Overhead Irrigators	6	97561	585366	120
ROSE HALL	Irrigator	7	72815	509705	104.5
ROSE HALL	Self-driven dam bed pumps- Irrigators	6	48543	291258	59.7
ROSE HALL	Irrigator/Tugs	4	48500	194000	39.8
East Demerara	Drainage - Excavator	4	170732	682927	140.0
Wales	Drainage - Excavator	4	170732	682927	140.0
Uitvlugt	Drainage Pumps	2	650000	1300000	266.5
Uitvlugt	Irrigators	4	50000	200000	41.0
TOTAL				4446183	911.5

DRAINAGE & IRRIGATION INVESTMENYS BY MACHINE TYPE

IRRIGATORS						
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M	
IRRIGATORS	Skeldon	Overhead Irrigators	6	97561	585366	120
	ROSE HALL	Irrigator	7	72815	509705	104.5
	ROSE HALL	Self-driven dam bed pumps- Irrigators	6	48543	291258	59.7
	ROSE HALL	Irrigator/Tugs	4	48500	194000	39.8
	Uitvlugt	Irrigators	4	50000	200000	41.0
	TOTAL		27		1780329	365.0

EXCAVATOR						
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M	
EXCAVATORS	East Demerara	Drainage - Excavator	4	170732	682927	140.0
	Wales	Drainage - Excavator	4	170732	682927	140.0
	TOTAL		8		1365854	280

DRAINAGE PUMPS						
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M	
DRAINAGE PUMPS	Uitvlugt	Drainage Pumps	2	650000	1300000	266.5
	TOTAL		2		1300000	266.5

ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M
GRAND TOTAL				4446182.5	911.5

AGRICULTURE CAPITAL INVESTMENT						
ESTATE	Description	AGRIC CAPITAL G\$M				TOTAL US \$
		2015	2016	2017	TOTAL	
Skeldon	ACCESSIBILITY & CANE TRANSPORT	356.8	356.8	356.8	1070.3	5221100
	CIVIL STRUCTURES	214.0	214.0	214.0	642.1	3132390
	DRAINAGE & IRRIGATION	40.0	40.0	40.0	120.0	585366
	MECHANIZATION	459.9	459.9	459.9	1379.7	6730248
	TILLAGE & PLANTING	35.8	35.8	35.8	107.3	523494
TOTAL	SKELDON	1106.5	1106.5	1106.5	3319.5	16192598
ALBION	ACCESSIBILITY & CANE TRANSPORT	218.0	218.0	218.0	654.0	3190309
	CIVIL STRUCTURES	313.3	313.3	313.3	939.9	4584976
	MECHANIZATION	270.2	270.2	270.2	810.7	3954391
	TILLAGE & PLANTING	22.0	22.0	22.0	65.9	321421
	TOTAL	ALBION	823.5	823.5	823.5	2470.5
ROSE HALL	ACCESSIBILITY & CANE TRANSPORT	129.8	129.8	129.8	389.3	1899111
	CIVIL STRUCTURES	191.5	191.5	191.5	574.4	2801900
	DRAINAGE & IRRIGATION	68.0	68.0	68.0	204.0	994963
	MECHANIZATION	344.4	344.4	344.4	1033.1	5039601
	TILLAGE & PLANTING	47.1	47.1	47.1	141.3	689316
TOTAL	ROSE HALL	780.7	780.7	780.7	2342.1	11424891
Blairmont	ACCESSIBILITY & CANE TRANSPORT	84.9	84.9	84.9	254.6	1241880
Blairmont	CIVIL STRUCTURES	119.2	119.2	119.2	357.5	1743879
Blairmont	MECHANIZATION	198.2	198.2	198.2	594.6	2900573
Blairmont	TILLAGE & PLANTING	20.7	20.7	20.7	62.0	302586
TOTAL	Blairmont	422.9	422.9	422.9	1268.7	6188919
East Demerara	ACCESSIBILITY & CANE TRANSPORT	135.0	135.0	135.0	405.0	1975602
	CIVIL STRUCTURES	88.1	88.1	88.1	264.4	1289854
	DRAINAGE & IRRIGATION	46.7	46.7	46.7	140.0	682927
	MECHANIZATION	289.3	289.3	289.3	867.9	4233756
	TILLAGE & PLANTING	97.7	97.7	97.7	293.0	1429033
TOTAL	East Demerara	656.8	656.8	656.8	1970.3	9611172
Wales	ACCESSIBILITY & CANE TRANSPORT	50.3	50.3	50.3	150.9	736098
Wales	CIVIL STRUCTURES	55.5	55.5	55.5	166.4	811805
Wales	DRAINAGE & IRRIGATION	46.7	46.7	46.7	140.0	682927
Wales	MECHANIZATION	23.9	23.9	23.9	71.7	349610
WALES	TILLAGE & PLANTING	20.7	20.7	20.7	62.0	302586
TOTAL	WALES	197.0	197.0	197.0	591.0	2883025
Uitvlugt	ACCESSIBILITY & CANE TRANSPORT	84.9	84.9	84.9	254.6	1241880
	CIVIL STRUCTURES	62.9	62.9	62.9	188.6	920000
	DRAINAGE & IRRIGATION	102.5	102.5	102.5	307.5	1500000
	MECHANIZATION	336.6	336.6	336.6	1009.7	4925243
	TILLAGE & PLANTING	77.2	77.2	77.2	231.7	1130000
TOTAL	Uitvlugt	664.0	664.0	664.0	1992.0	9717123
INDUSTRY	ACCESSIBILITY & CANE TRANSPORT	1059.6	1059.6	1059.6	3178.7	15505981
	CIVIL STRUCTURES	1044.5	1044.5	1044.5	3133.4	15284804
	DRAINAGE & IRRIGATION	303.8	303.8	303.8	911.5	4446183
	MECHANIZATION	1922.5	1922.5	1922.5	5767.4	28133423
	TILLAGE & PLANTING	321.1	321.1	321.1	963.2	4698436
TOTAL		4651.4	4651.4	4651.4	13954.1	68068826

AGRICULTURE CAPITAL INVESTMENT						
	Description	AGRIC CAPITAL G\$M				TOTAL US \$
		2015	2016	2017	TOTAL	
INDUSTRY	MECHANIZATION	1922.5	1922.5	1922.5	5767.4	28133423
	DRAINAGE & IRRIGATION	303.8	303.8	303.8	911.5	4446183
	CIVIL STRUCTURES	1044.5	1044.5	1044.5	3133.4	15284804
	ACCESSIBILITY & CANE TRANSPORT	1059.6	1059.6	1059.6	3178.7	15505981
	TILLAGE & PLANTING	321.1	321.1	321.1	963.2	4698436
TOTAL	TOTAL	4651.4	4651.4	4651.4	13954.1	68068826

MECHANIZATION INVESTMENTS					
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M
Skeldon	Harvesters and associated equipment	3	750,000	2,250,000	461.3
Skeldon	Excavators	5	176,850	884,248	181.3
Skeldon	Tractors - Fertilising	7	82,143	575,000	117.9
Skeldon	Boom Sprayer Implement	3	7,000	21,000	4.3
Skeldon	Land Conversion	2000	1,500	3,000,000	615.0
ALBION	Super long reach excavator	5	176,850	884,248	181.3
ALBION	Spring Tines Implement	2	9,709	19,418	4.0
ALBION	Planting trailer Implement	2	12,135	24,270	5.0
ALBION	Furrow coverer Implement	1	14,563	14,563	3.0
ALBION	Harvesters and associated equipment	1	780,488	780,488	160.0
ALBION	Tractors LGRP Spreader	6	82,390	494,342	101.3
ALBION	LGRP SPREADER Implement	1	24,390	24,390	5.0
ALBION	Land Conversion	1000	1,500	1,500,000	307.5
ALBION	Dump lorry- 10 Ton Tools	1	31,707	31,707	6.5
ALBION	Trolley jack- 20 ton Tools	2	8,536	17,072	3.5
ALBION	FWS Service unit Tools	1	72,816	72,816	14.9
ALBION	Portable welding plant Tools	2	2,184	4,368	0.9
ALBION	Lathe Tools	1	24,272	24,272	5.0
ALBION	Distilling unit Tools	1	1,951	1,951	0.4
ALBION	Heavy duty tool kit Tools	8	2,439	19,512	4.0
ALBION	Floor crane Tools	1	19,512	19,512	4.0
ALBION	Air compressor Tools	1	3,902	3,902	0.8
ALBION	Lighting plant Tools	2	8,780	17,560	3.6
ROSE HALL	100 HP tractor	5	48,544	242,720	49.8
ROSE HALL	Spring Tines Implement	2	9,709	19,418	4.0
ROSE HALL	80/66 Tractor JD	2	38,835	77,670	15.9
ROSE HALL	Land conversion Cultivation	2000	1,500	3,000,000	615.0
ROSE HALL	Excavator LR	5	176,850	884,248	181.3
ROSE HALL	Front end loader Excavator	1	121,360	121,360	24.9
ROSE HALL	Fertilizer applicator Implement	2	58,252	116,504	23.9
ROSE HALL	LGPL spreader Implement	2	58,252	116,504	23.9
ROSE HALL	Planting trailer Implement	2	12,135	24,270	5.0
ROSE HALL	Furrow opener Implement	2	7,282	14,564	3.0
ROSE HALL	Furrow coverer Implement	2	14,563	29,126	6.0
ROSE HALL	Tyre repair machine Tools	1	48,550	48,550	10.0
ROSE HALL	Trench cleaner Tractor	1	72,815	72,815	14.9
ROSE HALL	Backhoe Excavator	1	38,835	38,835	8.0
ROSE HALL	FWS Service unit Tools	1	72,816	72,816	14.9
ROSE HALL	Portable welding plant - Electrical Tools	4	19,420	77,680	15.9
ROSE HALL	Portable welding plant - Portable Tools	2	24,270	48,540	10.0
ROSE HALL	Lathe Tools	1	24,272	24,272	5.0
ROSE HALL	Boom Sprayer Implement	1	9,709	9,709	2.0
Blairmont	Harvesters and associated equipment	1	780,488	780,488	160.0
Blairmont	Tractors LGRP Spreader	4	80,085	320,341	65.7
Blairmont	LGRP SPREADER Implement	1	24,390	24,390	5.0
Blairmont	Boom Sprayer Implement	1	9,756	9,756	2.0
Blairmont	Fertilizer Hopper Implement	1	4,878	4,878	1.0
Blairmont	Land Development (840 Ha) Conversion	1056.74	1,500	1,585,110	324.9
Blairmont	110 Hp Tractor	3	58,537	175,610	36.0
East Demerara	Crop Care - 100 hp Tractor -Repair work	9	80,038	720,341	147.7
East Demerara	Crop Care - 100 hp + boom sprayer Implement	4	82,927	331,707	68.0
East Demerara	Crop Care - 100 hp + dondi Implement	6	87,805	526,829	108.0
East Demerara	100 hp +fertilizer hopper implement	4	82,927	331,707	68.0
East Demerara	Retooling of FWS Tools	1	73,171	73,171	15.0
East Demerara	Harvesters and associated equipment	3	750,000	2,250,000	461.3
Wales	110 Hp Tractor	5	69,922	349,610	71.7
Uitvlugt	Implements - Tillage	15	15,000	225,000	46.1
Uitvlugt	Excavators -	4	176,850	707,399	145.0
Uitvlugt	Tractors - LGRP	3	70,000	210,000	43.1
Uitvlugt	Spreaders - LGRP Implement	3	10,000	30,000	6.2
Uitvlugt	Tractors - Fertilising	2	70,000	140,000	28.7
Uitvlugt	Hoppers/Spreaders - Fertilising Implement	2	12,000	24,000	4.9
Uitvlugt	Tractors - Spraying	2	70,000	140,000	28.7
Uitvlugt	Boom Sprayers - Spraying Implement	2	7,000	14,000	2.9
Uitvlugt	Tractors - Inter Row Cultivation	2	70,000	140,000	28.7
Uitvlugt	Implements - Inter Row Cultivation	2	5,000	10,000	2.1
Uitvlugt	Harvesters with associated equipment	3	750,000	2,250,000	461.3
Uitvlugt	Laser Leveling Implement	1	35,000	35,000	7.2
Uitvlugt	Extension and Upgrade of Workshop		1,000,000	1,000,000	205.0
TOTAL				28133579	5767.4

MECHANIZATION INVESTMENTS BY MACHINE TYPE

BILLET HARVESTERS & ASSOCIATED EQUIPMENT						
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M	
HARVESTER & ASSOCIATED EQUIPMENT	Skeldon	Harvesters and associated equipment	3	750,000	2,250,000	461.3
	ALBION	Harvesters and associated equipment	1	780,488	780,488	160.0
	Blairmont	Harvesters and associated equipment	1	780,488	780,488	160.0
	East Demerara	Harvesters and associated equipment	3	750,000	2,250,000	461.3
	Uitvlugt	Harvesters with associated equipment	3	750,000	2,250,000	461.3
	TOTAL		11		8,310,976	1703.8

EXCAVATOR						
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M	
EXCAVATOR	Skeldon	Excavators	5	176,850	884,248	181.3
	ALBION	Super long reach excavator	5	176,850	884,248	181.3
	ROSE HALL	Excavator LR	5	176,850	884,248	181.3
	ROSE HALL	Backhoe Excavator	1	38,835	38,835	8.0
	ROSE HALL	Front end loader Excavator	1	121,360	121,360	24.9
	Uitvlugt	Excavators -	4	176,850	707,399	145.0
	TOTAL		21		3,520,339	721.7

TRACTORS						
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M	
TRACTORS	Skeldon	Tractors - Fertilising	7	82,143	575,000	117.9
	ALBION	Tractors LGRP Spreader	6	82,390	494,342	101.3
	ROSE HALL	100 HP tractor	5	48,544	242,720	49.8
	ROSE HALL	80/66 Tractor JD	2	38,835	77,670	15.9
	ROSE HALL	Trench cleaner Tractor	1	72,815	72,815	14.9
	Blairmont	Tractors LGRP Spreader	4	80,085	320,341	65.7
	Blairmont	110 Hp Tractor	3	58,537	175,610	36.0
	East Demerara	Crop Care - 100 hp Tractor with implements Repair work	9	80,038	720,341	147.7
	Wales	110 Hp Tractor	5	69,922	349,610	71.7
	Uitvlugt	Tractors - LGRP	3	70,000	210,000	43.1
	Uitvlugt	Tractors - Fertilising	2	70,000	140,000	28.7
	Uitvlugt	Tractors - Spraying	2	70,000	140,000	28.7
	Uitvlugt	Tractors - Inter Row Cultivation	2	70,000	140,000	28.7
	TOTAL		51		3,658,449	750.0

IMPLEMENTS						
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M	
IMPLEMENTS	Skeldon	Boom Sprayer Implement	3	7,000	21,000	4.3
	ALBION	Spring Tines Implement	2	9,709	19,418	4.0
	ALBION	Planting trailer Implement	2	12,135	24,270	5.0
	ALBION	Furrow coverer Implement	1	14,563	14,563	3.0
	ALBION	LGRP SPREADER Implement	1	24,390	24,390	5.0
	ROSE HALL	Spring Tines Implement	2	9,709	19,418	4.0
	ROSE HALL	Fertilizer applicator Implement	2	58,252	116,504	23.9
	ROSE HALL	LGPL spreader Implement	2	58,252	116,504	23.9
	ROSE HALL	Planting trailer Implement	2	12,135	24,270	5.0
	ROSE HALL	Furrow opener Implement	2	7,282	14,564	3.0
	ROSE HALL	Furrow coverer Implement	2	14,563	29,126	6.0
	ROSE HALL	Boom Sprayer Implement	1	9,709	9,709	2.0
	Blairmont	LGRP SPREADER Implement	1	24,390	24,390	5.0
	Blairmont	Boom Sprayer Implement	1	9,756	9,756	2.0
	Blairmont	Fertilizer Hopper Implement	1	4,878	4,878	1.0
	East Demerara	Crop Care - 100 hp + boom sprayer Implement	4	82,927	331,707	68.0
	East Demerara	Crop Care - 100 hp + dondi Implement	6	87,805	526,829	108.0
	East Demerara	100 hp +fertilizer hopper Implement	4	82,927	331,707	68.0
	Uitvlugt	Implements - Tillage	15	15,000	225,000	46.1
	Uitvlugt	Spreaders - LGRP implement	3	10,000	30,000	6.2
	Uitvlugt	Hoppers/Spreaders - Fertilising Implement	2	12,000	24,000	4.9
	Uitvlugt	Boom Sprayers - Spraying Implement	2	7,000	14,000	2.9
	Uitvlugt	Implements - Inter Row Cultivation	2	5,000	10,000	2.1
	Uitvlugt		1	35,000	35,000	7.2
	TOTAL		64		2,001,004	410.2

LAND CONVERSION						
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M	
LAND CONVERSION	Skeldon	Land Conversion	2000	1,500	3,000,000	615
	ALBION	Land Conversion	1000	1,500	1,500,000	307.5
	ROSE HALL	Land conversion Cultivation	2000	1,500	3,000,000	615.0
	Blairmont	Land Development (840 Ha) Conversion	1057	1,500	1,585,110	324.9
	TOTAL		6057		9,085,110	1862.4

TOOLS						
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M	
TOOLS	ALBION	Dump lorry- 10 Ton Tools	1	31,707	31,707	6.5
	ALBION	Trolley jack- 20 ton Tools	2	8,536	17,072	3.5
	ALBION	FWS Service unit Tools	1	72,816	72,816	14.9
	ALBION	Portable welding plant Tools	2	2,184	4,368	0.9
	ALBION	Lathe Tools	1	24,272	24,272	5.0
	ALBION	Distilling unit Tools	1	1,951	1,951	0.4
	ALBION	Heavy duty tool kit Tools	8	2,439	19,512	4.0
	ALBION	Floor crane Tools	1	19,512	19,512	4.0
	ALBION	Air compressor Tools	1	3,902	3,902	0.8
	ALBION	Lighting plant Tools	2	8,780	17,560	3.6
	ROSE HALL	Tyre repair machine Tools	1	48,550	48,550	10.0
	ROSE HALL	FWS Service unit Tools	1	72,816	72,816	14.9
	ROSE HALL	Portable welding plant - Electrical Tools	4	19,420	77,680	15.9
	ROSE HALL	Portable welding plant - Portable Tools	2	24,270	48,540	10.0
	ROSE HALL	Lathe Tools	1	24,272	24,272	5.0
	East Demerara	Retooling of FWS Tools	1	73,171	73,171	15.0
	TOTAL				557,701	114.3

FIELD WORKSHOP UPGRADE						
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M	
FIELD WORKSHOP UPGRADE	Uitvlugt	Extension and Upgrade of Workshop	1	1,000,000	1,000,000	205.0
	TOTAL			1,000,000	205.0	

ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M
GRAND TOTAL				28,133,579	5767.4

TILLAGE & PLANTING INVESTMENTS					
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M
Skeldon	Tillage tractors	6	70,000	420,000	86.1
Skeldon	Trailing Final Harrow	6	9,709	58,254	11.9
Skeldon	Plows	6	7,540	45,240	9.3
ALBION	160 HP Tractor	4	58,252	233,008	47.8
ALBION	Trailing Final Harrow	2	9,709	19,418	4.0
ALBION	Plows	4	7,540	30,160	6.2
ALBION	Tractor 100hp	1	38,835	38,835	8.0
ROSE HALL	180 HP Tractor	5	72,815	364,075	74.6
ROSE HALL	Mould Board Plow	5	9,709	48,545	10.0
ROSE HALL	Tandem Harrow	4	9,709	38,836	8.0
ROSE HALL	Low bed trailer	1	121,360	121,360	24.9
ROSE HALL	10/32 inverted harrow	4	29,125	116,500	23.9
Blairmont	Dundi Ditcher	4	5,000	20,000	4.1
Blairmont	160 HP Tractor	4	58,252	233,008	47.8
Blairmont	Trailing Final Harrow	2	9,709	19,418	4.0
Blairmont	Plows	4	7,540	30,160	6.2
East Demerara	Tillage - 100 hp Tractor with dondi	4	82,927	331,707	68.0
East Demerara	100 hp Tractor	2	68,293	136,585	28.0
East Demerara	Mould Board Plow	5	9,709	48,545	10.0
East Demerara	Tillage -150 hp tractor	11	82,927	912,195	187.0
Wales	Dundi Ditcher	4	5,000	20,000	4.1
Wales	160 HP Tractor	4	58,252	233,008	47.8
Wales	Trailing Final Harrow	2	9,709	19,418	4.0
Wales	Plows	4	7,540	30,160	6.2
Uitvlugt	Tractors - Planting	8	70,000	560,000	114.8
Uitvlugt	Bell Loaders - Planting	3	80,000	240,000	49.2
Uitvlugt	Trailers - Planting	8	5,000	40,000	8.2
Uitvlugt	Dondi Tractors - Planting	3	70,000	210,000	43.1
Uitvlugt	Dondi Ditchers - Planting	4	20,000	80,000	16.4
TOTAL				4,698,436	963.2

TILLAGE & PLANTING INVESTMENTS BY MACHINE TYPE

TRACTORS						
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M	
TRACTORS	Skeldon	Tillage tractors	6	70,000	420,000	86.1
	ALBION	160 HP Tractor	4	58,252	233,008	47.8
	ALBION	Tractor 100hp	1	38,835	38,835	8.0
	ROSE HALL	180 HP Tractor	5	72,815	364,075	74.6
	Blairmont	160 HP Tractor	4	58,252	233,008	47.8
	East Demerara	Tillage - 100 hp Tractor with dondi	4	82,927	331,707	68.0
	East Demerara	100 hp Tractor	2	68,293	136,585	28.0
	East Demerara	Tillage -150 hp tractor	11	82,927	912,195	187.0
	Wales	160 HP Tractor	4	58,252	233,008	47.8
	Uitvlugt	Tractors - Planting	8	70,000	560,000	114.8
	Uitvlugt	Dondi Tractors - Planting	3	70,000	210,000	43.1
	TOTAL		52		3,672,422	752.8

HARROW						
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M	
HARROW	Skeldon	Trailing Final Harrow	6	9,709	58,254	11.9
	ALBION	Trailing Final Harrow	2	9,709	19,418	4.0
	ROSE HALL	Tandem Harrow	4	9,709	38,836	8.0
	ROSE HALL	10/32 inverted harrow	4	29,125	116,500	23.9
	Blairmont	Trailing Final Harrow	2	9,709	19,418	4.0
	Wales	Trailing Final Harrow	2	9,709	19,418	4.0
	TOTAL		20		271,844	55.7

PLOWS						
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M	
PLOWS	Skeldon	Plows	6	7,540	45,240	9.3
	ALBION	Plows	4	7,540	30,160	6.2
	ROSE HALL	Mould Board Plow	5	9,709	48,545	10.0
	Blairmont	Plows	4	7,540	30,160	6.2
	East Demerara	Mould Board Plow	5	9,709	48,545	10.0
	Wales	Plows	4	7,540	30,160	6.2
	TOTAL		28		232,810	47.7

TRAILERS						
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M	
TRAILERS	ROSE HALL	Low bed trailer	1	121,360	121,360	24.9
	Uitvlugt	Trailers - Planting	8	5,000	40,000	8.2
	TOTAL		9		161,360	33.1

DITCHERS						
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M	
DITCHERS	Blairmont	Dundi Ditcher	4	5,000	20,000	4.1
	Wales	Dundi Ditcher	4	5,000	20,000	4.1
	Uitvlugt	Dondi Ditchers - Planting	4	20,000	80,000	16.4
	TOTAL		12		120,000	24.6

BELL LOADER						
ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M	
BELL LOADERS	Uitvlugt	Bell Loaders - Planting	3	80,000	240,000	49.2
	TOTAL		3		240,000	49.2

ESTATE	Description	Quantity	Unit Price US\$	Cost US\$	Cost G\$M
GRAND TOTAL				4,698,436	963.2

Guysuco Ledger
All Estates Compare Consol.
Year 2014

	Skeldon Actual	Albion Actual	Rose Hall Actual	Blairmont Actual	Enmore Actual	LBI Actual	Wales Actual	ICBU Actual	Industry Tot. Actual
Agriculture UNITS									
Hectares Harvested	8,117	8,900	6,724	5,656	5,112	3,374	2,895	4,451	45,228
Tonne Cane - Estate	472,502	567,411	386,578	380,390	269,138	156,148	127,230	176,809	2,536,206
Tonne Cane Per Hectare - Estate	58	64	57	67	53	46	44	40	56
Tonnes Sugar - Estate	28,840	50,467	29,168	33,499	19,272	11,076	9,456	13,362	195,140
Tonnes Sugar - Farmers	7,050	612	2,978	-	347	237	9,442	554	21,220
Tonne Sugar - Estates & Farmers	35,890	51,079	32,146	33,499	19,619	11,313	18,898	13,916	216,360
Tonnes Sugar Per Hectare	4	6	4	6	4	3	3	3	4
Hectares cultivation	8,903	9,616	6,689	5,808	4,693	2,988	3,356	4,500	46,553
Hectares Tilled	453	1,478	1,055	908	482	305	504	70	5,255
Hectares Planted	724	1,794	1,300	1,190	647	652	485	875	7,666

Total Cost (\$000) By Activity

Mech Tillage -	34,881	103,460	71,459	73,592	28,920	15,114	40,320	5,460	373,206
Preparatory Work	13,590	29,560	-	-	14,942	-	24,696	2,800	85,588
Field Works	172,350	201,111	113,797	83,173	95,454	62,139	121,344	141,582	990,950
Plant Cane	184,620	466,388	324,950	316,646	186,278	159,618	174,564	258,037	2,071,101
Ratoon Cane	519,469	584,989	430,323	441,191	419,184	286,790	312,649	356,048	3,350,644
Harvesting	1,308,656	1,729,241	1,309,172	1,205,405	897,209	569,436	408,559	617,602	8,045,280
Field Equipment	343,510	231,450	152,983	95,730	69,032	31,517	132,520	57,001	1,113,743
Water Management	85,989	247,284	173,088	75,082	161,006	135,343	41,175	58,374	977,341
Field Workshop	1,852,154	866,314	884,078	639,322	588,476	432,498	1,236,905	530,732	7,030,479
Field Management	4,515,219	4,459,797	3,459,850	2,930,142	2,460,501	1,692,455	2,492,732	2,027,636	24,038,331
Total									

UNIT COST \$000 By Activity

Mech Tillage - (Till ha)	77	70	68	81	60	50	80	78	71
Preparatory work (Till ha)	30	20	31	31	20	21	49	40	16
Field Works (Cultiv ha)	19	21	17	14	20	21	36	31	21
Plant Cane (Plant ha)	255	260	250	266	288	245	360	295	270
Ratoon Cane (Ha Harvest)	64	66	64	78	82	85	108	80	74
Harvesting (Tonnes cane)	2,77	3,05	3,39	3,17	3,33	3,65	3,21	3,49	3,17
Field Equipment (cultiv ha)	39	24	23	16	15	11	39	13	24
Water Management (cultiv ha)	10	26	26	13	34	45	12	13	21
Field Workshop									
Field Management (cultiv ha)	208	90	132	110	125	145	369	118	151
Agriculture cost per Unit									
Agriculture Cost-G\$ per tonne Sugar	125,807	87,311	107,629	87,470	125,414	149,608	131,908	145,705	111,104
Agriculture Cost-US \$ Per LB Sugar	30,39	21	26	21	30	36	32	35	27
Agriculture Cost-G\$ per Ha	507,185	463,775	517,283	504,492	524,281	566,417	742,747	450,586	516,369
Agriculture Cost-G\$ Per tonne cane	9,556	7,860	8,950	7,703	9,142	10,839	19,592	11,468	9,478

Guysuco
All Estates Compare Consol.
Projected 2017

	Skeldon Projected	Albion Projected	Rose Hall Projected	Blairmont Projected	Enmore Projected	LBI Projected	Wales Projected	ICBU Projected	Industry Tot. Projected
Agriculture UNITS									
Hectares Harvested	8,582	9,002	6,314	5,493	4,472	4,472	2,699	2,833	3,933
Tonne Cane - Estate	526,635	622,672	377,717	397,668	252,956	141,720	141,720	166,957	2,686,140
Tonne Cane Per Hectare - Estate	61	69	60	72	57	57	53	59	62
Tonnes Sugar - Estate	40,472	59,302	29,976	38,237	20,076	11,248	11,248	13,464	228,633
Tonnes Sugar - Farmers	9,632	684	3,243	-	513	249	249	10,740	29,632
Tonne Sugar - Estates & Farmers	50,104	59,986	33,219	38,237	20,589	11,497	11,497	24,204	258,265
Tonnes Sugar Per Hectare	5	7	5	7	4	4	4	5	5
Hectares cultivation	8,903	9,616	6,689	5,808	4,693	4,693	2,988	3,356	46,553
Hectares Tilled	1,780	1,630	1,020	870	704	704	500	620	7,924
Hectares Planted	1,780	1,630	1,005	870	704	704	500	620	7,909

Total Cost (\$000) By Activity

Mech Tillage -	124,600	110,840	71,400	65,250	42,240	42,240	24,777	49,600	551,107
Preparatory Work	53,400	16,300	-	-	21,824	21,824	10,000	30,380	163,904
Field Works	172,350	201,111	113,797	83,173	95,454	62,139	62,139	121,344	990,950
Plant Cane	409,400	423,800	251,250	231,420	168,960	120,000	120,000	223,200	2,064,030
Ratoon Cane	549,248	591,720	404,096	384,510	375,648	215,920	215,920	305,964	3,157,478
Harvesting	1,369,251	1,868,016	1,208,694	1,232,771	758,868	453,504	453,504	550,958	8,121,433
Field Equipment	343,510	231,450	152,983	95,730	69,032	69,032	31,517	132,520	1,113,743
Water Management	85,989	247,284	173,088	75,082	161,006	161,006	135,343	41,175	999,967
Field Workshop	1,852,154	866,314	884,078	639,322	588,476	588,476	289,836	1,236,905	7,167,085
Total	4,959,902	4,556,835	3,259,386	2,807,258	2,281,508	2,281,508	1,343,036	2,692,046	24,329,697

UNIT COST \$000 BY Activity

Mech Tillage - (Till ha)	70	68	70	75	60	60	50	80	78
Preparatory work (Till ha)	30	10	21	14	31	31	20	49	40
Field Works (Cultiv ha)	19	21	17	14	20	20	21	36	31
Plant Cane (Plant ha)	230	260	250	266	240	240	240	360	295
Ratoon Cane (Ha Harvest)	64	66	64	70	84	84	80	108	84
Harvesting (Tonnes cane)	2.60	3.00	3.20	3.10	3.00	3.00	3.20	3.30	3.40
Field Equipment (cultiv ha)	39	24	23	16	15	15	11	39	13
Water Management (cultiv ha)	10	26	26	13	34	34	45	12	18
Field Workshop									
Field Management (cultiv ha)	208	90	132	110	125	125	97	369	180

Agriculture cost per Unit

Agriculture Cost-G\$ per tonne Sugar	98,992	75,965	98,118	73,417	110,812	110,812	116,816	111,223	118,935
Agriculture Cost-US \$ Per LB Sugar	23.91	18	24	18	27	27	28	27	29
Agriculture Cost-G\$ per Ha	557,136	473,866	487,312	483,335	486,141	486,141	449,477	802,135	539,939
Agriculture Cost-G\$ Per tonne cane	9,418	7,318	8,629	7,059	9,019	9,019	9,477	16,124	12,160

GUYSUCO
All Estates Compare Consol.
Projected 2020

	Skeldon Projected	Albion Projected	Rose Hall Projected	Blairmont Projected	Enmore Projected	LBI Projected	Wales Projected	ICBU Projected	Industry Tot. Projected
Agriculture UNITS									
Hectares Harvested	8,582	9,002	6,314	5,493	4,472	2,699	2,915	3,984	43,461
Tonne Cane - Estate	626,008	679,488	427,245	419,895	307,102	178,720	201,050	233,953	3,073,461
Tonne Cane Per Hectare - Estate	73	75	68	76	69	66	69	59	71
Tonnes Sugar - Estate	49,683	65,970	37,055	40,375	24,766	14,184	16,214	18,867	267,114
Tonnes Sugar - Farmers	12,062	926	3,134	-	416	249	13,020	5,806	35,613
Tonne Sugar - Estates & Farmers	61,745	66,896	40,189	40,375	25,182	14,433	29,234	24,673	302,727
Tonnes Sugar Per Hectare	6	7	6	7	6	5	6	5	6
Hectares cultivation	8,903	9,616	6,689	5,808	4,693	2,988	3,356	4,500	46,553
Hectares Tilled	1,780	1,925	1,355	1,162	940	600	672	900	9,334
Hectares Planted	1,780	1,925	1,355	1,162	940	600	672	900	9,334

Total Cost (\$000) By Activity

Mech Tillage - Preparatory Work	106,800	130,900	92,140	81,340	47,000	29,732	53,760	70,200	611,872
Field Works	53,400	19,250	-	-	29,140	12,000	32,256	36,000	182,046
Plant Cane	172,350	201,111	113,797	83,173	95,454	62,139	121,344	141,582	990,950
Ratoon Cane	400,500	500,500	338,750	309,092	216,200	144,000	241,920	265,500	2,416,462
Harvesting	1,565,020	549,248	404,096	384,510	380,120	229,415	314,820	318,720	3,172,649
Field Equipment	343,510	2,038,464	1,367,184	1,259,685	859,886	571,904	643,360	795,440	9,100,943
Water Management	85,989	231,450	152,983	95,730	69,032	31,517	132,520	81,000	1,137,742
Field Workshop		247,284	173,088	75,082	161,006	135,343	41,175	81,000	999,967
Field Management	1,852,154	866,314	884,078	639,322	588,476	289,836	1,236,905	810,000	7,167,085
Total	5,128,971	4,826,993	3,526,116	2,927,934	2,446,314	1,505,886	2,818,060	2,599,442	25,779,716

UNIT COST \$000 By Activity

Mech Tillage - (Till ha)	60	68	68	70	50	50	80	78	66
Preparatory work (Till ha)	30	10			31	20	48	40	20
Field Works (Cultiv ha)	19	21	17	14	20	21	36	31	21
Plant Cane (Plant ha)	225	260	250	266	230	240	360	295	259
Ratoon Cane (Ha Harvest)	64	66	64	70	85	85	108	80	73
Harvesting (Tonnes cane)	2.50	3.00	3.20	3.00	2.80	3.20	3.20	3.40	2.96
Field Equipment (cultiv ha)	39	24	23	16	15	11	39	18	24
Water Management (cultiv ha)	10	26	26	13	34	45	12	18	21
Field Workshop	208	90	132	110	125	97	369	180	154

Agriculture cost per Unit

Agriculture Cost-G\$ per tonne Sugar	83,067	72,157	87,738	72,518	97,145	104,336	96,397	105,356	85,158
Agriculture Cost-US \$ Per LB Sugar	20.06	17	21	18	23	25	23	25	21
Agriculture Cost-G\$ per Ha	576,127	501,959	527,191	504,112	521,258	503,978	839,683	577,654	553,776
Agriculture Cost-G\$ Per tonne cane	8,193	7,104	8,253	6,973	7,966	8,426	14,017	11,111	8,388

Appendix 3

Cane Farming Records

Guyana Sugar Corporation Inc
Agriculture Services - Cane Farming

Cane Farmers' Register as at 1/1/2015

Estate	Individuals and Organised Cane Farming Groups	No of Farmers	Cultiv	Hect in Cane	Farm Status
Skeldon	SWR Cane Farmers Co-op Marketing Society Ltd (SWR1)	24	76.7	-	Abdn. Last harvest 2nd Crop 2014
	Upper Corentyne Agric Producers Co-op Society (SWR 2)	66	79.3	70.8	
	Stockholm Farm (SWR 3)	2	25.0	-	Abdn. Last harvest 2nd Crop 2005
	Bajjnauth and Sons Limited (SWR 4)	4	43.5	21.4	
	R. Prasad Cane Farming Inc.	1	425.1	369.9	
	Corentyne Cane Farming Inc. (Corcane)	2	500.1	409.9	
	H. N. Sugrim	1	182.2	182.2	
	Moleson Creek Cane Farmers Inc (Mo-cane)	2	29.0	-	Abdn 29.0 ha. Last harvest 2nd Crop 2007
	Rahim and Son Farm House Cane Inc.	2	87.7	81.2	
	Crabwood Creek Cane Farmers Company Inc.	14	237.0	219.5	
	SWR Agri Co-op Land Society Ltd (H/ Scheme)	85	550.1	528.0	
	Leeds Pioneer Co-operative Land Society Limited	96	259.6	223.0	
	Johannesburgh Cane Farming Inc	129	15.0	-	Abdn 15 ha. Last harvest 2nd Crop 2009
	Anacane	6	156.6	156.6	
	Corentyne Gold Inc(Anand Singh)	2	98.5	97.2	
	Raja's Cane Farming Inc	1	103.2	21.4	
	S and R Abdulla Cane Farming Inc	2	97.7	-	Absconded
	Skeldon Total	439	2,966.3	2,381.1	
Albion	L/Kenny Cane Farmers Co-op Marketing Society Ltd.	187	182.7	-	Abdn. Last harvest 2nd Crop 2010
	Bloomfield Cane Farmers Co-op Marketing Society Ltd.	202	183.8	-	Abdn. Last harvest 1st Crop 2012
	PMU Cane Farmers Co-operative Marketing Society Ltd.	95	334.7	119.4	Unable to replant & becoming abandon
	Sue-Young	1	134.7	-	Abdn. Last harvest 1st Crop 2009
	Albion Total	485	835.9	119.4	
Rose Hall	Lochaber Corporation	1	372.5	372.5	
	R Hanoman	1	231.0	231.0	Old ratoons. Undecided about replanting
	Good Samaritan Co-operative Land Society Ltd.	57	375.8	-	Abdn. Last harvest in 2013
	Nowrang Persaud	1	21.7	21.7	Old ratoons yielding poorly
	Isabella Collins	1	21.5	21.5	
	Rose Hall Total	61	1,022.5	646.7	
Enmore	Friendship farmers	13	76.5	32.0	
	Buxton farmers	41	105.5	78.3	
		Enmore Total	54	182.0	110.3
LBI	GARU	1	68.8	44.4	
	BV/Triumph	36	32.9	3.2	Farmers lack interest
	Plaisance	45	150.1	17.5	Farmers lack interest
	Diamond	28	344.5	-	Navig maint preventing c/transport
	Mocha/Archadia Cane Farmers Co-operative Society	12	34.4	-	Abdn. Last harvest in 2006
	Plantation Houston Sugar Estate Company Ltd.	1	685.1	-	Abdn. Last harvest 1st Crop 2011
	LBI Total	123	1,315.8	65.1	
Wales	La Grange Cane Farmers Co-op Marketing Society Ltd.	120	207.3	51.7	
	Canal #1 Front Cane Farming Group	13	100.6	26.1	
	Canal #1 Back Cane Farming Group	62	388.4	30.1	
	La Retraite/Stanleytown Cane Farmers Co-op Society	154	808.9	1,339.3	
	Canal #2 Cane Farmers Marketing Co-op Society Ltd.	191	470.2	346.5	
	Belle Vue Cane Farmers Marketing Co-op Society Ltd.	55	265.2	198.0	
	S/ Progressive Cane Farmers Marketing Co-op Society Ltd.	28	23.8	58.1	
	GI Sisters Cane Farmers Marketing Co-op Society Ltd.	92	101.3	22.4	
	Free & Easy Cane Farmers Marketing Co-op Society Ltd.	25	71.0	27.1	
	ML/Vbg/Shtille CF Marketing Co-op Society Ltd.	22	25.3	3.1	
	Growth & Consumer Cane Farmers Co-op Society Ltd	12	212.4	24.9	
		Wales Total	774	2,674.4	2,127.3
ICBU	Paul Cheong	1	288.7	99.3	
	Pradeep Chandar	1	219.0	106.5	
	Ganesh Ramrattan	1	98.8	-	
	Premraj Ramraj	1	208.0	83.8	
	T & H Deonarine	2	173.0	84.7	
	N F Agriculture Inc.	1	449.1	-	
	B. Ramdass	3	59.4	-	
		ICBU Total	10	1,496.0	374.3
	Grand Total	1,946	10,492.9	5,824.2	

Applications for lands at Uitvlugt - September 2015

NAME	ADDRESS	HECTARES
DEODAT SINGH	23 Adelphi New Road East Canje Berbice	800
DENISE PAMELA GLEN	952 Sec C Block Y Golden Grove EBD	100
HEMCHAND LALL RAM	Lot X 26 Anna Catherina Forth Street WCD	40
PARASRAM MAHADEO	53 Versailles H/S WBD	500
NIVALDO BONFIM	NF Agriculture Inc. 106 Lamaha Street Georgetown	500
TRIBUWAN LOOKNAUTH	109 Zeeburg WCD	50
MAHADEO UMRAOW	Eagle Transportation & General Construction Inc. 110 Regent Road Bourda G/town	150
	SUB TOTAL	2140
NAME	ADDRESS	HECTARES
JAVID ALI	Area 'M' Pln. Tuschen EBD	445
SHIRAZ ALI	Two Brothers Corp. 17 Vergenoegen EB Essequibo	283
AKBAR KHAN	30 Coglan Dam WBD	81
THAKUR SATROHAN	O Mes Delices Canal Number One WBD	81
NARAINDAT CYRIL	Lot 12 Lesperance Canal No. 1 WBD	40
SHIRAZ ALI	Two Brothers Corp. 17 Vergenoegen EB Essequibo	660
RAJENDRA PERSAUD	2 West Half Java, Canal # 1 WBD	405
SHAZAM RAMZAN ALLI/NEAZABAM ALLY	Lot 5 Monbijou Canal No. 1 WBD	61
RAGOBIR GURDYAL	341 Tuschen North EB Essequibo	20
SEODAT PURAN	S.P Worldwide Import & Export 109 Goedverwagting ECD	121
JAIPAUL SUKHAL	216 Temple Street Windsor Forest WCD	40
DEVENDRA BALDEO	B & M Trading Enterprise 149 A Regent Road Bourda	40
NAZIM HUSSAIN/SEDIK HUSSAIN	Lot 1 & 2 Endeavour Canal # 2 Polder WBD	202
NANRAJ BISSESSAR	13 Soesdyke Canal # 1 WBD	202
RAJENDRADEO GEORGE	Lot 1 Rotter Dam WCD	121
	SUB TOTAL	2806
	TOTAL	4946
S. MARAJ	S. Maraj Contracting Services 25 Success Leguan Essequibo	Not stated
SHAIRAZ ALI	Two Brothers Corp. Rice Millers, Gas Station Mining 16/17 Vergenoegen, EB Essequibo	Not stated
JOHN BRIDGLALL	Soil Water Company 15 Back Street Junior Staff Compound Diamond EBD	minimum one section of the land

TOTAL AMOUNT PAID TO SKELDON FARMERS FOR 2014

	SWP1			SWP2			SWP4			R Prashed			Corcane			H N Sugrim			AnaCane			Kahim & Son			Raja			CMC Company			Car Gold			Hunter Scheme			Leeds/Pioneer			Johnsburg			Sub Total
	GSM	GSM	%	GSM	GSM	%	GSM	GSM	%	GSM	GSM	%	GSM	GSM	%	GSM	GSM	%	GSM	GSM	%	GSM	GSM	%	GSM	GSM	%	GSM	GSM	%	GSM	GSM	%	GSM	GSM	%							
A. Hectares Harvested	42.1	69.9		43.5	406.6		339.3	182.2	141.7		82.3	79.4		229.2	58.0		437.8	263.8		0	2,376																						
B. Tonnes Cane Supplied	1,122	4,120	2,285	18,216	17,107		11,847	9,655	4,575		3,339	3,339		17,036	2,868		18,797	11,976		0	122,943																						
C. Tonnes Sugar Produced	36	192	156	1,019	1,007		705	705	621		277	201		675	98		1,318	688		0	6,993																						
D. Tonnes Cane per Hectare B/A	26.60	58.94	52.53	44.80	50.40		65.02	68.10	55.50		34.0	42.05		74.30	49.45		42.90	45.40		0	5.2																						
E. Tonnes Sugar per Hectare C/A	0.86	2.75	3.61	2.50	3.87		4.40	3.87	4.40		3.40	2.49		4.50	1.69		3.00	2.60		0	3																						
F. Tonnes Cane per Tonne Sugar A/B	31.17	21.46	14.55	17.80	17.00		16.80	15.50	16.50		16.50	16.86		16.40	29.27		14.10	17.30		0	18																						
G. Farmers are being paid on 86 puni sugar	36.95	195.89	159.78	1045.50	1027.76		723.77	638.90	282.44		201.55	201.55		698.85	99.51		1351.03	705.84		0	7,168																						
PUNTS USED	269	625	457	2,844	2,684		1,455	1,650	640		581	581		1,785	498		2,706	1,690		0	17,884																						
Tonnes Cane per Punt	4.17	6.59	5.00	6.41	6.37		7.18	6.64	7.15		5.75	5.75		9.54	5.76		6.95	7.09		0.00	6.87																						
G. Sugar Value per Tonne (\$74,642)	\$74,642	\$74,642	\$74,642	\$74,642	\$74,642		\$74,642	\$74,642	\$74,642		\$74,642	\$74,642		\$74,642	\$74,642		\$74,642	\$74,642		\$74,642	\$74,642																						
H. Total Gross Owed to Farmers for Cane Supplied	2.8	14.6	11.9	78.0	76.7		54.0	47.7	21.1		15.0	15.0		52.2	7.5		100.8	52.7		0.0	\$535																						
I. Less Expenses Deducted	838,506	4,400,986	2,342,624	25,730,042	23,103,565		16,261,034	14,422,237	6,360,940		4,623,211	4,623,211		15,769,039	2,244,786		30,362,404	8,858,288		0	\$155,317,662																						
J. Net Paid to the Farmers H-I	1,915,733	10,220,229	9,583,722	52,108,140	53,610,098		37,762,334	33,266,354	14,720,823		10,420,823	10,420,823		36,394,702	5,212,977		70,480,947	33,827,050		-	\$369,727,932																						
K. % of net income deducted for expenses	30%	30%	20%	33%	30%		30%	30%	30%		31%	31%		30%	30%		30%	17%		29%																							

Independent Auditors' Report to the Chairman of the National Cane Farming Committee

NATIONAL CANE FARMING COMMITTEE Cap. 6904 Cane Farmers Contract (General Conditions) Rules Farmer's Basic Share after Adjustment for Transport Differential	SKELDON ESTATE										
	2005	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015
Basic Average Price	\$89,315	\$102,104	\$105,667	\$110,580	\$107,440	\$92,825	\$109,800	\$128,074	\$136,472	\$91,297	
Less Transport Differential	\$1,363	\$1,489	\$1,500	\$1,085	\$1,692	\$2,904	\$2,412	\$2,231	\$1,890	\$1,917	
Net Average Sugar Price	\$87,952	\$100,615	\$104,166	\$109,495	\$105,748	\$89,921	\$107,389	\$125,842	\$134,581	\$89,380	
Plus Molasses	\$8,894	\$8,577	\$7,919	\$9,960	\$15,691	\$22,225	\$28,456	\$19,100	\$24,164	\$17,251	
Final Proceeds Sugar and Molasses	\$96,846	\$109,193	\$112,085	\$119,455	\$121,439	\$112,146	\$135,845	\$144,942	\$158,746	\$106,631	
Farmers Share 70%	\$67,792	\$76,435	\$78,460	\$83,618	\$85,007	\$78,502	\$95,091	\$101,459	\$111,122	\$74,642	\$62,000

Appendix 4
Agriculture Policy Matters

Carried Over canes

Brought Forward Canes

Year	Estate	Brought Forward Canes										Carried Over canes																									
		First Crop					Second Crop					Year					First Crop					Second Crop					Year										
		ha	tc	ts	tch	tcts	ha	tc	ts	tch	tcts	ha	tc	ts	tch	tcts	ha	tc	ts	tch	tcts	ha	tc	ts	tch	tcts	ha	tc	ts	tch	tcts						
2013	SWR	162.1	8223	425	507	19.3	162.1	8223	425	507	19.3	112.7	3479	213	30.9	16.3	112.7	3479	213	30.9	16.3	112.7	3479	213	30.9	16.3	0	0	0	0	0	0	0	0	0	0	
	AN	174.4	8904	661	51.1	13.5	174.4	8904	661	51.1	13.5	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
	RH	44.4	1418	97	31.9	14.6	44.4	1418	97	31.9	14.6	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
	BCF	260	12792.5	986	49.2	13.0	260	12792.5	986	49.2	13.0	257.3	16081.7	1303.5	51.7	13.5	257.3	16081.7	1303.5	51.7	13.5	257.3	16081.7	1303.5	51.7	13.5	0	0	0	0	0	0	0	0	0	0	
	EHP	0	0	0	0.0	0.0	0	0	0	0.0	0.0	41.9	2356	175	56.2	13.5	41.9	2356	175	56.2	13.5	41.9	2356	175	56.2	13.5	0	0	0	0	0	0	0	0	0	0	
	LBI	0	0	0	0.0	0.0	0	0	0	0.0	0.0	20.4	1654.14	119.13	81.1	13.9	20.4	1654.14	119.13	81.1	13.9	20.4	1654.14	119.13	81.1	13.9	0	0	0	0	0	0	0	0	0	0	
	GV	0	0	0	0.0	0.0	0	0	0	0.0	0.0	475.1	15501.2	1098.3	32.6	14.1	475.1	15501.2	1098.3	32.6	14.1	475.1	15501.2	1098.3	32.6	14.1	0	0	0	0	0	0	0	0	0	0	
	ICBU	306.7	10341	698	33.7	14.8	306.7	10341	698	33.7	14.8	285.7	13095	931	45.8	14.1	285.7	13095	931	45.8	14.1	285.7	13095	931	45.8	14.1	0	0	0	0	0	0	0	0	0	0	
	Net		387.4	14678.5	3887	44.4	14.8	387.4	14678.5	3887	44.4	14.8	592.4	23436	1629	39.6	14.4	592.4	23436	1629	39.6	14.4	592.4	23436	1629	39.6	14.4	0	0	0	0	0	0	0	0	0	0
	2014	SWR	38.7	2604	107	67.3	24.3	38.7	2604	107	67.3	24.3	48.2	2479	146	51.4	17.0	48.2	2479	146	51.4	17.0	48.2	2479	146	51.4	17.0	0	0	0	0	0	0	0	0	0	0
AN		546.7	29578	2400.4	54.1	12.3	546.7	29578	2400.4	54.1	12.3	265.3	18353	1482	69.2	12.4	265.3	18353	1482	69.2	12.4	265.3	18353	1482	69.2	12.4	0	0	0	0	0	0	0	0	0	0	
RH		446.2	20887	1493	46.8	14.0	446.2	20887	1493	46.8	14.0	459.2	31290	2080	68.1	15.0	459.2	31290	2080	68.1	15.0	459.2	31290	2080	68.1	15.0	0	0	0	0	0	0	0	0	0	0	
BCF		397.1	24519	2099	61.7	11.7	397.1	24519	2099	61.7	11.7	186.3	12934.3	1037.9	69.4	12.5	186.3	12934.3	1037.9	69.4	12.5	186.3	12934.3	1037.9	69.4	12.5	0	0	0	0	0	0	0	0	0	0	
EHP		30.8	1307	107	42.4	12.2	30.8	1307	107	42.4	12.2	101.2.5	51157	3371	50.5	15.2	101.2.5	51157	3371	50.5	15.2	101.2.5	51157	3371	50.5	15.2	0	0	0	0	0	0	0	0	0	0	
LBI		0	0	0	0.0	0.0	0	0	0	0.0	0.0	781.2	37205	2402.15	47.6	15.5	781.2	37205	2402.15	47.6	15.5	781.2	37205	2402.15	47.6	15.5	0	0	0	0	0	0	0	0	0	0	
GV		259.3	7453.08	508.08	28.7	14.7	259.3	7453.08	508.08	28.7	14.7	283.4	11762.7	650.4	45.3	13.7	283.4	11762.7	650.4	45.3	13.7	283.4	11762.7	650.4	45.3	13.7	0	0	0	0	0	0	0	0	0	0	
ICBU		313.1	12594	949	40.2	13.3	313.1	12594	949	40.2	13.3	201.2	9105	666	53.8	14.7	201.2	9105	666	53.8	14.7	201.2	9105	666	53.8	14.7	0	0	0	0	0	0	0	0	0	0	
Net			3385	36944.1	2883.4	48.7	13.8	3385	36944.1	2883.4	48.7	13.8	6297.3	31836	1853	53.8	14.7	6297.3	31836	1853	53.8	14.7	6297.3	31836	1853	53.8	14.7	0	0	0	0	0	0	0	0	0	0
2015		SWR	0	0	0	0.0	0.0	0	0	0	0.0	0.0	0	0	0	0.0	0.0	0	0	0	0.0	0.0	0	0	0	0.0	0.0	0	0	0	0.0	0.0	0	0	0	0.0	0.0
	AN	118.5	7246	549.06	61.1	13.2	118.5	7246	549.06	61.1	13.2	38	2373	219	0.0	0.0	38	2373	219	0.0	0.0	38	2373	219	0.0	0.0	0	0	0	0.0	0.0	0	0	0	0.0	0.0	
	RH	401.3	20871	1348	52.0	15.5	401.3	20871	1348	52.0	15.5	0	0	0	0.0	0.0	0	0	0	0.0	0.0	0	0	0	0.0	0.0	0	0	0	0.0	0.0	0	0	0	0.0	0.0	
	BCF	296.8	18665	1419.2	62.9	13.2	296.8	18665	1419.2	62.9	13.2	0	0	0	0.0	0.0	0	0	0	0.0	0.0	0	0	0	0.0	0.0	0	0	0	0.0	0.0	0	0	0	0.0	0.0	
	EHP	163.7	7891	593	48.2	13.3	163.7	7891	593	48.2	13.3	0	0	0	0.0	0.0	0	0	0	0.0	0.0	0	0	0	0.0	0.0	0	0	0	0.0	0.0	0	0	0	0.0	0.0	
	LBI	87.8	4344.26	315.72	49.5	13.8	87.8	4344.26	315.72	49.5	13.8	0	0	0	0.0	0.0	0	0	0	0.0	0.0	0	0	0	0.0	0.0	0	0	0	0.0	0.0	0	0	0	0.0	0.0	
	GV	479.6	23755	1820	49.5	13.1	479.6	23755	1820	49.5	13.1	0	0	0	0.0	0.0	0	0	0	0.0	0.0	0	0	0	0.0	0.0	0	0	0	0.0	0.0	0	0	0	0.0	0.0	
	ICBU	265.5	10952	747	41.3	14.7	265.5	10952	747	41.3	14.7	0	0	0	0.0	0.0	0	0	0	0.0	0.0	0	0	0	0.0	0.0	0	0	0	0.0	0.0	0	0	0	0.0	0.0	
	Net		1833	83745.3	8792	51.7	13.1	1833	83745.3	8792	51.7	13.1	65.7	11860	754	61.9	15.1	65.7	11860	754	61.9	15.1	65.7	11860	754	61.9	15.1	0	0	0	0.0	0.0	0	0	0	0.0	0.0

Approved Fertiliser application for the industry from 2011- 2016

Type Canes Fertilized	Fertiliser	Rate of Application per hectare					
		2011	2012	2013	2014	2015	2016
Plant canes							
Flood Fallow	Sulphate of Ammonium	176	176	176	176	176	176
	Di-ammonium phosphate	59	59	59	59	59	59
	Muriate of Potash	118	118	118	118	118	118
Plough and Plant (LGRP Applied)	Sulphate of Ammonium	235	235	235	235	235	235
	Urea	59	59	59	59	59	59
	Di-ammonium phosphate	59	59	59	59	59	59
	Muriate of Potash	88	88	88	88	88	88
Plough and Plant (No LGRP Applied)	Sulphate of Ammonium	176	176	176	176	176	176
	Urea	59	59	59	59	59	59
	Di-ammonium phosphate	118	118	118	118	118	118
	Muriate of Potash	88	88	88	88	88	88
Ratoon Canes							
1R+	Sulphate of Ammonium	235	235	235	235	235	235
	Urea	118	118	118	118	118	118
	Muriate of Potash	***	***	***	***	***	***

***NB. Muriate of Potash will be applied to all Plant and Ratoon crops with the exception of the following soils:

- 1.1 Whittaker # 37.
- 1.2 Tain # 9.

- i. These soils, however, should receive 88 Kg Muriate of Potash on every even number ratoon crop
- ii. Corentyne Series #11 & #12 Soils and Skeldon Series #13 soils of the new Skeldon development should be amended similarly to the Whittaker and Tain Series soils

N.B.

In 2012 there was an adjustment downwards for the SOA and MOP

Type Canes Fertilized	Fertiliser	2012	Adjusted 2012 rates	% of Orginal rate
Flood Fallow	Sulphate of Ammonium	176	126	-28
	Urea	0	25	
	Di-ammonium phosphate	59	59	0
	Muriate of Potash	118	0	-100
Plough and Plant (LGRP Applied)	Sulphate of Ammonium	235	101	-57
	Urea	59	82	39
	Di-ammonium phosphate	59	59	0
	Muriate of Potash	88	0	-100
Plough and Plant (No LGRP Applied)	Sulphate of Ammonium	176	95	-46
	Urea	59	62	5
	Di-ammonium phosphate	118	118	0
	Muriate of Potash	88	0	-100
1R+	Sulphate of Ammonium	235	101	-57
	Urea	118	126	7
	Muriate of Potash	***	0	-100


CROP DURATION FOR THE PERIOD 2002 TO 2015

Estates		2002	2003	2004	2005	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015	
BERBICE	Skeldon	15	13	16	18	14	17	19	14	11	16	9	6	15	10	
		16	19	23	21	22	23	12	16	20	19	19	17	21		
	Albion	14	12	16	13	13	16	21	13	11	22	13	8	11	13	
		15	19	23	20	22	23	19	20	22	21	25	25	21		
	Rose Hall	14	12	14	14	12	16	18	12	8	18	13	8	11	11	
		15	19	23	20	21	23	18	21	22	24	24	25	24		
	Blairmont	14	13	16	17	14	13	20	12	10	19	18	18	9	11	13
		16	18	22	22	19	24	16	20	22	20	20	23	22	21	
	Enmore	14	12	13	8	6	12	12	12	9	22	22	12	13	15	13
		13	17	19	18	20	20	18	18	18	21	22	21	21	22	
DEMERARA	L.B.I	14	12	14	8	8	12	12	11	11	18	10	13	15	11	
		13	18	19	19	23	22	18	17	22	22	18	19	18		
	Wales	17	11	14	8	7	10	11	12	9	19	11	13	13	12	
		12	18	18	16	17	16	18	18	20	18	14	14	20	17	
	Uitvlugt	16	13	16	9	10	10	11	10	7	20	13	13	12	15	
		13	18	21	19	21	17	15	19	19	20	20	21	23	15	

Appendix 5

Historical Rainfall and Climate


SKELDON ESTATE Monthly Precipitation Totals (mm) 1995 - 2014



Summary of wet months SKELDON ESTATE 1995 -2014

Month	% Incidence > 100 mm	% Incidence > 150 mm	% incidence > 200 mm
January	45%	25%	15%
February	50%	30%	15%
March	20%	10%	5%
April	60%	25%	10%
May	95%	85%	65%
June	95%	80%	45%
July	95%	70%	35%
August	55%	30%	5%
September	5%	5%	0%
October	20%	5%	0%
November	30%	0%	0%
December	65%	45%	25%


ALBION ESTATE Monthly Precipitation Totals (mm) 1995 - 2014



Summary of wet months ALBION ESTATE 1995 -2014

Month	% Incidence > 100 mm	% Incidence > 150 mm	% incidence > 200 mm
January	70%	60%	40%
February	45%	35%	25%
March	25%	10%	5%
April	60%	55%	45%
May	90%	75%	65%
June	90%	85%	65%
July	95%	80%	70%
August	70%	55%	30%
September	15%	5%	5%
October	20%	5%	5%
November	30%	15%	5%
December	75%	50%	35%


ROSEHALL ESTATE Monthly Precipitation Totals (mm) 1995 - 2014



Summary of wet months ROSEHALL ESTATE 1995 -2014

Month	% Incidence > 100 mm	% Incidence > 150 mm	% incidence > 200 mm
January	75%	55%	40%
February	45%	35%	30%
March	15%	5%	5%
April	60%	55%	30%
May	90%	90%	75%
June	95%	80%	65%
July	90%	75%	50%
August	65%	50%	30%
September	25%	15%	10%
October	15%	5%	0%
November	35%	10%	5%
December	80%	55%	35%


BLAIRMONT ESTATE Monthly Precipitation Totals (mm) 1995 - 2014



Summary of wet months BLARIMONT ESTATE 1995 -2014

Month	% Incidence > 100 mm	% Incidence > 150 mm	% incidence > 200 mm
January	65%	50%	30%
February	40%	30%	25%
March	30%	15%	5%
April	60%	50%	20%
May	90%	90%	60%
June	100%	95%	65%
July	95%	80%	45%
August	80%	60%	10%
September	15%	10%	0%
October	5%	0%	0%
November	25%	5%	0%
December	70%	55%	30%


ENMORE ESTATE Monthly Precipitation Totals (mm) 1995 - 2014



Summary of wet months ENMORE ESTATE 1995 -2014

Month	% Incidence > 100 mm	% Incidence > 150 mm	% incidence > 200 mm
January	65%	55%	50%
February	40%	30%	20%
March	25%	10%	10%
April	70%	45%	20%
May	85%	80%	75%
June	95%	95%	70%
July	90%	80%	60%
August	80%	65%	20%
September	10%	5%	5%
October	10%	5%	5%
November	60%	40%	25%
December	70%	65%	50%


L.B.I. ESTATE Monthly Precipitation Totals (mm) 1995 - 2014



Summary of wet months L.B.I. ESTATE 1995 -2014

Month	% Incidence > 100 mm	% Incidence > 150 mm	% incidence > 200 mm
January	70%	65%	55%
February	35%	25%	15%
March	20%	10%	10%
April	65%	40%	30%
May	90%	80%	75%
June	95%	75%	65%
July	100%	80%	55%
August	70%	40%	15%
September	20%	5%	5%
October	25%	10%	10%
November	70%	50%	25%
December	80%	65%	50%


WALES ESTATE
Monthly Precipitation Totals (mm)
1995 - 2014



Summary of wet months WALES ESTATE 1995 -2014

Month	% Incidence > 100 mm	% Incidence > 150 mm	% incidence > 200 mm
January	70%	60%	40%
February	45%	40%	25%
March	30%	15%	10%
April	65%	55%	40%
May	95%	90%	80%
June	100%	95%	90%
July	95%	90%	75%
August	75%	65%	15%
September	55%	25%	5%
October	4%	20%	15%
November	75%	50%	45%
December	80%	65%	50%


UITVLUGT ESTATE Monthly Precipitation Totals (mm) 1995 - 2014



Summary of wet months UITVLUGT ESTATE 1995 -2014

Month	% Incidence > 100 mm	% Incidence > 150 mm	% incidence > 200 mm
January	80%	65%	55%
February	50%	40%	30%
March	50%	25%	15%
April	70%	60%	45%
May	95%	95%	85%
June	100%	95%	80%
July	100%	100%	90%
August	80%	45%	40%
September	40%	15%	5%
October	50%	30%	10%
November	70%	55%	30%
December	85%	75%	75%


BERBICE ESTATES Monthly Precipitation Totals (mm) 1995 - 2014



Summary of wet months BERBICE ESTATES 1995 -2014

Month	% Incidence > 100 mm	% Incidence > 150 mm	% incidence > 200 mm
January	70%	55%	35%
February	40%	35%	20%
March	20%	10%	5%
April	60%	60%	25%
May	90%	85%	75%
June	100%	85%	70%
July	100%	80%	50%
August	70%	50%	15%
September	15%	10%	0%
October	5%	5%	5%
November	25%	5%	0%
December	80%	50%	25%

DEMERARA ESTATES Monthly Precipitation Totals (mm) 1995 - 2014



Summary of wet months DEMERARA ESTATES 1995 -2014

Month	% Incidence > 100 mm	% Incidence > 150 mm	% incidence > 200 mm
January	70%	60%	50%
February	45%	30%	20%
March	35%	10%	10%
April	70%	55%	35%
May	95%	90%	85%
June	100%	95%	85%
July	100%	95%	85%
August	80%	50%	25%
September	25%	5%	5%
October	30%	15%	5%
November	70%	50%	25%
December	80%	70%	65%

**GUYSUCO AGRICULTURE RESEARCH CENTRE
RAINFALL (IN MM)**

BERBICE

#	YEAR	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEPT	OCT	NOV	DEC	TOTAL
35	1990	373.2	123.1	216.6	357.0	231.1	249.6	224.9	215.3	34.9	33.6	109.5	339.4	2508.2
36	1991	104.0	33.4	71.8	226.7	100.0	306.1	279.5	235.2	138.5	58.9	52.8	181.9	1788.8
37	1992	62.7	118.5	42.8	48.4	216.2	147.5	197.6	145.2	21.2	40.2	52.5	88.7	1181.5
38	1993	189.2	101.5	209.8	62.6	136.0	241.1	102.6	133.7	105.7	76.1	233.9	132.0	1724.1
39	1994	110.0	52.6	184.5	79.0	217.8	184.5	253.6	117.4	58.9	160.2	93.9	143.8	1656.1
40	1995	54.2	18.9	76.4	37.4	282.9	377.3	202.6	135.9	13.9	32.9	79.5	164.5	1476.1
41	1996	279.3	271.9	50.9	56.0	256.2	427.4	359.0	127.3	37.6	13.2	73.4	62.9	2014.9
42	1997	240.2	196.5	49.4	59.8	188.7	120.6	106.3	60.0	5.3	10.5	10.5	67.1	1114.8
43	1998	43.8	4.6	41.0	171.8	200.4	286.2	146.1	185.5	71.8	48.3	135.1	163.8	1498.1
44	1999	149.9	88.6	92.7	184.6	87.0	238.4	231.3	173.7	29.5	80.7	17.9	312.8	1687.0
45	2000	441.0	123.8	95.8	151.5	369.8	330.8	187.0	162.3	47.8	18.5	103.8	111.8	2143.5
46	2001	42.8	19.3	34.8	62.3	196.2	303.5	183.5	89.8	182.4	35.4	54.2	72.8	1276.7
47	2002	170.1	50.9	96.3	202.4	273.4	294.2	107.2	84.3	36.7	39.6	74.7	123.6	1553.2
48	2003	28.1	43.7	27.6	44.1	286.1	200.4	242.3	98.0	73.5	51.0	66.7	137.1	1298.4
49	2004	169.4	43.4	84.4	220.5	343.1	185.9	235.6	105.6	154.5	58.2	14.9	155.5	1771.0
50	2005	368.6	175.0	38.8	202.9	252.7	140.8	195.0	186.1	77.5	27.8	129.8	400.9	2195.8
51	2006	415.4	92.1	76.6	25.3	352.9	311.0	135.2	68.5	67.5	79.9	96.1	124.4	1844.6
52	2007	119.5	62.5	158.7	226.4	343.1	282.0	261.8	237.5	102.3	70.2	48.9	402.7	2315.5
53	2008	181.0	421.8	118.4	197.4	278.2	259.8	170.4	135.2	78.3	87.9	30.4	661.5	2620.2
54	2009	224.9	79.4	123.2	166.6	52.3	161.8	195.5	45.9	15.4	85.2	19.7	63.9	1233.7
55	2010	61.8	68.0	51.7	167.2	265.9	149.7	271.6	249.5	60.5	69.6	115.3	191.7	1722.4
56	2011	113.0	260.0	416.9	58.3	241.9	206.9	187.9	157.7	25.8	232.3	50.3	144.2	2095.0
57	2012	363.6	292.5	41.4	253.3	418.6	126.3	296.6	182.7	9.5	13.0	166.1	190.8	2354.2
58	2013	38.5	167.4	32.2	171.0	397.0	223.4	274.3	186.1	46.2	65.7	98.4	367.2	2067.2
59	2014	112.0	97.1	47.2	70.2	144.7	231.2	244.1	233.3	23.9	47.1	86.7	131.2	1468.6
	mean	180.8	128.9	87.7	136.4	261.5	242.9	211.6	145.2	58.0	58.3	73.6	202.5	
	max	441.0	421.8	416.9	253.3	418.6	427.4	359.0	249.5	182.4	232.3	166.1	661.5	
	min	28.1	4.6	27.6	25.3	52.3	120.6	106.3	45.9	5.3	10.5	10.5	62.9	
60	2015													
	59 YEAR													
	MEAN	75.5	51.0	42.0	59.4	103.9	101.5	89.7	63.6	25.7	26.0	34.1	83.7	756.1

**GUYSUCO AGRICULTURE RESEARCH CENTRE
RAINFALL (IN MM)**

DEMERARA

#	YEAR	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEPT	OCT	NOV	DEC	TOTAL
35	1990	240.8	119.0	206.0	117.5	414.2	312.9	375.3	331.6	211.8	139.1	222.3	542.9	3233.3
36	1991	199.9	49.3	10.1	44.4	337.8	236.9	248.2	66.6	24.9	91.5	95.5	246.8	1651.6
37	1992	62.2	121.4	101.3	416.6	163.5	340.8	91.8	138.3	25.9	85.3	13.5	83.4	1644.0
38	1993	121.1	79.3	34.4	75.1	88.8	490.0	291.5	215.8	54.7	98.9	212.3	278.7	2040.5
39	1994	139.8	52.9	40.6	188.2	317.3	299.7	271.9	226.5	22.2	76.1	131.2	247.0	2013.1
40	1995	109.1	53.6	19.3	5.5	156.8	345.8	220.7	192.3	85.9	48.0	134.8	132.1	1503.9
41	1996	98.7	31.4	58.2	69.6	275.3	348.2	259.0	201.6	38.9	26.8	177.8	98.1	1683.6
42	1997	449.0	154.9	86.1	103.1	359.1	290.3	303.4	104.6	21.6	15.3	81.8	140.5	2109.7
43	1998	42.1	21.1	28.6	96.6	103.3	428.5	292.7	196.6	52.8	77.8	97.0	618.0	2055.0
44	1999	205.9	69.8	47.8	24.6	553.5	313.9	195.2	98.1	30.0	66.2	86.0	87.6	1778.5
45	2000	57.9	12.3	87.4	59.5	204.7	325.4	343.4	156.9	137.3	71.4	79.4	385.3	1920.8
46	2001	270.2	45.3	119.3	194.3	607.3	431.4	440.2	199.0	123.5	25.3	258.3	247.0	2960.8
47	2002	161.9	248.2	166.5	251.7	230.6	449.3	267.7	68.7	125.8	88.6	274.4	164.5	2498.0
48	2003	282.3	135.8	23.2	142.3	459.9	214.8	215.2	224.4	41.0	70.2	62.4	200.6	2071.8
49	2004	378.7	98.6	91.4	239.9	292.0	283.0	436.8	268.8	94.5	73.3	331.1	203.4	2791.4
50	2005	172.9	75.8	96.9	141.0	417.4	512.2	320.4	344.7	109.8	140.9	275.1	397.1	3004.1
51	2006	303.7	140.6	202.9	430.5	484.2	316.8	193.7	131.8	98.5	155.2	326.0	96.7	2880.5
52	2007	56.3	17.3	25.7	103.1	167.0	359.4	274.2	273.9	320.3	351.0	294.9	821.0	3064.0
53	2008	337.9	110.4	182.3	114.9	68.8	391.3	343.2	196.9	167.7	152.7	135.8	210.9	2412.6
54	2009	271.3	66.0	64.1	126.3	362.6	377.8	382.1	224.5	113.2	123.8	229.0	488.3	2828.9
55	2010	506.1	413.1	221.1	208.9	406.6	506.7	190.3	86.0	39.7	4.6	201.1	228.4	3012.5
56	2011	68.4	38.4	38.1	168.5	330.4	289.1	312.6	97.7	122.8	89.2	114.5	148.7	1818.3
57	2012	179.0	28.5	19.6	79.8	456.8	307.9	288.3	365.1	89.1	94.3	114.5	196.5	2219.1
58	2013	122.1	16.8	243.7	190.9	379.9	319.1	317.3	185.5	89.5	94.7	89.7	255.3	2304.3
59	2014	82.1	13.0	156.6	130.9	244.8	309.7	291.1	130.9	63.4	155.6	358.6	267.7	2204.2
	mean	207.8	89.5	98.9	144.1	328.1	356.0	294.4	187.4	98.3	96.2	186.1	269.4	
	max	506.1	413.1	243.7	430.5	607.3	512.2	440.2	365.1	320.3	351.0	358.6	821.0	
	min	42.1	12.3	19.3	5.5	68.8	214.8	190.3	68.7	21.6	4.6	62.4	87.6	
60	2015													
59 YEAR	MEAN	83.4	1.1	28.9	286.4	50.3	67.3	29.3	15.3	7.9	18.5	69.4	43.6	160.9

**GUYSUO AGRICULTURE RESEARCH CENTRE
RAINFALL (IN MM)**

INDUSTRY

#	YEAR	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEPT	OCT	NOV	DEC	TOTAL
36	1990	272.0	110.5	155.4	96.7	360.9	284.0	285.2	325.9	183.8	116.2	203.9	472.6	2867.1
36	1991	187.1	58.6	30.3	36.4	277.0	248.1	188.1	60.6	20.7	101.3	70.5	204.2	1482.6
37	1992	94.3	115.9	113.8	419.4	185.5	328.0	114.3	153.6	16.9	63.1	12.3	92.7	1709.8
38	1993	122.7	88.0	60.6	96.2	88.8	404.3	345.1	172.3	37.0	100.9	203.0	194.5	1913.3
39	1994	140.5	79.8	37.2	211.6	309.7	245.4	321.6	206.0	15.1	90.1	119.4	225.2	2001.6
40	1995	80.5	48.1	16.2	6.5	163.0	338.4	316.1	189.5	62.9	51.0	111.9	138.9	1522.9
41	1996	97.2	45.5	99.8	89.6	300.4	370.1	268.4	212.9	40.4	28.4	170.7	130.5	1853.9
42	1997	322.2	191.4	97.4	94.3	333.5	258.3	277.9	74.2	17.4	19.4	84.3	131.3	1901.5
43	1998	36.5	25.7	33.7	68.2	128.8	398.7	266.5	198.5	39.9	72.6	83.3	522.3	1874.6
44	1999	204.9	54.9	65.0	22.8	476.0	279.8	157.2	131.1	49.1	60.6	71.1	77.1	1649.4
45	2000	81.4	38.2	78.7	74.1	173.9	307.4	302.1	179.1	90.1	70.1	76.0	310.4	1781.5
46	2001	284.8	54.0	112.5	220.4	437.4	351.2	352.2	206.7	87.0	25.1	173.2	243.7	2548.3
47	2002	236.2	221.3	149.5	216.8	222.3	366.4	228.8	63.8	99.0	59.0	36.7	172.5	2164.0
48	2003	268.4	105.3	38.9	195.8	415.2	234.3	193.2	227.1	49.4	82.5	178.8	188.6	2019.2
49	2004	347.4	122.5	76.4	203.7	302.9	260.8	377.1	242.0	80.7	64.5	279.8	188.6	2546.5
50	2005	175.6	87.5	112.4	164.1	358.9	425.0	248.0	347.9	88.8	127.3	178.8	273.3	2587.5
51	2006	266.6	115.0	203.5	420.0	408.0	292.7	203.8	122.8	80.3	99.7	209.5	85.6	2507.4
52	2007	54.8	14.8	38.7	73.4	222.5	304.1	251.2	254.6	309.8	219.8	189.8	617.6	2550.9
53	2008	306.0	107.3	146.2	121.6	64.1	366.5	296.6	146.3	162.0	124.3	94.5	189.8	2125.2
54	2009	285.5	110.2	51.6	91.6	265.4	384.3	344.9	209.5	95.6	80.8	188.8	418.3	2526.4
55	2010	467.3	351.0	216.2	197.2	364.0	358.2	153.8	62.0	28.4	6.8	131.9	235.1	2571.9
56	2011	64.2	86.1	68.8	123.8	248.0	249.0	266.7	84.3	94.1	63.6	72.3	173.7	1594.5
57	2012	159.2	34.7	17.3	84.5	316.5	263.1	229.9	333.8	77.1	82.9	91.3	149.5	1839.8
58	2013	107.1	21.3	256.9	225.1	339.8	295.8	315.8	144.1	84.5	78.0	77.4	240.9	2186.5
59	2014	75.6	11.1	126.8	149.8	209.4	234.8	265.8	105.6	52.5	110.1	251.6	221.5	1814.6
	mean	196.1	92.3	100.3	142.1	287.5	316.9	265.8	176.8	84.4	76.3	138.1	231.6	
	max	467.3	351.0	256.9	420.0	476.0	425.0	377.1	347.9	309.8	219.8	279.8	617.6	
	min	36.5	11.1	16.2	6.5	64.1	234.3	153.8	62.0	17.4	6.8	36.7	77.1	
60	2015													
59 YEAR	MEAN	80.3	1.1	31.8	332.5	55.0	52.4	31.4	19.0	7.4	18.9	64.2	52.9	207.2

Appendix 6

Tillage, Planting and Machine Utilization

Hectares under Cultivation as At June 30th 2015							
Estate	tilled	Non - tilled	TAB	Total Out (In Cane)	total ha	% Out Of Cane	
SWR	251.3	668.8	0	920.1	7982.5	8902.6	10%
AN	134.2	185.5	0	319.7	9296.3	9616	3%
RH	108.9	84.2	0	193.1	6495.4	6688.5	3%
BCF	5.3	19.4	0	24.7	5783.4	5808.1	0%
Ber	499.7	957.9	0	1457.6	29557.6	31015.2	5%
EHP	179.3	196.6	0	375.9	4317.2	4693.1	8%
LBI	72.3	172.3	0	244.6	2744.2	2988.8	8%
GV	109	421	0	530	2826.1	3356.1	16%
ICBu	97.4	533.9	44.7	676	3958.2	4634.2	15%
Dem	458	1323.8	44.7	1826.5	13845.7	15672.2	12%
Ind	957.7	2281.7	44.7	3284.1	43403.3	46687.4	7%

2NC4:I43D CROP 2014 PLANT CANES YILED : Flood Falow v/s Plough and Plant

Estates	Flood Falow			Plough and Plant			
	Fields	HA	TCH	Fields	HA	TCH	
Skeldon	0	0	0	80/119 - 121	8.7	89.77	
				80/41	2.6	111.15	
				BK12/19 - 21	15.9	44.59	
				BK15/1 - 24	145	41.15	
				BK16/1 - 25	157.7	52.06	
				BK9/1 - 9, 23	72.9	47.65	
				MRP2 3/1	8	75.88	
				MRP3A 3/7 - 8	9.8	26.22	
				MRP4A 4/1 - 7 + 10 - 11	53.4	59.25	
				NSG/9 - 23	68.6	62.16	
		TOTAL	0	0	TOTAL	542.6	51.09
	Albion	Hamp 61	4.67	76.08	TainOG 42-31	78.9	89.50
Hamp 62		5.3	76.28	TainLDE 1-8	33.2	84.42	
Hamp 63		5.3	75.74	ResOG 8-9	8.7	89.61	
Hamp 64		5.3	77.02	AnkEW 31-47	55.1	70.11	
Hamp 65		5.3	76.18	PME 43-50	50.6	94.74	
Hamp 66		5.3	77.66	R/Hall 1A-4	23.4	90.01	
Hamp 67		5.3	75.85	Hamp 75-88	67.6	83.93	
Hamp 68		5.23	74.54	Belvd 75-77	18.7	96.97	
Hamp 69		5.23	76.24	Hamp A1-F	40.3	81.30	
Hamp 70		5.23	78.67	Belvd A1-2	12	85.34	
Hamp 71		4.93	77.34	ELC 1	3.5	92.90	
Hamp 72		4.93	79.75	ELE 1-19	115.4	81.14	
Hamp 73		4.93	75.31	Long John 15-20	9.5	88.78	
Hamp 74		4.93	78.69				
RH (AN) 8		8.9	82.7				
RH (AN) 7		8.1	99.15				
RH (AN) 6		8	83.87				
RH (AN) 5		7.9	88.62				
Nigg 38		5.4	80.43				
Nigg 37		5.31	86.06				
Nigg 36		4.76	108.14				
Nigg 35		4.93	114.46				
Nigg 34		4.93	99.61				
Nigg 33		3.31	83.82				
Nigg 32	5.27	95.25					
	Total:	138.69	84.15	TOTAL	516.9	84.59	
	FF 23	2.6	79.64	Rel 30-37	28.6	59.32	
	FF 25	3.5	70.61	Ent A 10-13	18.1	76.45	

Rose Hall	FF 27	3.6	74	Maz G 1-21	81.6	65
	FF 29	2.5	68.68	MazH 19	4.1	73.34
	FF 31	2.5	74.36	Owg W 12, 14 pt- 17 pt, 18	23.7	70.86
	FF 33	3.9	72.72	Maz C 6, 12-16	33.9	67.44
	FF 35	3.4	93.43	EntA 31bl- 37	25.8	79.97
				L26B 6- 20	21	68.84
				Owg W 45-53	24.7	77.6
	Total:	22	76.34	Total:	261.5	69.12
Blairmont	0	0	0	BHP 9-19	83	82.15
				RS 1-9	46.9	101.90
				RS 11-14C	22.3	98.95
				RS 16-17B	9.9	107.87
				BK 31A-39	43.2	73.24
				JWCB 1-11	37.5	86.05
				OL 17-22	29.6	109.06
				BHL 2-10	52.8	90.30
				RP 21-29	70.4	80.45
				ML 7-8	11.7	91.38
				ML 12A	4.2	85.95
Total:	0	0	Total:	411.5	88.34	
EHP		0	0	ENTW 32-38	23.2	65.04
				ENTW 40-58	45.6	66.18
				NPE 59-65	22.4	80.71
	Total:	0	0	Total:	91.2	69.46

Actual Tillage & Planting 2001 - 2015

Year	Estate	First Crop			Second Crop			Year		
		Tillage			Tillage			Tillage		
		Budget	Actual	Variance	Budget	Actual	Variance	Budget	Actual	Variance
2001	SWR		867.2			698.4		0	1565.6	
	AN		1202.6			1112.8		0	2315.4	
	RH		801.8			1296		0	2097.8	
	BCF		883.6			668.3		0	1551.9	
	BER		3755.2			3775.5		0	7530.7	
	EHP		510.6			558.9		0	1069.5	
	LBI		531.4			761.5		0	1292.9	
	GV		466.7			409.7		0	876.4	
	ICBU		576.7			656.1		0	1232.8	
	DEM		2085.4			2386.2		0	4471.6	
	IND		5840.6			6161.7		0	12002.3	
2002	SWR		330.8			857.1			1187.9	
	AN		486.6			1244.3			1730.9	
	RH		320.6			1037.3			1357.9	
	BCF		171.1			846.3			1017.4	
	BER		1309.1			3985			5294.1	
	EHP		272.7			665			937.7	
	LBI		307.9			889			1196.9	
	GV		268			505.1			773.1	
	ICBU		395.1			680.4			1075.5	
	DEM		1243.7			2739.5			3983.2	
	IND		2552.8			6724.5			9277.3	
2003	SWR		740.7			451.6			1192.3	
	AN		728.3			769.5			1497.8	
	RH		578.8			759.9			1338.7	
	BCF		673.9			682.1			1356	
	BER		2721.7			2663.1			5384.8	
	EHP		513.3			617.5			1130.8	
	LBI		615.9			602.5			1218.4	
	GV		402.2			242.5			644.7	
	ICBU		552.8			393			945.8	
	DEM		2084.2			1855.5			3939.7	
	IND		4805.9			4518.6			9324.5	
2004	SWR		230.1			576.7			806.8	
	AN		292.8			1105.5			1398.3	
	RH		352.6			554.2			906.8	
	BCF		330.4			686.2			1016.6	
	BER		1205.9			2922.6			4128.5	
	EHP		472			641.2			1113.2	
	LBI		312.5			904.3			1216.8	
	GV		192.6			497.5			690.1	
	ICBU		324.5			797.5			1122	
	DEM		1301.6			2840.5			4142.1	
	IND		2507.5			5763.1			8270.6	
2005	SWR		69.4			622.4			691.8	
	AN		287.8			1482.7			1770.5	
	RH		109.7			882.3			992	
	BCF		129.1			750.1			879.2	
	BER		596			3737.5			4333.5	
	EHP		244.9			700.8			945.7	
	LBI		121.6			742.5			864.1	
	GV		187.3			315.3			502.6	
	ICBU		267.3			724.1			991.4	
	DEM		821.1			2482.7			3303.8	
	IND		1417.1			6220.2			7637.3	
2006	SWR		422.1			643.8			1065.9	
	AN		646.6			1305.2			1951.8	
	RH		477.7			1157.4			1635.1	
	BCF		492.2			459.4			951.6	
	BER		2038.6			3665.8			5604.4	
	EHP		381.7			365.8			747.5	
	LBI		326.6			255.2			581.8	
	GV		354.2			394.2			748.4	
	ICBU		478.9			165.2			644.1	
	DEM		1541.4			1180.4			2721.8	
	IND		3580			4746.2			8326.2	

Actual Tillage & Planting 2001 - 2015

Year	Estate	First Crop			Second Crop			Year		
		Tillage			Tillage			Tillage		
2007	SWR		0			433.7			433.7	
	AN		395.7			661.8			1057.5	
	RH		249.9			703.8			953.7	
	BCF		95.1			281.6			376.7	
	BER		740.7			2080.9			2821.6	
	EHP		455.5			548.2			1003.7	
	LBI		471.1			499.1			970.2	
	GV		352.4			574.6			927	
	ICBU		450.6			473.3			923.9	
	DEM		1729.6			2095.2			3824.8	
IND		2470.3			4176.1			6646.4		
2008	SWR		26.8			184.7			211.5	
	AN		394.4			1160.1			1554.5	
	RH		275.4			697.4			972.8	
	BCF		127.4			606.2			733.6	
	BER		824			2648.4			3472.4	
	EHP		304			544.7			848.7	
	LBI		231.3			462.4			693.7	
	GV		254.5			358.7			613.2	
	ICBU		234.2			714.7			948.9	
	DEM		1024			2080.5			3104.5	
IND		1848			4728.9			6576.9		
2009	SWR	1737	214.1	-1522.9	2397	2127.9	-269.1	4134	2342	-1792
	AN	734	294.8	-439.2	1102	1385.1	283.1	1836	1679.9	-156.1
	RH	554.1	152.9	-401.2	1050	909.8	-140.2	1604.1	1062.7	-541.4
	BCF	619.9	154.1	-465.8	736.3	917.8	181.5	1356.2	1071.9	-284.3
	BER	3645	815.9	-2829.1	5285.3	5340.6	55.3	8930.3	6156.5	-2773.8
	EHP	350.2	147.6	-202.6	476	739.7	263.7	826.2	887.3	61.1
	LBI	455.7	129.5	-326.2	657	623.1	-33.9	1112.7	752.6	-360.1
	GV	351.4	203.3	-148.1	341.9	584.8	242.9	693.3	788.1	94.8
	ICBU	400	341.3	-58.7	700	483.6	-216.4	1100	824.9	-275.1
	DEM	1557.3	821.7	-735.6	2174.9	2431.2	256.3	3732.2	3252.9	-479.3
IND	5202.3	1637.6	-3564.7	7460.2	7771.8	311.6	12662.5	9409.4	-3253.1	
2010	SWR	1998	1312.4	-685.6	2901.1	1091.3	-1809.8	4899.1	2403.7	-2495.4
	AN	928	884.9	-43.1	1407.2	730.2	-677	2335.2	1615.1	-720.1
	RH	668	646.6	-21.4	1004	391.5	-612.5	1672	1038.1	-633.9
	BCF	614	716.7	102.7	838	541.4	-296.6	1452	1258.1	-193.9
	BER	4208	3560.6	-647.4	6150.3	2754.4	-3395.9	10358.3	6315	-4043.3
	EHP	461.3	233.5	-227.8	956.1	341.4	-614.7	1417.4	574.9	-842.5
	LBI	378	155	-223	861.6	218.1	-643.5	1239.6	373.1	-866.5
	GV	352	385.5	33.5	487	167.4	-319.6	839	552.9	-286.1
	ICBU	554	503.3	-50.7	831	159.2	-671.8	1385	662.5	-722.5
	DEM	1745.3	1277.3	-468	3135.7	886.1	-2249.6	4881	2163.4	-2717.6
IND	5953.3	4837.9	-1115.4	9286	3640.5	-5645.5	15239.3	8478.4	-6760.9	
2011	SWR	2370.5	280.6	-2089.9	2105	679.9	-1425.1	4475.5	960.5	-3515
	AN	953.8	914.1	-39.7	1455.2	1051	-404.2	2409	1965.1	-443.9
	RH	670	470.8	-199.2	1008	785.9	-222.1	1678	1256.7	-421.3
	BCF	612	320.7	-291.3	840	676.7	-163.3	1452	997.4	-454.6
	BER	4606.3	1986.2	-2620.1	5408.2	3193.5	-2214.7	10014.5	5179.7	-4834.8
	EHP	663.8	291.4	-372.4	499.8	292.6	-207.2	1163.6	584	-579.6
	LBI	380	196.5	-183.5	584.5	159.3	-425.2	964.5	355.8	-608.7
	GV	353	299.5	-53.5	487	201.4	-285.6	840	500.9	-339.1
	ICBU	568	475.3	-92.7	798.4	554.4	-244	1366.4	1029.7	-336.7
	DEM	1964.8	1262.7	-702.1	2369.7	1207.7	-1162	4334.5	2470.4	-1864.1
IND	6571.1	3248.9	-3322.2	7777.9	4401.2	-3376.7	14349	7650.1	-6698.9	
2012	SWR	1755.3	126.4	-1628.9	2684.3	1238.4	-1445.9	4439.6	1364.8	-3074.8
	AN	941	196.9	-744.1	1592	1279.7	-312.3	2533	1476.6	-1056.4
	RH	670	126.2	-543.8	1002	721.9	-280.1	1672	848.1	-823.9
	BCF	612	62	-550	840	636.8	-203.2	1452	698.8	-753.2
	BER	3978.3	511.5	-3466.8	6118.3	3876.8	-2241.5	10096.6	4388.3	-5708.3
	EHP	516.2	132.9	-383.3	698.9	598.7	-100.2	1215.1	731.6	-483.5
	LBI	297	95.4	-201.6	446	326	-120	743	421.4	-321.6
	GV	326	252.4	-73.6	513	431.8	-81.2	839	684.2	-154.8
	ICBU	601	195.5	-405.5	900	364.7	-535.3	1501	560.2	-940.8
	DEM	1740.2	676.2	-1064	2557.9	1721.2	-836.7	4298.1	2397.4	-1900.7
IND	5718.5	1187.7	-4530.8	8676.2	5598	-3078.2	14394.7	6785.7	-7609	

Actual Tillage & Planting 2001 - 2015

Year	Estate	First Crop			Second Crop			Year		
		Tillage			Tillage			Tillage		
2013	SWR	1691.5	306.7	-1384.8	2052.5	583.7	-1468.8	3744	890.4	-2853.6
	AN	934	607.5	-326.5	1470	867.5	-602.5	2404	1475	-929
	RH	669	396.3	-272.7	1003	543	-460	1672	939.3	-732.7
	BCF	614	404	-210	838	460.5	-377.5	1452	864.5	-587.5
	BER	3908.5	1714.5	-2194	5363.5	2454.7	-2908.8	9272	4169.2	-5102.8
	EHP	515	248.8	-266.2	662	148	-514	1177	396.8	-780.2
	LBI	300	266.4	-33.6	445	77.5	-367.5	745	343.9	-401.1
	GV	336	241.7	-94.3	503	161.8	-341.2	839	403.5	-435.5
	ICBU	601	424.1	-176.9	900	302.3	-597.7	1501	726.4	-774.6
	DEM	1752	1181	-571	2510	689.6	-1820.4	4262	1870.6	-2391.4
IND	5660.5	2895.5	-2765	7873.5	3144.3	-4729.2	13534	6039.8	-7494.2	
2014	SWR	745.8	415.4	-330.4	1522.4	855.4	-667	2268.2	1270.8	-997.4
	AN	781	516.4	-264.6	1144	1113	-31	1925	1629.4	-295.6
	RH	540	471.8	-68.2	798	801.5	3.5	1338	1273.3	-64.7
	BCF	456	489.7	33.7	706	628	-78	1162	1117.7	-44.3
	BER	2522.8	1893.3	-629.5	4170.4	3397.9	-772.5	6693.2	5291.2	-1402
	EHP	360	289.1	-70.9	540	335	-205	900	624.1	-275.9
	LBI	240	325	85	360	299.8	-60.2	600	624.8	24.8
	GV	241.8	299.4	57.6	524.4	219.8	-304.6	766.2	519.2	-247
	ICBU	820.6	762	-58.6	1014.7	429.5	-585.2	1835.3	1191.5	-643.8
	DEM	1662.4	1675.5	13.1	2439.1	1284.1	-1155	4101.5	2959.6	-1141.9
IND	4185.2	3568.8	-616.4	6609.5	4682	-1927.5	10794.7	8250.8	-2543.9	
2015	SWR	1212	537.3	-674.7			0	1212	537.3	-674.7
	AN	770	333.2	-436.8			0	770	333.2	-436.8
	RH	564	573.8	9.8			0	564	573.8	9.8
	BCF	466	364.4	-101.6			0	466	364.4	-101.6
	BER	3012	1808.7	-1203.3	0	0	0	3012	1808.7	-1203.3
	EHP	360	210.3	-149.7			0	360	210.3	-149.7
	LBI	240	77.1	-162.9			0	240	77.1	-162.9
	GV	228	311.1	83.1			0	228	311.1	83.1
	ICBU	500	310.3	-189.7			0	500	310.3	-189.7
	DEM	1328	908.8	-419.2	0	0	0	1328	908.8	-419.2
IND	4340	2717.5	-1622.5	0	0	0	4340	2717.5	-1622.5	

